

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	40-M	WINNEBAGO	165	27
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

20100110	TREE REMOVAL (6 TO15 UNITS DIAMETER)	UNIT	LOCATION	OFFSET	REMARKS
		11.0	IL 2	340+39.97	55.0
		10.0	LT	342+53.17	77.4
		7.0	RT	342+56.38	79.7
		15.0	RT	342+76.45	86.0
		8.0	RT	342+80.36	86.7
		13.0	RT	342+98.74	72.0
		13.0	RT	343+16.31	107.4
		9.0	RT	343+26.73	104.5
		13.0	RT	343+51.40	66.4
		15.0	RT	343+64.74	75.8
		13.0	RT	343+71.54	87.5
		15.0	RT	345+68.38	39.0
		7.0	RT	346+43.66	41.0
		8.0	RT	346+54.12	45.4
		15.0	RT	347+34.44	33.0
		10.0	LT	347+34.58	46.4
		9.0	RT	350+39.15	34.5
		15.0	CER+41	11+94.70	45.7
		12.0	LT	12+80.50	21.0
		12.0	RT		
TOTAL		218.0			

20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	LOCATION	OFFSET	REMARKS
		32.0	IL 2	334+48.24	40.6
		18.0	RT	344+08.60	86.3
		22.0	RT	344+12.12	87.0
		20.0	RT	344+06.40	39.5
		24.0	RT	344+20.15	65.2
		18.0	RT	344+52.30	38.2
		17.0	RT	344+73.50	38.5
		21.0	LT	344+98.95	69.0
		36.0	RT	345+17.00	39.0
		21.0	RT	345+48.34	38.5
		19.0	RT	345+90.21	38.5
		22.0	RT	346+26.24	37.2
		24.0	RT	347+68.65	41.6
		26.0	RT	347+88.82	32.5
		16.0	RT	348+56.36	40.0
		17.0	RT	350+29.07	33.7
		25.0	CER+41	11+98.10	52.2
		18.0	LT	12+04.50	63.0
		24.0	LT	12+37.70	43.3
		33.0	LT	12+80.76	14.5
TOTAL		453.0			

20100500	TREE REMOVAL, ACRES	ACRES	LOCATION	REMARKS
		0.24	IL 2	
		0.10	LEFT	333+10.00 TO 337+63.0
		0.13	RIGHT	332+66.71 TO 334+09.0
		0.20	RIGHT	334+43.00 TO 336+52.0
		0.23	RIGHT	336+05.00 TO 338+64.0
TOTAL		0.90	RIGHT	338+64.00 TO 340+50.0

20200200	ROCK EXCAVATION	CU.YD.	LOCATION	REMARKS
		75.00	BOX CULVERT EXTENSION	
TOTAL		75.00		

25000210	SEEDING CLASS 2A	ACRE	LOCATION	REMARKS
		0.98	IL 2	
		1.08	LT	332+66.71 TO 347+50.00
			RT	332+66.71 TO 343+75.00
		0.10	CLIFTON AVE	
		0.09	LT	30+50.00 TO 32+00.00
			RT	30+50.00 TO 32+00.00
		0.06	CER+41	
		0.17	LT	11+00.00 TO 13+00.00
			RT	11+00.00 TO 13+00.00
TOTAL		2.48		

25000400	NITROGEN FERTILIZER NUTRIENT	POUNDS	LOCATION	REMARKS
		88.20	IL 2	
		97.20	LT	332+66.71 TO 347+50.00
			RT	332+66.71 TO 343+75.00
		9.00	CLIFTON AVE	
		8.10	LT	30+50.00 TO 32+00.00
			RT	30+50.00 TO 32+00.00
		5.31	CER+41	
		15.30	LT	11+00.00 TO 13+00.00
			RT	11+00.00 TO 13+00.00
TOTAL		223.11		

25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUNDS	LOCATION	REMARKS
		88.20	IL 2	
		97.20	LT	332+66.71 TO 347+50.00
			RT	332+66.71 TO 343+75.00
		9.00	CLIFTON AVE	
		8.10	LT	30+50.00 TO 32+00.00
			RT	30+50.00 TO 32+00.00
		5.31	CER+41	
		15.30	LT	11+00.00 TO 13+00.00
			RT	11+00.00 TO 13+00.00
TOTAL		223.11		

25000600	POTASSIUM FERTILIZER NUTRIENT	POUNDS	LOCATION	REMARKS
		88.20	IL 2	
		97.20	LT	332+66.71 TO 347+50.00
			RT	332+66.71 TO 343+75.00
		9.00	CLIFTON AVE	
		8.10	LT	30+50.00 TO 32+00.00
			RT	30+50.00 TO 32+00.00
		5.31	CER+41	
		15.30	LT	11+00.00 TO 13+00.00
			RT	11+00.00 TO 13+00.00
TOTAL		223.11		

25100115	MULCH, METHOD 2	ACRE	LOCATION	REMARKS
		0.98	IL 2	
		1.08	LT	332+66.71 TO 347+50.00
			RT	332+66.71 TO 343+75.00
		0.10	CLIFTON AVE	
		0.09	LT	30+50.00 TO 32+00.00
			RT	30+50.00 TO 32+00.00
		0.06	CER+41	
		0.17	LT	11+00.00 TO 13+00.00
			RT	11+00.00 TO 13+00.00
TOTAL		2.48		

25100630	EROSION CONTROL BLANKET	SQ.YD	LOCATION	REMARKS
		2414.0	IL 2	
		3705.0	LT	332+66.71 TO 340+50.00
			RT	332+66.71 TO 340+50.00
		342.0	CER+41	
		1153.2	LT	11+00.00 TO 13+00.00
			RT	11+00.00 TO 13+00.00
TOTAL		7,614.2		

25200100	SODDING	SQ.YD	LOCATION	REMARKS
		586.0	IL 2	
		1248.7	LT	347+50.00 TO 350+50.00
			RT	344+00.00 TO 350+50.00
TOTAL		1,834.7		

20800150	TRENCH BACKFILL	CU.YD	REMARKS
		1285	WATER MAIN
TOTAL			

28000300	TEMPORARY DITCH CHECKS	EACH	LOCATION	REMARKS
		16.0	IL 2	
		4.0	LT	333+50.00 TO 335+25.00 10' CTS
		5.0	LT	336+25.00 TO 338+00.00 20' CTS
			RT	338+00.00 TO 338+75.00 33' CTS
		1.0	CER+41	
			LT	13+00.00
TOTAL		25.0		CONCRETE OUTLET

28000400	PERIMETER EROSION BARRIER	FEET	LOCATION	REMARKS
		121.0	IL 2	
		83.0	RT	332+66.70 TO 333+75.00 1 RUN
		1040.0	LT	332+66.70 TO 333+50.00 1 RUN
		215.0	RT	333+75.00 TO 338+75.00 2 RUNS
			LT	335+25.00 TO 336+25.00 2 RUNS
		262.0	CLIFTON AVE	
			RT	30+50.00 TO 32+38.00 1 RUN
			CER+41	
		224.0	RT	11+00.00 TO 13+00.00 1 RUN
TOTAL		1,945.0		

PLOT DATE = Fri, May 26 13:44:41 2006
 FILE NAME = c:\pvc\mca\20050228\38500228.dgn
 PLOT SCALE = 50.0000 7 IN.
 USER NAME = jordanhd