

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	40-M	WINNEBAGO	165	31
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

78100100	RAISED REFLECTIVE PAVEMENT MARKERS	LOCATION	REMARKS
	EACH	IL 2	
	13.00	NB	332+66.71 TO 345+05.40 ONE-WAY CRYSTAL
	8.00	NB/SB	332+66.71 TO 334+09.73 TWO-WAY AMBER @ CORR.MEDIAN
	18.00	NB	339+32.51 TO 345+05.40 ONE-WAY CRYSTAL RT TURN LANE
	14.00	NB	340+13.86 TO 345+05.40 ONE-WAY CRYSTAL LT TURN LANE
	13.00	SB	332+66.71 TO 345+05.40 ONE-WAY CRYSTAL
	8.00	NB	344+06.63 TO 350+52.86 ONE-WAY CRYSTAL
	7.00	SB	344+08.85 TO 345+53.04 ONE-WAY CRYSTAL RT TURN LANE
	10.00	SB	344+06.63 TO 345+97.86 ONE-WAY CRYSTAL LT TURN LANE
	8.00	SB	344+06.63 TO 350+52.86 ONE-WAY CRYSTAL
	10.00	NB/SB	348+75.72 TO 350+52.86 TWO-WAY AMBER @ CORR. MEDIAN
	6.00	CLIFTON AVE RT	31+01.62 TO 32+16.28 ONE-WAY CRYSTAL LT TURN LANE
	3.00	CER+41 RT	10+75.01 TO 11+23.01 ONE-WAY CRYSTAL
	14.00	LT/RT	10+75.01 TO 12+43.01 TWO-WAY AMBER @ FLUSH MEDIAN
TOTAL	132.0		

78100205	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER, TYPE II	LOCATION	REMARKS
	EACH	IL 2	
	49	STAGE I 50' spacing	332+00.00 TO 357+25.00 place mid-way between flexible delineators
	48	STAGE II 50' spacing	330+40.00 TO 355+00.00 place mid-way between flexible delineators
TOTAL	97.0		

78300100	PAVEMENT MARKING REMOVAL	LOCATION	REMARKS
	SQ FT	IL 2	
	1166.7	STAGE 1	323+91.70 TO 332+66.71 FOUR LINES AT 4 INCHES EACH
	533.3		351+75.00 TO 355+75.00 FOUR LINES AT 4 INCHES EACH
	313.6		329+91.00 TO 355+00.00 SKIP DASH
	362.5	STAGE 2A	325+41.00 TO 332+66.00 SKIP DASH
	200.0		351+25.00 TO 355+25.00 SKIP DASH
	500.0	STAGE 2	351+50.00 TO 355+25.00 FOUR LINES AT 4 INCHES EACH
TOTAL	3,076.1		

X0321558	SANITARY MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	LOCATION	REMARKS
	EACH		
	1.0	RT	337+00 to 338+00 location unknown
	1.0	RT	343+15.1 SAN
	1.0	RT	343+59.6 SAN
	1.0	LT	344+17.6 SAN
	1.0	RT	345+94.3 SAN
	1.0	RT	345+93.0 SAN
	1.0	RT	346+70.4 SAN
	1.0	RT	348+13.6 SAN
	1.0	RT	349+07.9 SAN
TOTAL	9.0		

X0322902	SAW CUTTING, (PARTIAL DEPTH)	LOCATION	REMARKS
	FOOT		
	52.0		332+46.00
	52.0		350+70.00
TOTAL	104.0		

X0323230	ISLAND (SPECIAL)	LOCATION	REMARKS
	SQ YD.	IL 2	
	38.83	RT	343+05.40 TO 343+27.19
	39.66	LT	343+88.23 TO 344+08.85
TOTAL	78.5		

X5011100	FOUNDATION REMOVAL	LOCATION	OFFSET (FT)	REMARKS
	EACH	IL 2		
	1.0	RT	341+82.61	46.0 OLD LIGHT FOUNDATION
	1.0	RT	342+14.00	44.0 OLD LIGHT FOUNDATION
	1.0	RT	342+51.50	78.5 OLD LIGHT FOUNDATION
	1.0	RT	342+52.00	40.5 OLD LIGHT FOUNDATION
	1.0	RT	342+76.00	89.0 OLD LIGHT FOUNDATION
	1.0	LT	343+47.40	49.0 2' x 2' OLD LIGHT FOUNDATION
	1.0	LT	344+01.60	49.0 4' x 4.5' OLD SIGN FOUNDATION
	1.0	LT	345+61.90	41.3 OLD SIGN FOUNDATION
	1.0	LT	346+23.80	38.0 2.5' x 8' SIGN FOUNDATION
TOTAL	9.0			

XX001135	PAVEMENT PATCHING SPECIAL	LOCATION	REMARKS
	SQ YD	IL 2	
	60.00		347+50.00
	59.11		349+92.00
TOTAL	119.1		

XX002943	CONCRETE FOUNDATION SPECIAL	LOCATION	REMARKS
	EACH	IL 2	
	8	RT	339+75.0 TO 340+45.00 PIPE HANDRAIL FOUNDATIONS
TOTAL	8.0		

XX004900	TURF REINFORCEMENT MAT	LOCATION	REMARKS
	SQ YD	IL 2	
	506.0	LT	333+50.00 TO 340+50.00
TOTAL	506.0		

XX006241	GATE VALVE AND BOX 8"	LOCATION	REMARKS
	EACH	35' RT	
	1.0		31+05
TOTAL	1.0		

XX146400	STORM SEWER REMOVAL	LOCATION	REMARKS
	FOOT	IL 2	
	93.0		332+72.50 TO 333+63.92 MH TO MH
	46.0		333+64.53 TO 333+65.94 INLET TO MH
	6.0		333+65.94 TO 333+65.94 INLET TO MH
	203.0		333+68.08 TO 335+69.51 MH TO MH
	6.0		335+71.20 TO 335+71.20 INLET TO MH
	200.0		335+73.68 TO 337+72.67 MH TO MH
	49.0		337+58.18 TO 337+74.07 INLET TO MH
	6.0		337+75.63 TO 337+75.63 INLET TO MH
	200.0		337+76.90 TO 339+79.31 MH TO MH
	6.0		339+81.48 TO 339+81.48 MH TO INLET
	44.0		339+83.35 TO 340+26.86 INLET TO MH
	9.0		340+31.07 TO 340+39.00 MH TO SIDE OF CULVERT
	44.0		340+32.32 TO 340+70.56 PAVED DITCH TO SIDE OF CULVERT
	53.0		348+38.81 TO 348+36.68 INLET TO MH
	28.0		348+34.08 TO 348+07.28 MH TO INLET
	187.0		348+04.21 TO 346+18.51 INLET TO INLET
	77.0		346+15.51 TO 345+39.18 INLET TO MH
	58.0		346+39.00 TO 346+17.30 INLET TO INLET
	151.0		345+34.01 TO 343+81.71 MH TO INLET
	61.0		344+15.81 TO 343+80.86 INLET TO MH
	5.0		343+79.88 TO 343+79.70 INLET TO MH
	39.0		343+77.49 TO 343+39.47 MH TO MH
	155.0		343+35.32 TO 341+80.44 MH TO MH
	57.0		341+63.70 TO 341+75.71 INLET TO INLET
	11.0		341+75.76 TO 341+77.40 INLET TO MH
	126.0		341+75.29 TO 340+46.28 MH TO SIDE OF CULVERT
	34.0	CLIFTON AVE RT	31+72.00 TO 31+72.00 INLET TO INLET
	24.0	RT	31+72.00 TO 31+80.00 INLET TO OUTLET
TOTAL	1978.0		

Z0005305	BOX CULVERTS TO BE CLEANED	LOCATION	REMARKS
	FOOT	340+34.00	
	60.0		12ft wide x 7 ft high
TOTAL	60.0		

Z0024476	FLEXIBLE DELINEATOR MAINTENANCE	REMARKS
	EACH	
	50.0	ENTIRE PROJECT ESTIMATED QUANTITY
TOTAL	50.0	

Z0024478	FLEXIBLE DELINEATORS	LOCATION	REMARKS
	EACH	IL 2	
	50	STAGE I 50' spacing	332+00.00 TO 357+25.00
	50	STAGE II 50' spacing	330+40.00 TO 355+00.00
TOTAL	100.0		

PLOT DATE = Fri May 28 13:44:42 2026  
 FILE NAME = c:\p\proj\p1\20260528\ud5692c-rrr.dgn  
 PLOT SCALE = 50.0000 / 1 IN.  
 USER NAME = jordanhd