

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	40-M	WINNEBAGO	165	32
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

BUILDING REMOVAL SCHEDULE

NO.	DESCRIPTION	LOCATION	REMARKS
Z0028415	GEOTECHNICAL REINFORCEMENT		
	SO YD	IL 2	
		RT	332+66.71 TO 350+52.86 FULL DEPTH PAVEMENT
		LT	332+66.71 TO 350+52.86 FULL DEPTH PAVEMENT
		CLIFTON AVE	
		RT & LT	30+50.00 TO 32+46.10 FULL DEPTH PAVEMENT
TOTAL	1,740.0		
	17,044.0		
Z0041700	PLUG EXISTING STORM SEWERS		
	EACH	IL 2	
		RT	340+37.86 15" STORM SEWER
		LT	340+46.29 15" STORM SEWER
TOTAL	1.0		
	1.0		
	2.0		
*2001384	FIRE HYDRANT WITH 6" VALVE AND VALVE BOX		
	EACH	LOCATION	
		54' RT	339+49
		55' RT	344+10
		48' LT	350+57
		33' RT	31+10
TOTAL	1.0		
	1.0		
	4.0		
*2001385	BUTTERFLY VALVE AND BOX 16"		
	EACH	LOCATION	
		39' RT	339+50
		41' RT	350+48
TOTAL	1.0		
	1.0		
	2.0		
*2001386	CONNECT TO EXISTING WATER MAIN 16"		
	EACH	LOCATION	
		37' RT	339+45
		39' LT	339+92
TOTAL	1.0		
	1.0		
	2.0		
*2001387	COPPER SERVICE PUSHED 1"		
	EACH	LOCATION	
		LT	347+27
		LT	348+28
		LT	348+90
TOTAL	1.0		
	1.0		
	3.0		
*2001388	COPPER SERVICE 2"		
	EACH	LOCATION	
		RT	348+99
TOTAL	1.0		
	1.0		

NO.	BUILDING REMOVAL NO.	LOCATION	REMARKS
Z0007601	1		
	EACH	106' RT	
TOTAL	1.0		334+05
Z0007602	2		
	EACH	127' RT	
TOTAL	1.0		335+11
Z0007603	3		
	EACH	120' RT	
TOTAL	1.0		338+00
Z0007604	4		
	EACH	88' LT	
TOTAL	1.0		343+85
Z0007605	5		
	EACH	83' LT	
TOTAL	1.0		344+49
Z0007606	6		
	EACH	48' RT	
TOTAL	1.0		349+95
Z0007607	7		
	EACH	63' LT	
TOTAL	1.0		350+15

EARTH WORK SCHEDULE

LOCATION	EARTH EXC (CUT) CU YD	EARTH EXC ADJ SHRINK 25% EARTH CU YD	EMBANK (FILL) CU YD	EARTH WORK BALANCE WASTE (+) SHORTAGE (-) CU YD	UNSUITBL OR UNSTABLE MATERIAL	TOP SOIL FURNISH & PLACE 4" SQ YD
					CU YD	SQ YD
STAGE 1 LEFT						
332 + 50 - 343 + 50	3287	2465	903	1562	410	1277
343 + 50 - 350 + 75	2235	1676	27	1649	1221	441
STAGE 2A MIDDLE						
332 + 50 - 335 + 00	142	106	7	99		
348 + 00 - 350 + 75	163	122	7	116		
STAGE 2 RIGHT						
332 + 50 - 343 + 50	2928	2196	6898	-4702	72	1530
343 + 50 - 350 + 75	1778	1333	34	1299	140	429
SIDEROADS						
CLIFTON AVE						
30 + 50 - 32 + 00	1377	1033	49	984	599	
CER + 41						
11 + 00 - 13 + 25	1358	1019	0	1019		698
TOTAL	13268	9951	7926	2025	2442	4374

SCHEDULE OF QUANTITIES