

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	Z1T	STEPHENSON	49	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CODE NUMBER	ITEM	UNITS	ROADWAY Y007
X0325135	FIELD TILE 6"	FOOT	22
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	6
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	32
20200100	EARTH EXCAVATION	CU. YD.	892
20400800	FURNISHED EXCAVATION	CU. YD.	174
20800150	TRENCH BACKFILL	CU. YD.	43
25000310	SEEDING, CLASS 4	ACRE	0.13
25000910	SEEDING, CLASS 1 (MODIFIED)	ACRE	0.37
25001830	SEEDING, CLASS 6 (MODIFIED)	ACRE	0.55
25100115	MULCH, METHOD 2	ACRE	1.05
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	365
28000300	TEMPORARY DITCH CHECKS	EACH	13
28000400	PERIMETER EROSION BARRIER	FOOT	321
28100107	STONE RIPRAP, CLASS A4	SQ. YD.	81
28200200	FILTER FABRIC	SQ. YD.	81
35100100	AGGREGATE BASE COURSE, TYPE A	TON	108
35101400	AGGREGATE BASE COURSE, TYPE B	TON	273
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.4
42001200	PAVEMENT FABRIC	SQ. YD.	114
44000600	SIDEWALK REMOVAL	SQ. FT.	27
44201013	CLASS B PATCHES, TYPE IV, 13 INCH	SQ. YD.	114
44213200	SAW CUTS	FOOT	317
48101200	AGGREGATE SHOULDERS, TYPE B	TON	243
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1

FILE NAME = #FILES
 LEVELS = #LEVELS
 PLOT SCALE = #PLOTS/SCALE
 PLOT DATE = F, M, Sep, 02 14:55:53 2005
 SHEET NO. = 3
 SHEET TOTAL = 49
 SHEET REF =
 SHEET REF =