

# SUMMARY OF QUANTITIES

CONTRACT NO. 64A49

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	288R-1	JO DAVIESS	53	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	X080-2A	SFTY-3N
				80% FED/20% STATE	80% FED/20% STATE
20200100	EARTH EXCAVATION	CU YD	99	99	
20400800	FURNISHED EXCAVATION	CU YD	288	288	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1900	1900	
25100630	EROSION CONTROL BLANKET	SQ YD	467	467	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	415	415	
28000400	PERIMETER EROSION BARRIER	FOOT	1275	1275	
44000007	BITUMINOUS SURFACE REMOVAL, 2"	SQ YD	228	228	
48200400	BITUMINOUS SHOULDERS 6"	SQ YD	422	422	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURE	EACH	1	1	
50102400	CONCRETE REMOVAL	CU YD	13	13	
50200300	COFFERDAM EXCAVATION	CU YD	180	180	
50200500	COFFERDAM	EACH	1	1	
50300225	CONCRETE STRUCTURES	CU YD	16.6	16.6	
50300260	BRIDGE DECK GROOVING	SQ YD	1056	1056	
50300300	PROTECTIVE COAT	SQ YD	1056	1056	
5030305	CONCRETE WEARING SURFACE 5"	SQ YD	1043	1043	
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	5301	5301	
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	4084	4084	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	16,690	16,690	
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	570	570	
51500100	NAME PLATES	EACH	1	1	
63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	650	650	
63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4	
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	2	2	
63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	2	2	
63200310	GUARDRAIL REMOVAL	FOOT	931	931	
63500105	DELINEATORS	EACH	4	4	

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	X080-2A	SFTY-3N
				80% FED/20% STATE	80% FED/20% STATE
66700305	PERMANENT SURVEY MARKERS TYPE II	EACH	2	2	
67000400	ENGINEER'S FIELD OFFICE TYPE A	CAL MO	5	5	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70106700	TEMPORARY RUMBLE STRIPS	EACH	3	3	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	180	180	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	7572	7572	
70300280	TEMPORARY PAVEMENT MARKING -LINE 24"	FOOT	48	48	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2681	2681	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	708	708	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1416	1416	
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2985	2985	
78200410	GUARDRAIL MARKERS, TYPE A	EACH	16	16	
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300500	PAINT PAVEMENT MARKING REMOVAL	SQ FT	973	973	
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	161.3	161.3	
X0321781	MECHANICAL SPLICE	EACH	54	54	
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIXTURE "D", N70	TON	75	75	
XX005495	PRECAST PRESTRESSED CONCRETE DECK BEAM (21" DEPTH) SPECIAL	SQ FT	156.2	156.2	
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	110	110	
Z0002600	BAR SPLICERS	EACH	332	332	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0073500	TEMPORARY SUPPORT SYSTEM	L SUM	1	1	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH <= 4.5")	SQ FT	19.5	19.5	
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH > 5")	SQ FT	107.5	107.5	
X0325294	PERFORMED JOINT STRIP SEAL	FT	99	99	

\* SPECIALTY ITEM

PLOT DATE = Thu, 20 Jun 2006 08:28:05  
 FILE NAME = c:\pvc\projects\2006\64A49\64A49.dgn  
 PLOT SCALE = 1/8" = 1'-0"  
 USER NAME = mgj111

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_

## SUMMARY OF QUANTITIES