

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	28BR-1	JO DAVIESS	54	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

# SCHEDULE OF QUANTITIES

### 20200100 EARTH EXCAVATION

CU YD	LOCATION
61	US 20 LT&RT 1429+61 - 1433+13
38	LT&RT 1436+02 - 1439+07
99	TOTAL

### 20400800 FURNISHED EXCAVATION

CU YD	LOCATION
288	US 20 LT&RT 1429+61 - 1432+75
288	TOTAL

### 21101615 TOPSOIL FURNISH AND PLACE, 4"

SQ YD	LOCATION
1,703	US 20 LT&RT 1429+61 - 1433+13
197	LT&RT 1436+02 - 1439+07
1,900	TOTAL

### 25100630 EROSION CONTROL BLANKET

SQ YD	LOCATION
3	US 20 RT 1429+85 - 1429+92 (3' WIDE)
212	RT 1429+92 - 1433+13 (6' WIDE)
21	LT 1430+42 - 1430+81 (6' WIDE)
10	LT 1431+54 - 1431+84 (3' WIDE)
86	LT 1431+84 - 1433+13 (6' WIDE)
48	LT 1436+17 - 1437+58 (3' WIDE)
4	RT 1436+25 - 1436+37 (3' WIDE)
36	RT 1436+37 - 1436+91 (6' WIDE)
2	RT 1436+91 - 1436+96 (3' WIDE)
41	LT 1437+58 - 1438+18 (6' WIDE)
4	LT 1438+18 - 1438+30 (3' WIDE)
467	TOTAL

### 28000400 PERIMETER EROSION BARRIER

FOOT	LOCATION
411	US 20 RT 1429+54 - 1433+13
367	LT 1429+69 - 1433+13
177	RT 1436+01 - 1437+76
320	LT 1436+02 - 1439+19
1,275	TOTAL

### 44000007 BITUMINOUS SURFACE REMOVAL, 2"

SQ YD	LOCATION
113	US 20 LT&RT 1432+83 - 1433+13
115	LT&RT 1436+01 - 1436+32
228	TOTAL

### 48200400 BITUMINOUS SHOULDER, 6"

SQ YD	LOCATION
140	US 20 RT 1429+61 - 1433+13
133	LT 1430+18 - 1433+13
56	RT 1436+01 - 1437+70
93	LT 1436+01 - 1439+06
422	TOTAL

### 63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

FOOT	LOCATION
237.5	US 20 RT 1430+42 - 1432+79
175	LT 1431+05 - 1432+79
50	RT 1436+35 - 1437+85
187.5	LT 1436+35 - 1438+23
650	TOTAL

### 63100087 TRAFFIC BARRIER TERMINAL, TYPE 6A

EACH	LOCATION
1	US 20 RT 1432+79 - 1433+13
1	LT 1432+79 - 1433+13
1	RT 1436+01 - 1436+35
1	LT 1436+01 - 1436+35
4	TOTAL

### 63100167 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)

EACH	LOCATION
1	US 20 RT 1436+85 - 1437+35
1	LT 1438+23 - 1438+73
2	TOTAL

### 63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

EACH	LOCATION
1	US 20 RT 1429+02 - 1430+42
1	LT 1430+55 - 1431+05
2	TOTAL

### 63200310 GUARDRAIL REMOVAL

FOOT	LOCATION
301	US 20 RT 1430+13 - 1433+14
239	LT 1430+75 - 1433+14
127	RT 1436+01 - 1437+28
264	LT 1436+01 - 1438+65
931	TOTAL

### 63500105 DELINEATORS

EACH	LOCATION
1	US 20 RT 1429+02
1	LT 1430+55
1	RT 1437+35
1	LT 1438+73
4	TOTAL

### 70300100 SHORT-TERM PAVEMENT MARKING

FOOT	LOCATION
40	US 20 STA. 1428+01 - 1432+00 (CENTER LINE)
52	RT 1428+01 - 1440+64 (EDGE LINE)
52	LT 1428+01 - 1440+64 (EDGE LINE)
36	STA. 1437+00 - 1440+64 (CENTER LINE)
180	TOTAL

### 70300220 TEMPORARY PAVEMENT MARKING - LINE 4"

FOOT	LOCATION
2524	US 20 LT& RT 1428+00 - 1440+62 (PRE-STAGE 1)
2524	LT& RT 1428+00 - 1440+62 (STAGE 1)
2524	LT& RT 1428+00 - 1440+62 (STAGE 2)
7572	TOTAL

### 70300280 TEMPORARY PAVEMENT MARKING - LINE 24"

FOOT	LOCATION
12	US 20 RT 1428+00
12	LT 1429+24 (WEST LONGHOLLOW ROAD)
12	RT 1429+58 (WEST LONE STREET)
12	LT 1440+73
48	TOTAL

### 70301000 WORKZONE PAVEMENT MARKING REMOVAL

SQ FT	LOCATION
841	US 20 LT& RT 1428+00 - 1440+62 (PRE-STAGE 1)
841	LT& RT 1428+00 - 1440+62 (STAGE 1)
841	LT& RT 1428+00 - 1440+62 (STAGE 2)
24	RT 1428+00 (US 20)
24	LT 1429+24 (WEST LONGHOLLOW ROAD)
24	RT 1429+58 (WEST LONE STREET)
24	LT 1440+73 (US 20)
14	STA. 1428+01 - 1432+00 (CENTER LINE)
18	RT 1428+01 - 1440+64 (EDGE LINE)
18	LT 1428+01 - 1440+64 (EDGE LINE)
12	STA. 1437+00 - 1440+64 (CENTER LINE)
2681	TOTAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. DATE  
HORIZ. DRAWN BY  
CHECKED BY

PLOT DATE = Thu Mar 30 07:52:35 2006  
 PLOT SCALE = 50.000000  
 USER NAME = megilj