

# SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
308	*	ROCK ISLAND	40	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CODE NO.	ITEM	UNIT	TOTAL QTY	100% STATE	
				1000 TOTAL QUANTITY	100% STATE SFTY-2A SN081-0091 SN081-00
70400100	TEMPORARY CONCRETE BARRIER	FOOT	500		500
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	500		500
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	357	357	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1485	1485	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	232	232	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	140	140	
* 78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	2730	2730	
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	22952	22952	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	149	149	
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	134	134	
78300500	PAINT PAVEMENT MARKING REMOVAL	SQ FT	476		476
* 81400215	HEAVY-DUTY HANDHOLE TO BE ADJUSTED	EACH	2	2	
* 87900205	DRILL EXISTING HEAVY DUTY HANDHOLE	EACH	10	10	
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	810	810	
X0320887	POLYMER CONCRETE	CU FT	13.3		13.3
X0321468	PLUG EXISTING DECK DRAINS	EACH	32		32
X0322121	SHEET WATERPROOFING MEMBRANE SYSTEM	SQ YD	783		783
X0322932	SILICONE JOINT SEALER, 1.5"	FOOT	146		146
X0324885	CONDUIT INSTALLED, 1" DIA., NON-METALLIC	FOOT	380	380	
X0324887	CONDUIT INSTALLED, 2 1/2" DIA., NON-METALLIC	FOOT	48	48	
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	1814	1814	
X4066528	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90	TON	2825	2759	66
X4066658	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N90	TON	554	176	378
X4066745	LEVELING BINDER (HAND METHOD), SUPERPAVE, N90	TON	60	60	
X4066915	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, N90	TON	1848	1848	
X4080020	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50	TON	67	67	
X4402810	ISLAND SURFACE REMOVAL AND REPLACEMENT	SQ FT	30	30	
X6330103	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL, TANGENT	EACH	1		1
Z0002600	BAR SPLICERS	EACH	52		52
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	4		4
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	20		20
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	20		20
Z0017202	DOWEL BARS 1 1/2"	EACH	2220	2220	
Z0028415	GEOTECHNICAL REINFORCEMENT	SQ YD	659	659	
Z0028700	GRANULAR SUBGRADE REPLACEMENT	CU YD	34	34	
** Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2
** Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2
Z0075300	TIE BARS	EACH	9	9	

\* Specialty Item  
 \*\* SFTY-3N

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
SCALE: VERT.	DRAWN BY	CHECKED BY
HORIZ.	DATE	

## SUMMARY OF QUANTITIES