

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
599	17(D)BR-2-M	Rock Island	12	2
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

paycode	description	units	total quantity
			100% State
			SFTY-2A
			URBAN
42001300	PROTECTIVE COAT	SQ YD	29
50102400	CONCRETE REMOVAL	CU YD	10.5
50300255	CONCRETE SUPERSTRUCTURE	CU YD	9.7
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	52220
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1510
67100100	MOBILIZATION	L SUM	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1180
70300500	PAVEMENT MARKING TAPE, TYPE III	FOOT	9420
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4070
70400100	TEMPORARY CONCRETE BARRIER	FOOT	400
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	400
78300100	PAVEMENT MARKING REMOVAL	SQ FT	788
X0321781	MECHANICAL SPLICE	EACH	136
Z0022400	FABRIC REINFORCED ELASTOMERIC TROUGH	FOOT	69
* Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2
* Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2

* SFTY-3N

GENERAL NOTES

This structure will retain the same number 081-0040.

The contractor shall submit four copies of the required shop drawings for review and approval to the Bureau of Bridges and Structures, 2300 South Dirksen Parkway, Springfield, IL 62764. After approval of initial submittal, the contractor shall submit one set of shop drawings to Eric Harm, Engineer of Materials, 126 East Ash Street, Springfield, IL 62706, and eight (8) sets of shop drawings to be distributed to:

- District 2 District Engineer (1)
- Fabricator (1)
- Contractor (2)
- Resident Engineer (2)
- District 2 Bureau of Materials (2)

At bridge expansion joints, if temporary expansion joint bulkheads are attached to adjacent deck slabs or abutments for support, the Contractor shall cut the attachments as soon as the concrete has set to prevent joint damage due to horizontal contraction or expansion.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123. The following listed utilities located within the project limits or immediately adjacent to the project construction limits are members of JULIE:

- SBC/Ameritech
- MidAmerican Energy Company
- Mediacom
- Village of Milan
- City of Rock Island

The Resident Engineer shall contact the Bureau of Operations one or two days before the finish of each stage so that locations can be painted.

Summary of Quantities
US 67 OVER SOUTH CHANNEL
OF THE ROCK RIVER
FAP Route 599 (US 67)
Section 17(D)BR-2-M
Rock Island County
Structure No. 081-0040