

# SUMMARY OF QUANTITIES

CONTRACT NO. 64C02				
F.A.E. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
549	117BR-M	Ogle	12	2
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

100 % State  
SFTY-2A

Pay Code	Item Description	Units	Quantity
20400800	FURNISHED EXCAVATION	CU YD	75
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.2
40600300	AGGREGATE (PRIME COAT)	TON	1
<b>40600990</b>	<b>TEMPORARY RAMP</b>	SQ YD	<b>300</b>
42001300	PROTECTIVE COAT	SQ YD	199
<b>40600980</b>	<b>BITUMINOUS SURFACE REMOVAL BUTT JOINT</b>	SQ YD	<b>160</b>
44001205	BITUMINOUS CONCRETE SURFACE REMOVAL COMPLETE	SQ YD	203
48101200	AGGREGATE SHOULDERS, TYPE B	TON	50
50102400	CONCRETE REMOVAL	CU YD	3.1
50300255	CONCRETE SUPERSTRUCTURE	CU YD	3.6
50300260	BRIDGE DECK GROOVING	SQ YD	<b>186</b>
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	450
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3010
* 50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	107
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	375
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4
63200310	GUARDRAIL REMOVAL	FOOT	260
63500105	DELINEATORS	EACH	4
67100100	MOBILIZATION	L SUM	1
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	2
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1

100 % State  
SFTY-2A

Pay Code	Item Description	Units	Quantity
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	64
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	2580
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	24
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	535
70400100	TEMPORARY CONCRETE BARRIER	FOOT	275
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	550
78200400	GUARDRAIL REFLECTORS	EACH	4
78200410	GUARDRAIL MARKERS, TYPE A	EACH	16
78300100	PAVEMENT MARKING REMOVAL	SQ FT	150
X0301424	SILICONE JOINT SEALER	FOOT	33
X0320887	POLYMER CONCRETE	CU FT	2.4
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	86
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	199
Z0002600	BAR SPLICERS	EACH	64
Z0003700	BEARING PAD ADJUSTMENT	EACH	22
Z0017300	DOWEL REPAIR	EACH	22
• Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2
• Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0032700	KEYWAY REPAIR	FOOT	524

• SFTY-3M

Summary of Quantities  
 Illinois Route 72 over Tributary to Mud Creek  
 FAP Route 549  
 Section 117BR-M  
 Ogle County  
 Structure No. 071-0068