

80% FEDERAL
20% STATE

SUMMARY OF QUANTITIES					
CODE NO	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY 1000-2A	BRIDGE X181-5B
20200100	EARTH EXCAVATION	CU YD	230.0	230.0	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	105.0	105.0	
20400800	FURNISHED EXCAVATION	CU YD	45.0	45.0	
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	61.0		61.0
25000210	SEEDING, CLASS 2A	ACRE	0.25	0.25	
25100115	MULCH, METHOD 2	ACRE	0.25	0.25	
28000400	PERIMETER EROSION BARRIER	FOOT	1155.0	1155.0	
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	1180.0	1180.0	
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	675.5	675.5	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	29.0	29.0	
42001300	PROTECTIVE COAT	SQ YD	240.0	240.0	
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	240.0	240.0	
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	1571.0	1571.0	
44000700	APPROACH SLAB REMOVAL	SQ YD	290.0	290.0	
44004250	PAVED SHOULDER REMOVAL	SQ YD	45.0	45.0	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	62.0	62.0	
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	770.0	770.0	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1.0		1.0
50200100	STRUCTURE EXCAVATION	CU YD	61.0		61.0
50300260	BRIDGE DECK GROOVING	SQ YD	493.0		493.0
50300300	PROTECTIVE COAT	SQ YD	496.0		496.0
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	4457.0		4457.0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	6580.0		6580.0
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	248.0		248.0

* SPECIALTY ITEMS

80% FEDERAL
20% STATE

SUMMARY OF QUANTITIES					
CODE NO	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY 1000-2A	BRIDGE X181-5B
51500100	NAME PLATES	EACH	1.0		1.0
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	38		38
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	4.0		4.0
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	112.0		112.0
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	675.0	675.0	
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4.0	4.0	
63100075	TRAFFIC BARRIER TERMINAL, TYPE 5A	EACH	4.0	4.0	
63200310	GUARDRAIL REMOVAL	FOOT	320.0	320.0	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5.0	5.0	
67100100	MOBILIZATION	L SUM	1.0	1.0	
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2527.0	2527.0	
78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	140.0	140.0	
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	8.0	8.0	
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2.0	2.0	
78200410	GUARDRAIL MARKERS - TYPE A	EACH	14.0	14.0	
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4.0	4.0	
X0300136	BRIDGE APPROACH SHOULDER REMOVAL	SQ YD	30.0	30.0	
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	132.0	132.0	
X4073116	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 1 1/4"	SQ YD	120.0	120.0	
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	495.2		495.2
X6050700	REMOVE INLET BOX	EACH	4.0	4.0	
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1.0	1.0	
XX005369	TRAFFIC CONTROL & PROTECTION FOR TEMPORARY DETOUR	L SUM	1.0	1.0	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1.0	1.0	
X0325337	PREFORMED JOINT STRIP SEAL, 1"	FOOT	72.0		72.0

* SPECIALTY ITEMS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION F.A.P. ROUTE 653 (IL 18)
NAME	DATE	
		SUMMARY OF QUANTITIES