CONTRACT NO. 68072

F. A. S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
2402	(113B-2)I	PEORIA	55	5
STA.		TO STA.		
FED. ROAD DIST. NO. 5	US 150	FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	80% FED 20% STATE	SFTY-3N	X081-2A
* 78200410	GUARDRAIL MARKER TYPE A	EACH	19		19
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	6		6
X0301512	GUARDRAIL AGGREGATE EROSION CONTROL	TON	99		99
X0321475	PIPE ELBOW 12"	EACH	8		8
X0322752	WORK ZONE PAVEMENT MARKING REMOVAL	FOOT	72		72
X0323655	GABION ANCHOR STAKE	EACH	244		244 △1
X0324744	REMOVAL OF EXISTING PRECAST CONCRETE UNITS	SQ FT	359		359
X3560120	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 8 INCH	SQ YD	313		313
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	186		186
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	670		670
XX005128	STRIP SEAL EXPANSION JOINT ASSEMBLY	FOOT	33		33
Z0002600	BAR SPLICERS	EACH	183		183
Z0013798	CONSTRUCTION LAYOUT	L SUM	1		1
Z0020800	EROSION CONTROL CURB	FOOT	429		429
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
X0325446	SHOULDER INLET WITH CURB (4 FT SHOULDER)	EACH	4		4

* SPECIALTY ITEM △1 REVISED 5-30-06