

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	55-2	McDONOUGH	1025	53
STA.		TO STA.		
FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT		

LOCATION	PROCESSING MODIFIED SOILS 12"	PROCESSING MODIFIED SOIL 24"	LIME	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SUB-BASE GRANULAR MATERIAL, TYPE A 24"	SUB-BASE GRANULAR MATERIAL, TYPE A 18"	BITUMINOUS MATERIALS (PRIME COAT)	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), TYPE 2 13 1/4"	BITUMINOUS SHOULDERS SUPERPAVE 8"	SUB-BASE GRANULAR MATERIAL, TYPE C	AGGREGATE SHOULDERS, TYPE B	BITUMINOUS CONCRETE SURFACE COURSE MIX D SUPERPAVE, N70 2"	BITUMINOUS BASE COURSE SUPERPAVE 8"	BITUMINOUS SHOULDERS SUPERPAVE 6"
LOCATION	SQ YD	SQ YD	TON	SQ YD	SQ YD	SQ YD	TON	SQ YD	SQ YD	CU YD	TON	TON	SQ YD	SQ YD
RAMP J														
STA. 150+00.00 TO STA. 182+34.80							0.8	6,588.8	3,527.3	1,010.1	876.7			
STA. 150+00.00 TO STA. 155+20.00	1,241.3		27.6											
STA. 155+20.00 TO STA. 156+40.00					373.3									
STA. 156+40.00 TO STA. 172+10.00	4,950.1		110.3											
STA. 172+10.00 TO STA. 182+34.80					3,188.3									
U.S. ROUTE 136 (RELOCATED)														
STA. 1+41.50 TO STA. 31+74.65							1.0	8,088.3	2,701.5		1,377.3			
CROSS-OVERS														
STA. 18+28.68 TO STA. 28+00.00	2,834.2		63.1									237.6	2,121.0	713.2
STA. 128+00.00 TO STA. 138+80.28	2,942.9		65.6									249.4	2,227.2	715.7
SUBTOTAL	378,789.3	3,735.6	8,604.0	14,151.7	6,206.0	8,510.0	31.2	263,016.3	132,440.0	40,352.6	27,964.8	487.0	4,348.2	1,428.9
TOTAL	378,790	3,736	8,604	14,152	6,206	8,510	32	263,016	132,440	40,353	27,965	487	4,349	1,429

LOCATION	AGGREGATE BASE COURSE, TYPE A, 8"	AGGREGATE BASE COURSE, TYPE B, 6"	AGGREGATE SURFACE COURSE, TYPE A 8"	AGGREGATE SURFACE COURSE, TYPE B 6"	COVER COAT AGGREGATE	SEAL COAT AGGREGATE	AGGREGATE SHOULDERS, TYPE B	BITUMINOUS MATERIALS (PRIME COAT) (FOR CLA 3)	BITUMINOUS MATERIALS (COVER AND SEAL COAT)	BITUMINOUS MATERIALS (PRIME COAT) (FOR SUPERPAVE MIXTURES)	BITUMINOUS BASE COURSE SUPERPAVE 3 1/4"	BITUMINOUS CONCRETE SURFACE COURSE MIX C SUPERPAVE, N50 2"
LOCATION	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	TON	TON	TON	TON	TON	TON
TWP. ROAD 350 E												
STA. 4+86.10 TO STA. 8+89.60	863.4				21.6	10.8	63.8	1.73	5.18			
STA. 11+10.90 TO STA. 13+75.00	522.4				13.1	6.5	47.9	1.04	3.13			
SERVICE DRIVE												
STA. 0+00.00 TO STA. 27+40.33			7,108.5				557.1					
TWP. ROAD 118												
STA. 15+29.90 TO STA. 18+88.60	822.9						62.3		1.65	149.8	92.2	
STA. 20+99.20 TO STA. 22+90.00	375.4						33.2		0.75	68.3	42.0	
TWP. ROAD 150/COUNTY HIGHWAY 8												
STA. 25+25.00 TO STA. 28+86.70	725.9				18.1	9.1	62.9	1.45	4.36			
STA. 31+42.30 TO STA. 38+00.00	2,093.1						138.9		4.44	380.9	234.4	
TWP. ROAD 900N (WEST)												
STA. 21+65.00 TO STA. 24+00.00	452.3				11.3	5.7	37.5	0.90	2.71			
COUNTY HIGHWAY 8 (EAST)												
STA. 37+77.80 TO STA. 38+73.70	116.1						14.2		0.25	21.1	13.0	
TWP. ROAD 194												
STA. 47+00.00 TO STA. 48+90.70	328.7				8.2	4.1	33.6	0.66	1.97			
TWP. ROAD 900N (RELOCATED)												
STA. 72+20.00 TO STA. 89+96.61	4,430.6				110.8	55.4	346.4	8.86	26.58			
TWP. ROAD 200 (RELOCATED)												
STA. 46+87.00 TO STA. 58+58.50	3,088.8				77.2	38.6	234.6	6.18	18.53			
STA. 61+41.50 TO STA. 69+50.00	2,132.5				53.3	26.7	147.9	4.27	12.80			
TWP. ROAD 900N (EAST)												
STA. 99+50.00 TO STA. 99+88.00		107.5			2.6	1.3		0.21	0.65			
STA. 100+62.40 TO STA. 102+70.00	380.8				9.5	4.8	36.8	0.76	2.28			
TWP. ROAD 226 (RELOCATED)												
STA. 100+99.00 TO STA. 111+30.00	2,480.8				62.0	31.0	186.8	4.96	14.88			
GOLF COURSE ACCESS ROAD												
STA. 29+14.48 TO STA. 58+50.41		6,346.0			79.3	79.3		12.69	38.08			
CUL-DA-SACS (IL 336 STATIONING)												
STA. 209+97.10 TO STA. 211+01.00	1,063.4				26.6	13.3	18.0	2.12	6.38			
STA. 209+97.00 TO STA. 211+00.06	1,059.6				26.4	13.2	14.8	2.12	6.36			
STA. 289+98.30 TO STA. 290+93.60	1,072.5				26.8	13.4	17.8	2.14	6.44			
STA. 293+02.10 TO STA. 294+15.20	1,130.8				28.2	14.1	21.2	2.26	6.78			
STA. 461+49.80 TO STA. 462+70.50	1,145.0				26.8	14.3	16.8	2.29	6.87			
PRIVATE ENTRANCE OFF TWP. RD. 226												
STA. 500+12.00 TO STA. 504+56.00				1,103.6								
SUBTOTAL	24,285.0	6,453.5	7,108.5	1,103.6	601.9	341.5	2,092.5	54.64	163.99	7.09	620.1	381.6
TOTAL	24,285	6,454	7,109	1,104	602	342	2,093	55	164	8	621	382

82,724 (TON)

CONVERSION RATES
 ASPHALT: 112 LB/SQ YD IN
 AGGREGATE = 2.05 TON/CU YD
 0.004 TONS = GALLON

LOCATION	AGGREGATE SURFACE COURSE, TYPE B (6")	TON
ILL. 336		
STA. 129+57.40 RT		64
STA. 140+00.00 RT		564
STA. 198+00.00 RT		85
STA. 210+04.20 LT		49
STA. 210+12.30 RT		44
STA. 210+98.90 RT		34
STA. 264+00.00 LT		94
STA. 269+50.00 LT		93
STA. 269+50.00 RT		101
STA. 290+91.30 RT		59
STA. 308+50.00 LT		91
STA. 308+50.00 RT		98
STA. 316+00.00 RT		70
STA. 442+50.00 LT		46
STA. 442+50.00 RT		41
STA. 462+27.80 RT		17
STA. 462+68.50 RT		19
STA. 483+57.70 RT		25
STA. 477+50.00 RT		170
STA. 489+00.00 RT		210
STA. 503+75.00 RT		53
U.S. ROUTE 136 (RELOCATED)		
STA. 5+00.00 LT		68
STA. 5+00.00 RT		55
STA. 8+50.00 RT		44
STA. 14+00.00 LT		53
STA. 14+00.00 RT		45
STA. 21+50.00 RT		72
SERVICE DRIVE		
STA. 0+00.00 RT		36
STA. 12+00.00 RT		29
STA. 17+04.80 RT		47
STA. 19+17.80 RT		47
TR 350E		
STA. 4+60 RT		34
TWP. ROAD 118		
STA. 16+22.00 RT		41
STA. 24+00.00 RT		24
CO. HWY. 8 (REL.)/TR 150		
STA. 27+00.00 LT		55
TWP. ROAD 900N (WEST)		
STA. 19+50.00 RT		35
STA. 23+00.00 RT		29
TWP. ROAD 194		
STA. 46+25.00 LT		27
TWP. ROAD 900N (RELOCATED)		
STA. 87+00.00 RT		37
TWP. ROAD 200 (RELOCATED)		
STA. 51+00.00 RT		42
STA. 64+94.60 LT		57
STA. 64+94.60 RT		48
TWP. ROAD 226 (RELOCATED)		
STA. 103+50.00 LT		387
STA. 106+75.00 LT		98
STA. 107+37.00 RT		128
PRIVATE ENTRANCE OFF TWP. 226		
STA. 500+10-500+55		333.0
SUBTOTAL		3,896.7
TOTAL		3,897

REVISED
 5-30-02

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
IL. ROUTE 336
 DATE 3/30/06
 DRAWN BY
 CHECKED BY