

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	55-2	McDONOUGH	1025	9
STA.		TO STA.		
FED. ROAD DIST. NO. 4		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES				MCDONOUGH COUNTY 80% FEDERAL / 20% STATE											
				ROADWAY RURAL			CONSTRUCTION TYPE CODE								
				(BIT.)	(A-3)	(AGG)	Y030-1E LIGHTING	BRIDGES X181-5B SN 055-0052, 0053	BRIDGES X641-5B SN 055-9901	BRIDGES X641-5B SN 055-9902	BRIDGES X641-5B SN 055-9903	BRIDGES X081-2A SN 055-0060, 0061	BRIDGES WILDLIFE BRIDGES	CULVERTS X028-2A SN 055-2501, 2502, 2503	
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	(BIT.)	(A-3)	(AGG)									
28300400	AGGREGATE DITCH	TON	17,551	15,239	1,871	441									
28400100	GABIONS	CU YD	152	140	12										
28500100	FABRIC FORMED CONCRETE REVETMENT MATS	SQ YD	558	558											
30103000	SHAPING AND GRADING ROADWAY	UNIT	29		29										
30200650	PROCESSING MODIFIED SOILS 12"	SQ YD	378,790	378,790											
30201250	PROCESSING MODIFIED SOILS 24"	SQ YD	3,736	3,736											
30201500	LIME	TON	8,604.0	8,604.0											
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	14,152	14,152											
31100935	SUB-BASE GRANULAR MATERIAL, TYPE A 18"	SQ YD	8,510	8,510											
31100965	SUB-BASE GRANULAR MATERIAL, TYPE A 24"	SQ YD	6,206	6,206											
31102000	SUB-BASE GRANULAR MATERIAL, TYPE C	CU YD	40,353	40,353											
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	26,836	5,959	20,877										
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	6,454	6,346	108										
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	3,654	3,654											
40200700	AGGREGATE SURFACE COURSE, TYPE A 8"	SQ YD	7,109			7,109									
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	3,897	2,483	1,255	159									
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	55		55										
40300400	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	TON	164		164										
40300500	COVER COAT AGGREGATE	TON	602		602										
40300600	SEAL COAT AGGREGATE	TON	342		342										
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	40	40											
40600895	CONSTRUCTING TEST STRIP	EACH	2	2											
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	223	223											
40600980	TEMPORARY RAMP	SQ YD	190	190											
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	1,175	1,175											
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT 8 INCH	SQ YD	128	128											
44000100	PAVEMENT REMOVAL	SQ YD	26,897	26,897											
44004250	PAVED SHOULDER REMOVAL	SQ YD	2,753	2,753											
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	204	204											
48101200	AGGREGATE SHOULDERS, TYPE B	TON	30,058	28,212	1,289	557									

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
**IL. ROUTE 336**  
 DATE 3/30/06  
 DRAWN BY  
 CHECKED BY

5/7/2006 12:28:33 PM