

SUMMARY OF QUANTITIES				MCDONOUGH COUNTY 80% FEDERAL / 20% STATE CONSTRUCTION TYPE CODE													
				ROADWAY RURAL			Y030-1E LIGHTING	BRIDGES X181-5B SN 055-0052, 0053 BRIDGES OVER RAILROAD	BRIDGES X641-5B SN 055-9901 RR BRIDGES OVER ROADWAY	BRIDGES X641-5B SN 055-9902 RR BRIDGES OVER ROADWAY	BRIDGES X641-5B SN 055-9903 RR BRIDGES OVER ROADWAY	BRIDGES X081-2A SN 055-0060, 0061 WILDLIFE BRIDGES	CULVERTS X028-2A SN 055-2501, 2502, 2503 CAST IN PLACE CULVERTS				
				(BIT.)	(A-3)	(AGG)											
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	(BIT.)	(A-3)	(AGG)											
Z0069700	SUB-BALLAST	CU YD	2,522	2,522													
<input checked="" type="checkbox"/> Z0076600	TRAINEES	hour	3,000	3,000													
Z0077000	VERTICAL PLASTIC DRAINAGE WICKS	FOOT	121,850	121,850													
* A2002016	TREE, AESCULUS GLABRA (OHIO BUCKEYE), 2" CALPER, BALLED AND BURLAPPED	EACH	17	17													
* A2002816	TREE, CATALPA SPECIOSA (NORTHERN CATALPA), 2" CALIPER, BALLED AND BURLAPPED	EACH	24	24													
* A2002916	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2" CALIPER BALLED AND BURLAPPED	EACH	24	24													
* A2005016	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2" CALIPER BALLED AND BURLAPPED	EACH	27	27													
* A2006708	TREE, QUERCUS MACROCARPA (BUR OAK), 1" CALIPER, BALLED AND BURLAPPED	EACH	33	29	4												
* B2001116	TREE, CERCIS CANADENSIS (EASTERN REDBUD) 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	27	27													
* D2002760	EVERGREEN, PINUS NIGRA (AUSTRIAN PINE), 5' HEIGHT, BALLED AND BURLAPPED	EACH	213	213													
* K1005431	SEEDLING MIXTURE "A"	UNIT	54	54													
X0301512	GUARDRAIL AGGREGATE EROSION CONTROL	TON	2,001	1,786	215												
X0320547	REMOVE AND REINSTALL END SECTION	EACH	1	1													
X0321475	PIPE ELBOW 12"	EACH	12	12													
X0321583	PIPE ELBOW 18"	EACH	1	1													
X0322865	GRATED END SECTION, SPECIAL	EACH	1	1													
X0324895	SANITARY SEWER MANHOLES, TYPE A, TYPE 1 FRAME, CLOSED LID	EACH	1	1													
X0325109	POROUS GRANULAR MATERIAL	CU YD	454	454													
X0488100	REMOVING EXISTING SEPTIC TANK	EACH	2	2													
X0840000	SANITARY SEWER REMOVAL 8"	FOOT	120	120													
X0919000	TEMPORARY PAVEMENT REMOVAL	SQ YD	6,346		6,346												
X2111000	TOPSOIL EXCAVATION	CU YD	4,515	4,515													
X2510630	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	1,191	860	331												
X3550010	BITUMINOUS BASE COURSE SUPERPAVE	TON	1,643		1,643												
X3550500	BITUMINOUS BASE COURSE SUPERPAVE 8"	SQ YD	4,349	4,349													
X4020500	AGGREGATE SURFACE COURSE, TYPE B 6"	SQ YD	1,104		1,104												
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	668	668													
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	882	882													
X4073146	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, TYPE 2 13 1/4"	SQ YD	263,016	263,016													
X4080020	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50	TON	34	34													

← I000-2A →

\* SPECIALTY ITEMS  
 Y080

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
**IL. ROUTE 336**

DATE 3/30/06

DRAWN BY  
CHECKED BY

5/2/2006 12:36:08 PM