

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	55-2	MCDONOUGH	1025	28
STA.		TO STA.		
FED. ROAD DIST. NO. 4 ILLINOIS		FED. AID PROJECT		

LEFT STATION ELEVATION AND OFFSET       $\frac{1}{2}$  RIGHT STATION ELEVATION AND OFFSET

478+50.00	617.24	49.00L	617.42	37.00L	617.24	25.00L				478+50.00	617.24	25.00R	617.42	37.00R	617.24	49.00R				
478+75.00	617.13	49.00L	617.30	37.00L	617.13	25.00L				478+75.00	617.13	25.00R	617.31	37.00R	617.13	49.00R				
479+00.00	616.94	49.00L	617.12	37.00L	617.05	25.00L				479+00.00	617.05	25.00R	617.23	37.00R	617.17	49.00R				
479+25.00	616.78	49.00L	616.96	37.00L	617.00	25.00L				479+25.00	617.00	25.00R	617.18	37.00R	617.23	49.00R				
479+50.00	616.65	49.00L	616.83	37.00L	616.98	25.00L				479+50.00	616.98	25.00R	617.16	37.00R	617.32	49.00R				
479+75.00	616.55	49.00L	616.77	37.00L	616.99	25.00L				479+75.00	616.99	25.00R	617.22	37.00R	617.44	49.00R				
480+00.00	616.48	49.00L	616.76	37.00L	617.03	25.00L				480+00.00	617.03	25.00R	617.31	37.00R	617.59	49.00R				
480+25.00	616.43	49.00L	616.77	37.00L	617.10	25.00L				480+25.00	617.10	25.00R	617.44	37.00R	617.78	49.00R				
480+50.00	616.42	49.00L	616.82	37.00L	617.20	25.00L				480+50.00	617.20	25.00R	617.60	37.00R	617.99	49.00R				
480+75.00	616.44	49.00L	616.89	37.00L	617.33	25.00L				480+75.00	617.33	25.00R	617.78	37.00R	618.24	49.00R				
481+00.00	616.49	49.00L	617.00	37.00L	617.49	25.00L				481+00.00	617.49	25.00R	617.99	37.00R	618.50	49.00R				
503+50.00	656.43	49.00L	656.93	37.00L	657.42	25.00L				503+50.00	657.17	17.71R	657.42	25.00R	657.93	37.00R	658.43	49.00R		
503+75.00	656.89	49.00L	657.39	37.00L	657.88	25.00L				503+75.00	657.62	16.46R	657.88	25.00R	658.39	37.00R	658.89	49.00R		
504+00.00	657.45	49.00L	657.90	37.00L	658.34	25.00L				504+00.00	658.07	15.36R	658.34	25.00R	658.79	37.00R	659.25	49.00R		
504+25.00	658.02	49.00L	658.42	37.00L	658.80	25.00L				504+25.00	658.54	14.41R	658.80	25.00R	659.20	37.00R	659.59	49.00R		
504+50.00	658.59	49.00L	658.93	37.00L	659.26	25.00L				504+50.00	659.02	13.59R	659.26	25.00R	659.60	37.00R	659.94	49.00R		
504+75.00	659.16	49.00L	659.44	37.00L	659.72	25.00L				504+75.00	659.48	13.00R	659.72	25.00R	660.00	37.00R	660.28	49.00R		
505+00.00	659.73	49.00L	659.96	37.00L	660.18	25.00L				505+00.00	659.94	13.00R	660.18	25.00R	660.40	37.00R	660.63	49.00R		
505+25.00	660.30	49.00L	660.48	37.00L	660.64	25.00L				505+25.00	660.40	13.00R	660.64	25.00R	660.82	37.00R	660.97	49.00R		
505+50.00	660.87	49.00L	661.05	37.00L	661.10	25.00L				505+50.00	660.86	13.00R	661.10	25.00R	661.28	37.00R	661.32	49.00R		
505+75.00	661.44	49.00L	661.62	37.00L	661.56	25.00L				505+75.00	661.32	13.00R	661.56	25.00R	661.74	37.00R	661.67	49.00R		
506+00.00	662.01	49.00L	662.19	37.00L	662.02	25.00L				506+00.00	661.78	13.00R	662.02	25.00R	662.20	37.00R	662.02	49.00R		
506+25.00	662.47	49.00L	662.65	37.00L	662.47	25.00L				506+25.00	662.23	13.00R	662.47	25.00R	662.65	37.00R	662.47	49.00R		

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUPERELEVATION TRANSITION DETAIL**  
**IL. ROUTE 336**  
**STA. 478 + 50.00 TO STA. 506 + 25.00**

DATE 3/30/06  
DRAWN BY  
CHECKED BY