

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	55-2	McDONOUGH	1025	33
STA.		TO STA.		
FED. ROAD DIST. NO. 4		ILLINOIS	FED. AID PROJECT	

BOX CULVERT END SECTIONS SCHEDULE											
LOCATION	BOX CULVERT END SECTION, CULVERT NO.1	BOX CULVERT END SECTION, CULVERT NO.2	BOX CULVERT END SECTION, CULVERT NO.3	BOX CULVERT END SECTION, CULVERT NO.4	BOX CULVERT END SECTION, CULVERT NO.5	BOX CULVERT END SECTION, CULVERT NO.6	BOX CULVERT END SECTION, CULVERT NO.7	BOX CULVERT END SECTION, CULVERT NO.10	BOX CULVERT END SECTION, CULVERT NO.11	BOX CULVERT END SECTION, CULVERT NO.12	BOX CULVERT END SECTION, CULVERT NO.14
	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
IL ROUTE 336											
STA. 145+73.00	2										
STA. 176+37.65		2									
STA. 213+42.81			2								
STA. 253+39.23				2							
STA. 276+05.41					2						
STA. 286+54.16						2					
STA. 301+29.45							2				
STA. 524+02.00											2
STA. 543+50.00									2		
IL ROUTE 136 (RELOCATED)											
STA. 2+96.22									2		
STA. 24+50.00										2	
TOTAL	2	2	2	2	2	2	2	2	2	2	2

NOTE:
BOX CULVERT END SECTIONS NO. 8, NO. 9, AND NO. 13
ARE CAST IN PLACE END SECTIONS AND ARE INCLUDED
IN BOX CULVERT QUANTITIES.

BOX CULVERT SCHEDULE												
LOCATION					PRECAST CONCRETE BOX CULVERT 4' X 3'	PRECAST CONCRETE BOX CULVERT 6' X 4'	PRECAST CONCRETE BOX CULVERT 6' X 5'	PRECAST CONCRETE BOX CULVERT 6' X 6'	PRECAST CONCRETE BOX CULVERT 8' X 7'	PRECAST CONCRETE BOX CULVERT 8' X 8'	PRECAST CONCRETE BOX CULVERT 8' X 5'	PRECAST CONCRETE BOX CULVERT 10' X 7'
					FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
IL ROUTE 336												
STA. 145+73.00	LT	TO	STA. 145+73.00	RT					306.0			
STA. 175+95.00	LT	TO	STA. 176+98.20	RT						300.0		
STA. 212+47.00	RT	TO	STA. 214+42.00	LT				281.0				
STA. 252+35.00	LT	TO	STA. 254+46.00	RT							388.0	
STA. 275+45.00	LT	TO	STA. 276+66.00	RT					314.0			
STA. 287+03.00	LT	TO	STA. 286+06.00	RT			260.0					
STA. 300+29.00	RT	TO	STA. 302+32.00	LT			328.0					
STA. 523+09.00	RT	TO	STA. 524+95.00	LT		250.0						
STA. 543+50.00	RT	TO	STA. 543+50.00	LT	192.0							
US ROUTE 136 (RELOCATED)												
STA. 2+71.50	RT	TO	STA. 3+15.00	LT			107.0					
STA. 24+50.00	LT	TO	STA. 24+50.00	RT		72.0						
TOTAL					192.0	72.0	357.0	588.0	587.0	314.0	300.0	388.0

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
IL. ROUTE 336

DATE 3/30/06
DRAWN BY
CHECKED BY