

PIPE UNDERDRAINS (SPECIAL) SCHEDULE (CONTINUED)																	
LOCATION	PIPE UNDERDRAINS 4" (SPECIAL)						PIPE UNDERDRAINS 6" (SPECIAL)		CONCRETE HEADWALL FOR PIPE DRAINS				RIP RAP, SPECIAL				
	WEST BOUND		EAST BOUND		RAMPS		RAMPS		WEST BOUND		EAST BOUND		RAMPS		LENGTH	SQ YD	
	O/S LT.	I/S LT.	I/S RT.	O/S RT.	LT.	RT.	LT.	RT.	O/S LT.	I/S LT.	I/S RT.	O/S RT.	LT.	RT.			
RAMP I																	
STA. 19+50	TRANS.													6			
STA. 20+25						14								1			
STA. 20+50	TRANS.													6			
STA. 23+00	TRANS.													6			
STA. 25+00	TRANS.													6			
STA. 27+00						16								1			
STA. 27+10	TRANS.													6			
STA. 28+50	TRANS.													6			
STA. 29+00	N. PIPE					15								1			
STA. 29+00	S. PIPE					15								1			
STA. 30+50	TRANS.													6			
STA. 32+50	TRANS.													6			
STA. 34+00	TRANS.													6			
STA. 34+00						24								1			
STA. 39+00						18								1			
RAMP J																	
STA. 155+00	N. PIPE					14								1			
STA. 155+00	S. PIPE					14								1			
STA. 156+00	TRANS.													6			
STA. 158+00	TRANS.													6			
STA. 159+90						14								1			
STA. 161+25	TRANS.					14								1			
STA. 161+25						14								1			
STA. 163+75						14								1			
STA. 165+50	TRANS.													6			
STA. 167+00	TRANS.													6			
STA. 167+25														14			
STA. 169+00	TRANS.													6			
STA. 170+25														12			
STA. 171+00	TRANS.													6			
STA. 173+00	TRANS.													6			
STA. 175+25						12								1			
STA. 179+25						14								1			
SUBTOTAL		1,778	1,587	1,668	1,764	212	110	6	6	84	67	69	89	4	24	6,699	2,238
TOTAL				7,119				12				337				6,699	2,238

FENCE SCHEDULE					
LOCATION				FOOT	EACH
STA.	TO STA.	TYPE	FOOT	TYPE	FOOT
IL ROUTE 336					
STA. 337+38.00	LT TO STA. 341+00.00	LT	409		
STA. 341+00.00	LT TO STA. 353+00.00	LT	1,213		
STA. 353+00.00	LT TO STA. 365+00.00	LT	1,203		
STA. 365+00.00	LT TO STA. 375+00.00	LT	1,000		
STA. 375+00.00	LT TO STA. 387+00.00	LT	1,200		
STA. 387+00.00	LT TO STA. 399+00.00	LT	1,154		
STA. 396+00.00	RT TO STA. 399+00.00	RT	303		
STA. 399+00.00	LT TO STA. 403+92.00	LT	492		
STA. 399+00.00	RT TO STA. 404+41.00	RT	541		
STA. 475+00.00	LT TO STA. 481+00.00	LT	602		
STA. 478+00.00	RT TO STA. 481+00.00	RT	303		
STA. 481+00.00	LT TO STA. 493+00.00	LT	1,209		
STA. 481+00.00	RT TO STA. 493+00.00	RT	1,350		
STA. 488+62.08	RT				1
STA. 493+00.00	LT TO STA. 494+40.00	LT	202		
STA. 493+00.00	RT TO STA. 493+82.50	RT	60		
STA. 494+00.00	LT				1
STA. 495+15.00	RT TO STA. 505+00.00	RT	1,070		
STA. 495+50.00	RT TO				1
STA. 495+68.50	LT TO STA. 505+00.00	LT	900		
STA. 503+75.00	RT				1
STA. 505+00.00	RT TO STA. 517+00.00	RT	1,269		
STA. 505+00.00	LT TO STA. 517+00.00	LT	1,272		
STA. 517+00.00	RT TO STA. 519+80.00	RT	285		
STA. 517+00.00	LT TO STA. 529+00.00	LT	1,204		
STA. 522+65.00	RT TO STA. 529+00.00	RT	652		
STA. 529+00.00	RT TO STA. 541+00.00	RT	1,201		
STA. 531+30.00	LT TO STA. 541+00.00	LT	994		
STA. 541+00.00	LT TO STA. 546+45.30	LT	545		
STA. 541+00.00	RT TO STA. 553+00.00	RT	1,219		
RAMP I					
STA. 21+74.60	RT TO STA. 28+63.40	RT	626		
RAMP J					
STA. 161+00.00	RT TO STA. 162+25.00	RT	152		
SERVICE DRIVE					
STA. 7+00.00	LT TO STA. 10+00.00	LT	300		
STA. 10+00.00	LT TO STA. 20+00.00	LT	1,002		
STA. 20+00.00	LT TO STA. 27+10.00	LT	716		
TOTAL			9,533	15,115	2

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	55-2	MCDONOUGH	1025	38
STA.	TO STA.			
FED. ROAD DIST. NO. 4	ILLINOIS	FED. AID PROJECT		

TRAFFIC CONTROL AND PROTECTION SCHEDULE							
LOCATION	STANDARD 701331	STANDARD 701201	STANDARD 701306	STANDARD 701326	STANDARD 701406	STANDARD BLR 21	STANDARD BLR 22
	EACH	L. SUM	L. SUM	L. SUM	L. SUM	L. SUM	L. SUM
ENTIRE PROJECT	1	1	1	1	1	1	1
TOTAL	1	1	1	1	1	1	1

MOBILIZATION SCHEDULE	
LOCATION	L. SUM
ENTIRE PROJECT	1
TOTAL	1

FURNISHING AND MAINTAINING AUTOMOTIVE VEHICLES	
LOCATION	CAL MO
ENTIRE PROJECT	24
TOTAL	24

ENGINEER'S FIELD LABORATORY SCHEDULE	
LOCATION	CAL MO
ENTIRE PROJECT	24
TOTAL	24

TRAFFIC CONTROL SURVEILLANCE SCHEDULE	
LOCATION	TRAFFIC CONTROL SURVEILLANCE
	CAL DA
ENTIRE PROJECT	100
TOTAL	100

ENGINEER'S FIELD OFFICE, TYPE A SCHEDULE	
LOCATION	CAL MO
ENTIRE PROJECT	24
TOTAL	24

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
IL. ROUTE 336
 DRAWN BY
 CHECKED BY
 DATE 3/30/06