F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
316	55-2	McDONOUGH	1025	40
STA.		TO STA.		
FED. ROAD DIST. NO. 4	ILLINOIS	FED. AID PROJECT		

MAINLINE- CLASS A PIPE CULVERT AND END SECTION SCHEDULE

LOCATION							PIPE CULVERTS, CLASS A, TYPE 1			PIPE CULVERTS, CLASS A, TYPE 2						PIPE CULVERTS, CLASS A, TYPE 3				PIPE CULVERTS, CLASS A, TYPE 4	PIPE CULVERTS, CLASS A, TYPE 5	PIPE CULVERTS, CLASS A, TYPE 6	PRECAST REINFORCED CONCRETE FLARED END SECTIONS					CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS		
							12"	18"	24"	18"	24"	48"	54"	66"	72"	18"	24"	36"	60"	24"	36"	24"	18"	24"	36"	48"	54"	60"	66"	72"
							FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	EA	EA	EA	EA	EA	EA	EA	EA
IL ROUTE 336																															
STA. 128+00.00		CL	TO	STA. 128+00.00	81.00 FT	LT				80													1							
STA. 132+74.00	14.00 FT	LT	TO	STA. 132+74.00	79.00 FT	LT	65																								
STA. 137+00.00	3.30 FT	LT	TO	STA. 137+00.00	74.00 FT	LT			69															1							
STA. 139+50.00	113.00 FT	RT	TO	STA. 140+50.00	116.00 FT	RT										100							2								
STA. 140+80.00	6.00 FT	RT	TO	STA. 140+80.00	94.00 FT	LT					98													1							
STA. 159+00.00	140.50 FT	LT	TO	STA. 159+00.00	147.50 FT	RT																288		2							
STA. 166+00.00		CL	TO	STA. 166+00.00	117.00 FT	RT											116							1							
STA. 183+03.00	112.50 FT	RT	TO	STA. 184+39.67	107.45 FT	LT							259														1				
STA. 184+62.00	6.00 FT	RT	TO	STA. 184+62.00	96.00 FT	RT					89													1							
STA. 199+64.00	88.00 FT	LT	TO	STA. 200+00.00	91.50 FT	RT						183														2					
STA. 201+00.00		CL	TO	STA. 201+00.00	88.00 FT	RT					87													1							
STA. 210+54.00		CL	TO	STA. 210+54.00	80.00 FT	LT					79													1							
STA. 219+50.00		CL	TO	STA. 219+50.00	95.00 FT	RT					94													1							
STA. 237+06.00	6.00 FT	LT	TO	STA. 237+06.00	99.50 FT	RT					104													1							
STA. 240+02.00	109.40 FT	RT	TO	STA. 242+37.00	105.60 FT	LT													318									2			
STA. 253+39.23		CL	TO	STA. 254+00.00		CL			58																						
STA. 278+90.00		CL	TO	STA. 278+90.00	96.00 FT	RT											95							1							
STA. 284+50.00		CL	TO	STA. 284+50.00	124.90 FT	RT															124				1						
STA. 297+00.00		CL	TO	STA. 297+00.00	90.00 FT	RT					89													1							
STA. 316+50.00		CL	TO	STA. 316+50.00	85.60 FT	LT					87													1							
STA. 317+00.00		CL	TO	STA. 317+00.00	86.00 FT	RT					86													1							
STA. 317+70.00	84.00 FT	RT	TO	STA. 318+20.00	93.00 FT	LT								184															2		
STA. 325+22.00	113.00 FT	RT	TO	STA. 327+46.00	115.50 FT	LT									320																2
STA. 348+88.00		CL	TO	STA. 348+88.00	108.00 FT	RT					107													1							
STA. 349+91.00	117.00 FT	LT	TO	STA. 349+91.00	109.30 FT	LT		8															1								
STA. 350+74.00	6.00 FT	RT	TO	STA. 350+74.00	93.50 FT	RT					87													1							
STA. 360+00.00	80.00 FT	LT	TO	STA. 360+00.00		CL					77													1							
STA. 360+00.00		CL	TO	STA. 360+00.00	91.00 FT	RT					90													1							
STA. 368+00.00	85.00 FT	LT	TO	STA. 368+00.00	92.00 FT	RT			152															2							
STA. 376+00.00	76.00 FT	LT	TO	STA. 376+00.00	92.00 FT	RT			154															2							
STA. 377+55.00	15.25 FT	RT	TO	STA. 377+55.00	78.50 FT	RT		64															1								
STA. 382+00.00	13.58 FT	LT	TO	STA. 382+00.00	71.00 FT	LT			57.5															1							
STA. 403+00.00	6.00 FT	LT	TO	STA. 403+00.00	90.00 FT	LT					83													1							
STA. 422+00.00		CL	TO	STA. 422+00.00	90.00 FT	LT					89													1							
STA. 438+00.00	84.80 FT	RT	TO	STA. 438+34.53	3.00 FT	LT					93													1							
STA. 438+34.53	3.00 FT	LT	TO	STA. 438+68.00	89.00 FT	LT					92													1							
STA. 441+75.00	5.00 FT	LT	TO	STA. 441+75.00	76.00 FT	LT			70															1							
STA. 453+00.00		CL	TO	STA. 453+00.00	92.00 FT	LT					91													1							
STA. 469+96.00	9.00 FT	LT	TO	STA. 469+96.00	90.00 FT	LT					76													1							
STA. 479+50.00		CL	TO	STA. 479+50.00	112.00 FT	RT												112							1						
STA. 498+00.00		CL	TO	STA. 498+00.00	89.00 FT	RT					88													1							
STA. 507+55.00	94.00 FT	RT	TO	STA. 507+70.00	4.00 FT	RT					90													1							
STA. 532+00.00		CL	TO	STA. 532+00.00	118.00 FT	LT														117				1							
						SUBTOTAL	65	72	561	80	1876	183	259	184	320	100	211	112	318	117	124	288	5	33	2	2	1	2	2	2

MAINLINE- CLASS D PIPE CULVERT AND END SECTION SCHEDULE

LOCATION							PIPE CULVERTS, CLASS D, TYPE 1	PIPE CULVERTS, CLASS D, TYPE 2	PIPE CULVERTS, CLASS D, TYPE 3		METAL END SECTIONS	
							24"	18"	18"	24"	18"	24"
							FT	FT	FT	FT	EA	EA
IL ROUTE 336												
STA. 197+77.50	96.73 FT	RT	TO	STA. 198+22.50	97.41 FT	RT	45					2
STA. 269+08.00	89.50 FT	RT	TO	STA. 269+94.00	89.80 FT	RT		86			2	
STA. 269+09.00	88.80 FT	LT	TO	STA. 269+93.00	89.80 FT	LT		84			2	
STA. 307+90.00	109.80 FT	RT	TO	STA. 309+10.00	107.20 FT	RT				120		2
STA. 308+02.10	109.10 FT	LT	TO	STA. 308+97.90	104.10 FT	LT			96		2	
						SUBTOTAL	45	170	96	120	6	4

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
IL. ROUTE 336

DATE 3/30/06

DRAWN BY

CHECKED BY