

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	55-2	McDONOUGH	1025	43
STA.		TO STA.		
FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT		

RAMPS AND SIDE ROADS- DRAINAGE SCHEDULE						TRENCH BACKFILL	INLET AND PIPE PROTECTION	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	STEEL PIPE CULVERT, SPECIAL (JACKED)
LOCATION						CU YD	EA	EA	24" FT
RAMP I									
STA. 20+00.00	22.80 FT	RT	TO	STA. 20+00.00	54.80 FT	LT			
STA. 27+00.00	41.00 FT	RT	TO	STA. 27+00.00	53.00 FT	LT		1	
RAMP J									
STA. 157+00.00	34.00 FT	LT	TO	STA. 157+00.00	18.00 FT	RT		1	
STA. 165+00.00	13.00 FT	RT	TO	STA. 165+00.00	28.40 FT	LT		1	
STA. 181+80.00	48.00 FT	RT	TO	STA. 182+21.70	22.80 FT	RT		1	1
US ROUTE 136 (RELOCATED)									
STA. 5+17.90	39.20 FT	LT						1	
STA. 5+24.00	37.10 FT	RT						1	
STA. 9+50.00	38.00 FT	LT	TO	STA. 9+50.00	36.00 FT	RT		1	
STA. 21+24.50	46.16 FT	RT	TO	STA. 21+75.00	46.83 FT	RT		1	
US 136 Temporary Runaround									
STA. 203+60.00	30.80 FT	LT							1
STA. 204+33.10	63.40 FT	LT						1	
SERVICE DRIVE									
STA. 16+80.00	22.50 FT	RT	TO	STA. 17+28.00	22.90 FT	RT		1	
STA. 18+85.90	26.60 FT	RT	TO	STA. 19+54.20	48.80 FT	RT		1	
STA. 21+50.00	19.20 FT	RT	TO	STA. 21+50.00	20.50 FT	LT		1	
STA. 24+24.00	66.90 FT	RT	TO	STA. 24+62.00	50.00 FT	LT		1	
TWP. ROAD 350E									
STA. 8+70.00	72.50 FT	LT	TO	STA. 8+75.00	42.90 FT	LT		1	1
STA. 8+75.00	42.90 FT	LT	TO	STA. 8+88.50	38.00 FT	RT		1	
TWP. ROAD 118									
STA. 17+90.00	28.80 FT	LT	TO	STA. 17+90.00	29.20 FT	RT		1	
STA. 18+94.00	34.00 FT	LT	TO	STA. 18+94.00	31.00 FT	RT		1	
STA. 21+10.00	35.60 FT	LT	TO	STA. 21+10.00	28.40 FT	RT		1	
COUNTY HIGHWAY 8 (RELOCATED)/TWP. ROAD 150									
STA. 26+25.00	20.90 FT	LT	TO	STA. 26+65.00	24.60 FT	RT	34.4	1	
STA. 26+80.00	28.70 FT	LT	TO	STA. 27+20.00	28.80 FT	LT		1	
STA. 35+50.00	20.00 FT	RT	TO	STA. 35+50.00	23.00 FT	LT	14.8	1	
COUNTY HIGHWAY 8 (EAST)									
STA. 38+86.00	44.00 FT	LT	TO	STA. 38+90.00	40.00 FT	RT	71.5	1	
TWP. ROAD 900N (WEST)									
STA. 20+61.00	42.00 FT	LT	TO	STA. 20+68.00	43.00 FT	RT	19.7	1	
TWP. ROAD 194									
STA. 49+03.00	35.00 FT	LT	TO	STA. 49+07.00	32.40 FT	RT		1	
TWP. ROAD 200 (RELOCATED)									
STA. 50+74.00	25.50 FT	RT	TO	STA. 51+24.00	27.20 FT	RT		1	
STA. 54+03.00	24.00 FT	LT	TO	STA. 54+28.07	30.70 FT	RT		1	
STA. 54+35.00	23.00 FT	LT	TO	STA. 54+35.00	26.00 FT	RT		1	
STA. 56+45.00	24.75 FT	LT	TO	STA. 56+72.00	24.75 FT	LT		1	
STA. 58+83.00	73.40 FT	LT	TO	STA. 59+07.00	33.60 FT	RT		1	
STA. 60+99.00	33.70 FT	LT	TO	STA. 61+16.00	41.10 FT	RT		1	
STA. 65+21.00	24.40 FT	LT	TO	STA. 64+68.00	24.30 FT	LT		1	
STA. 65+22.00	22.60 FT	RT	TO	STA. 64+69.00	24.00 FT	RT		1	
TWP. ROAD 900N (RELOCATED)									
STA. 86+80.00	27.80 FT	RT	TO	STA. 87+20.00	27.80 FT	RT		1	
STA. 89+48.00	23.00 FT	LT	TO	STA. 89+48.00	37.00 FT	RT		1	
STA. 89+70.00	36.00 FT	LT	TO	STA. 89+53.50	38.00 FT	RT		1	
TWP. ROAD 900N (EAST)									
STA. 100+50.00	18.50 FT	LT	TO	STA. 100+50.00	21.50 FT	RT		1	
TWP. ROAD 226 (RELOCATED)									
STA. 103+10.00	52.60 FT	LT	TO	STA. 103+93.70	67.70 FT	LT		1	
STA. 107+02.00	52.90 FT	LT	TO	STA. 106+44.00	53.30 FT	LT		1	
STA. 107+66.00	54.86 FT	RT	TO	STA. 106+96.00	70.00 FT	RT		1	
RAILROAD SHOO-FLY									
STA. 19+50.00	80.00 FT	LT	TO	STA. 19+50.00	80.00 FT	RT		1	160
SUBTOTAL						140.4	41	3	160
TOTAL						141	41	3	160

RAMPS AND SIDE ROADS- CLASS D PIPE CULVERT AND END SECTION SCHEDULE																		
LOCATION	PIPE CULVERTS, CLASS D, TYPE 1					PIPE CULVERTS, CLASS D, TYPE 2	PIPE CULVERTS, CLASS D, TYPE 2	PIPE CULVERTS, CLASS D, TYPE 3	METAL END SECTIONS									
	15" FT	18" FT	21" FT	24" FT	30" FT	18" FT	30" FT	30" FT	15" EA	18" EA	21" EA	24" EA	30" EA					
US ROUTE 136 (RELOCATED)																		
STA. 4+79.00	38.30 FT	RT	TO	STA. 5+24.00	37.10 FT	RT							2					
STA. 4+79.60	43.90 FT	LT	TO	STA. 5+17.90	39.20 FT	LT							2					
STA. 21+24.50	46.16 FT	RT	TO	STA. 21+75.20	46.83 FT	RT		51					2					
SERVICE DRIVE																		
STA. 16+80.00	22.50 FT	RT	TO	STA. 17+28.00	22.90 FT	RT							2					
STA. 18+85.90	26.60 FT	RT	TO	STA. 19+54.20	48.80 FT	RT							2					
TWP. ROAD 118																		
STA. 16+01.00	27.20 FT	RT	TO	STA. 16+43.00	29.20 FT	RT		41					2					
STA. 23+82.00	23.50 FT	RT	TO	STA. 24+18.00	23.50 FT	RT							2					
COUNTY HIGHWAY 8 (RELOCATED)/TWP. ROAD 150																		
STA. 26+80.00	28.70 FT	LT	TO	STA. 27+20.00	28.80 FT	LT		40					2					
TWP. ROAD 900N (WEST)																		
STA. 20+61.00	42.00 FT	LT	TO	STA. 20+68.00	43.00 FT	RT							4					
TWP. ROAD 200 (RELOCATED)																		
STA. 50+74.00	25.50 FT	RT	TO	STA. 51+24.00	27.20 FT	RT		50					2					
STA. 56+42.00	24.75 FT	LT	TO	STA. 56+76.00	24.75 FT	LT		34					2					
STA. 65+21.00	24.40 FT	LT	TO	STA. 64+68.00	24.30 FT	LT							2					
STA. 65+22.00	22.60 FT	RT	TO	STA. 64+69.00	24.00 FT	RT				54			2					
TWP. ROAD 900N (RELOCATED)																		
STA. 86+80.00	27.80 FT	RT	TO	STA. 87+20.00	27.80 FT	RT							40					
TWP. ROAD 226 (RELOCATED)																		
STA. 103+10.00	52.60 FT	LT	TO	STA. 103+93.70	67.70 FT	LT							102					
STA. 107+02.00	52.90 FT	LT	TO	STA. 106+44.00	53.30 FT	LT							58					
STA. 107+66.00	54.86 FT	RT	TO	STA. 106+96.00	70.00 FT	RT							72					
TWP. ROAD 64																		
STA. 703+74.50	19.70 FT	RT	TO	STA. 704+25.50	19.46 FT	RT		51					2					
FIELD ENTRANCE @ IL. ROUTE 336 - STA. 140+00 RT.																		
STA. 13+35.00	20.00 FT	RT	TO	STA. 13+70.00	21.00 FT	RT							35					
US 136 Temporary Runaround																		
STA. 198+38.90	25.00 FT	LT	TO	STA. 203+60.00	30.80 FT	LT							520					
STA. 203+60.00	30.80 FT	LT	TO	STA. 204+33.10	63.40 FT	LT							80					
TOTAL						51	364	54	258	40	222	600	102	2	24	2	8	6

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
IL. ROUTE 336
 DATE 3/30/06
 DRAWN BY
 CHECKED BY