

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	55-2	McDONOUGH	1025	52
STA.		TO STA.		
FED. ROAD DIST. NO. 4 ILLINOIS		FED. AID PROJECT		

ILL 336, RAMPS AND CROSS-OVER PAVING SCHEDULE														
LOCATION	PROCESSING MODIFIED SOILS 12"	PROCESSING MODIFIED SOIL 24"	LIME	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SUB-BASE GRANULAR MATERIAL, TYPE A 24"	SUB-BASE GRANULAR MATERIAL, TYPE A 18"	BITUMINOUS MATERIALS (PRIME COAT)	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), TYPE 2 13 1/4"	BITUMINOUS SHOULDERS SUPERPAVE 8"	SUB-BASE GRANULAR MATERIAL, TYPE C	AGGREGATE SHOULDERS, TYPE B	BITUMINOUS CONCRETE SURFACE COURSE MIX D SUPERPAVE, N70 2"	BITUMINOUS BASE COURSE SUPERPAVE 8"	BITUMINOUS SHOULDERS SUPERPAVE 6"
	SQ YD	SQ YD	TON	SQ YD	SQ YD	SQ YD	TON	SQ YD	SQ YD	CU YD	TON	TON	SQ YD	SQ YD
ILL 336 EAST BOUND LANES														
STA. 128+00.00 TO STA. 152+38.70	11,582.7		258.0				0.9	7,199.3	3,761.5	1,138.1	664.0			
STA. 155+66.80 TO STA. 183+80.40			288.3				1.0	8,724.3	4,083.5	1,285.1	714.1			
STA. 183+18.30 TO STA. 184+43.40				1,104.0										
STA. 183+80.40 TO STA. 237+80.70							1.9	15,914.7	8,067.5	2,504.8	1,701.6			
STA. 184+43.40 TO STA. 237+18.00	24,268.5		540.6											
STA. 237+18.00 TO STA. 238+42.40				1,103.5										
STA. 237+80.70 TO STA. 275+00.00							1.3	10,948.2	5,728.5	1,728.0	1,172.0			
STA. 238+42.40 TO STA. 275+00.00	17,119.0		381.3											
STA. 275+00.00 TO STA. 324+52.20							1.8	14,657.4	7,831.6	2,349.4	1,576.9			
STA. 275+00.00 TO STA. 323+69.00	22,927.2		510.7											
STA. 323+69.00 TO STA. 325+53.30				1,375.2										
STA. 324+52.20 TO STA. 349+72.20							0.9	7,872.1	3,588.7	1,137.5	794.1			
STA. 325+53.30 TO STA. 348+92.60	10,629.6		236.8											
STA. 348+92.60 TO STA. 350+47.90				1,350.5										
STA. 349+72.20 TO STA. 376+71.30							1.0	8,256.2	3,879.3	1,230.8	850.5			
STA. 350+47.90 TO STA. 376+71.30	12,205.3		271.9											
STA. 376+71.30 TO STA. 405+14.40							1.1	9,238.8	4,094.6	1,274.9	901.9			
STA. 376+71.30 TO STA. 404+14.00	13,151.6		293.0											
STA. 404+14.00 TO STA. 406+14.80				1,709.9										
STA. 405+14.40 TO STA. 450+00.00							1.6	13,104.1	6,961.9	2,134.3	1,419.0			
STA. 406+14.80 TO STA. 450+00.00	20,434.2		455.2											
STA. 450+00.00 TO STA. 470+75.00	9,945.7		221.5				0.7	6,177.8	3,232.6	977.5	660.7			
STA. 470+75.00 TO STA. 493+40.10	10,291.3		229.2				0.7	6,174.1	3,532.2	1,070.8	649.6			
STA. 495+68.20 TO STA. 546+24.50							1.6	13,484.0	7,548.8	2,334.4	1,394.2			
STA. 495+68.20 TO STA. 500+80.00	2,296.8		51.2											
STA. 500+80.00 TO STA. 501+55.00		341.7	15.2											
STA. 501+55.00 TO STA. 515+80.00	6,398.1		142.5											
STA. 515+80.00 TO STA. 518+05.00		1,025.0	45.7											
STA. 518+05.00 TO STA. 525+50.00	3,338.7		74.4											
STA. 525+50.00 TO STA. 535+60.00						4,713.3								
STA. 535+60.00 TO STA. 538+50.00	1,299.6		28.9											
STA. 538+50.00 TO STA. 539+50.00				528.0										
STA. 539+50.00 TO STA. 546+24.50	2,650.4		59.0											
ILL 336 WEST BOUND LANES														
STA. 128+00.00 TO STA. 153+49.60	12,765.3		284.3				1.0	8,453.3	3,851.3	1,572.9	664.0			
STA. 156+78.00 TO STA. 183+80.40			263.0				0.9	7,454.9	4,167.7	1,277.2	714.1			
STA. 183+18.30 TO STA. 184+43.40	11,807.1			1,107.0										
STA. 183+80.40 TO STA. 237+80.70							1.9	15,893.0	8,062.5	2,500.3	1,701.6			
STA. 184+43.40 TO STA. 237+18.00	24,263.3		540.5											
STA. 237+18.00 TO STA. 238+42.40				1,008.1										
STA. 237+80.70 TO STA. 275+00.00							1.4	11,418.1	5,713.4	1,728.0	1,172.0			
STA. 238+42.40 TO STA. 275+00.00	17,569.1		391.4											
STA. 275+00.00 TO STA. 324+52.20							1.7	14,357.8	7,651.6	2,349.4	1,576.9			
STA. 275+00.00 TO STA. 323+69.00	22,545.9		502.2											
STA. 323+69.00 TO STA. 325+53.30				1,664.4										
STA. 324+52.20 TO STA. 349+72.20							1.0	8,221.0	3,599.9	1,123.0	794.1			
STA. 325+53.30 TO STA. 348+92.60	11,070.2		246.6											
STA. 348+92.60 TO STA. 350+47.90				963.7										
STA. 349+72.20 TO STA. 376+71.30							1.0	7,927.1	4,172.5	1,279.1	850.5			
STA. 350+47.90 TO STA. 376+71.30	12,305.4		274.1											
STA. 376+71.30 TO STA. 405+14.40							1.0	8,503.0	4,373.5	1,339.0	901.9			
STA. 376+71.30 TO STA. 404+14.00	12,810.2		285.3											
STA. 404+14.00 TO STA. 406+14.80				1,709.4										
STA. 405+14.40 TO STA. 450+00.00							1.7	14,024.4	6,603.1	2,071.6	1,419.0			
STA. 406+14.80 TO STA. 450+00.00	20,859.1		464.6											
STA. 450+00.00 TO STA. 470+75.00	9,455.8		210.6				0.7	5,753.0	3,170.3	977.5	660.7			
STA. 470+75.00 TO STA. 493+79.80							0.8	6,344.4	3,539.4	1,089.7	649.6			
STA. 470+75.00 TO STA. 489+40.00	8,525.4		189.9											
STA. 489+40.00 TO STA. 490+90.00		683.3	30.4											
STA. 490+90.00 TO STA. 493+79.80	1,284.5		28.6											
STA. 496+13.00 TO STA. 541+57.10							1.4	12,078.8	6,108.6	1,939.5	1,394.2			
STA. 496+13.00 TO STA. 515+80.00	8,666.9		193.1											
STA. 515+80.00 TO STA. 519+30.00		1,685.6	75.1											
STA. 519+30.00 TO STA. 527+65.00	3,742.0		83.4											
STA. 527+65.00 TO STA. 535+60.00						3,796.7								
STA. 535+60.00 TO STA. 538+50.00	939.8		20.9											
STA. 538+50.00 TO STA. 539+50.00				528.0										
STA. 539+50.00 TO STA. 541+57.10	671.3		15.0											
RAMP I														
STA. 10+32.40 TO STA. 42+39.96							0.7	6,159.4	3,286.7	929.6	714.1			
STA. 10+32.40 TO STA. 18+75.00					2,644.4									
STA. 18+75.00 TO STA. 39+87.10	6,057.3		134.9											

CONVERSION RATES
 ASPHALT: 112 LB/SQ YD IN
 AGGREGATE = 2.05 TON/CU YD
 0.004 TONS = GALLON

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
IL. ROUTE 336

DATE 3/30/06
 DRAWN BY
 CHECKED BY

SCHEMATIC: 5/7/2006 11:00 PM