F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	55-2	McDONOUGH	1025	696
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

UNLESS ELEVATIONS ARE SHOWN, ALL UTILITY LOCATIONS SHOWN ON THE CROSS SECTIONS ARE BASED ON THE APPROXIMATE DEPTH SUPPLIED BY THE UTILITY CO. & SHOULD BE FIELD VERIFIED BY CONTRACTOR

SCALE IN FEET

NOTE: SEE GRADING PLAN AND SERVICE DRIVE CROSS SECTIONS FOR ADDITIONAL INFORMATION

178+00.00

PROP. R.O.W.
668.00
1:3
1:6
671.59
178+00.00
668.72
671.59
1:6
1:3
EX. R.O.W.
EARTHWORK MATCH LINE
658.00
EX. FIBER OPTIC
EX. TEL.
660.57
20+72.23 EX. R.O.W.
SERVICE DRIVE
659.10
1:3
1:3
PROP. R.O.W.

C=443
F=348
TOPSOIL EXCAVATION=12
TOPSOIL PLACEMENT=144 FT

177+00.00

TEMP. EASE.
PROP. R.O.W.
665.00
1:6
1:3
177+00.00
671.41
668.42
671.41
1:6
1:3
EX. R.O.W.
660.50
EARTHWORK MATCH LINE
19+71.08
SERVICE DRIVE
EX. R.O.W.
666.01
1:20
EX. TEL.
EX. FIBER OPTIC
℄ STA. 176+37.65
INLETS, TY. B, WITH
MEDIAN INLET (604101) SPECIAL
GRATE ELEV. = 668.20
STA. 176+75.7, 104.4' RT.
INLETS, TYPE B, WITH
MEDIAN INLET (604101) SPECIAL
GRATE ELEV. = 659.64
EXISTING GROUND LINE
FOLLOWS STREAM ℄
PAST END OF CULVERT
PROP. R.O.W. (AH)
END AGGREGATE DITCH
LT. STA. 177+00
℄ STA. 176+37.65, SKEW 20° 2' RF,
300 FT., PRECAST CONCRETE
BOX CULVERT 9' X 5' @ 0.55% SLOPE
STA. 176+98.2, 165.7' RT.
BOX CULVERT END SECTIONS,
INV. = 650.50
STONE RIPRAP, CLASS B3
STILLING BASIN

C=67
F=1028
TOPSOIL PLACEMENT=112 FT
ROCK EXCAVATION TO 12" BELOW CULVERT

177+00.00

FINAL SURVEY: SURVEYED, PLOTTED, NOTE BOOK, AREAS, NO.
BY, DATE

ORIGINAL SURVEY: SURVEYED, PLOTTED, NOTE BOOK, AREAS CHECKED
By, DATE

PLOT DATE = $DATE$
FILE NAME = $FILE$
PLOT SCALE = $SCALE$
USER NAME = $USER$

338 sheets-1.dgn 3/30/2006 3:42:05 PM

CROSS SECTIONS – IL. ROUTE 336