


DESIGNED RB	 RANDOLPH & ASSOCIATES, INC. 111 W. FIDELITY PARKWAY, PEORIA, IL 61614-1001 TEL: 309.696.3344 FAX: 309.696.3345 WWW.RANDOLPHINC.COM CONSULTING ENGINEERS • LAND SURVEYORS	FILE NUMBER 136.115	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
CHECKED AMPH			6584	105R-1	PEORIA	115	7	
DRAWN AMPH		DATE June 2003	STA.	TO STA.				
CHECKED RB		FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT						

SUMMARY OF QUANTITIES (SHEET 3 of 3)

CONSTRUCTION TYPE CODE

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	100% STATE URBAN ROADWAY	
				I000-2A	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	50	50	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2257	2257	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	526	526	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	5532	5532	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	998	998	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	444	444	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	123	123	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	164	164	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	248	248	
* 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	526	526	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	5532	5532	
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	998	998	
* 78001140	PAINT PAVEMENT MARKING - LINE 8"	FOOT	444	444	
* 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	123	123	
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	164	164	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	349	349	
X0301007	INLET-MANHOLE, TYPE G-1, 4' -DIAMETER , SPECIAL	EACH	1	1	
X0322054	REMOVAL OF PRECAST FLARED END SECTION	EACH	4	4	
X0322494	CURB CUT	FOOT	69	69	
X4066412	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N30	TON	502	502	
X4066526	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N 70	TON	1284	1284	
X4066910	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE N 70	TON	286	286	
X4420500	TEMPORARY PAVEMENT PATCH	SQ YD	100	100	
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	8	8	
XX000321	INLET-MANHOLE, TYPE G-1, 5' - DIAMETER, SPECIAL	EACH	3	3	
XX001672	STORM SEWERS, (POLYVINYL CHLORIDE), SDR 26, 12 INCH	FOOT	53	53	
XX003570	STORM SEWERS, (POLYVINYL CHLORIDE), SDR 26, 15 INCH	FOOT	63	63	
XX004033	CLEAN EXISTING CULVERT	EACH	1	1	
Z0000990	AGGREGATE FOR TEMPORARY ACCESS	TON	289	289	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	
X0325440	CRACK & SEAT REVETMENT MAT	SQ YD	271	271	
X0325441	STORM SEWERS, (POLYVINYL CHLORIDE), SDR 26, 21 INCH	FOOT	47	47	
X0325442	INLET-MANHOLE, TYPE G-1, 6' - DIAMETER, SPECIAL	EACH	2	2	
X0325443	STORM SEWER, (POLYVINYL CHLORIDE) SDR 26, 33 INCH	FOOT	213	213	

*SPECIALTY ITEMS

SUMMARY OF QUANTITIES

ALLEN ROAD
 F.A.U. 6584 (SBI 174) SECTION 105R-1
 PEORIA COUNTY