


DESIGNED AMP/RR	 RANDOLPH & ASSOCIATES, INC. 111 N. FIFTH AVENUE, PEORIA, IL 61614-2124 TEL: 309-693-8844 FAX: 309-693-8855 • 1-800-951-1031 HTTP://WWW.RANDOLPHINC.COM CONSULTING ENGINEERS • LAND SURVEYORS	FILE NUMBER 136.115	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CHECKED RR		DATE February 2004	6584	105R-1	PEORIA	115	20
DRAWN AMP		STA.	TO STA.				
CHECKED RR		FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT					

COMBINATION CONCRETE CURB AND GUTTER SCHEDULE

LOCATION STATION TO STATION	LT/RT	DESCRIPTION	CCC&G B6.24	CCC&G B6.12	Subbase Granular Material Type A, 4"
			FOOT	FOOT	SQ YD
STA. 176+60.00 TO STA. 178+56.48	RT	Mainline	196.48		67.2
STA. 178+69.48 TO STA. 180+92.32	RT	Mainline	222.84		76.3
STA. 181+05.32 TO STA. 182+75.48	RT	Mainline	170.16		58.2
STA. 182+88.48 TO STA. 184+64.84	RT	Mainline	176.36		60.4
STA. 178+89.50 TO STA. 180+46.48	LT	Mainline	156.98		53.7
STA. 180+59.48 TO STA. 182+62.48	LT	Mainline	203.00		69.5
STA. 182+75.48 TO STA. 184+33.30	LT	Mainline	157.82		54.0
STA. 184+46.30 TO STA. 184+64.84	LT	Mainline	18.54		6.3
STA. 181+16.65	LT	Curb Lining Entrance		42.0	9.7
STA. 181+46.23	LT	Curb Lining Entrance		42.0	9.7
STA. 183+88.71	LT	Curb Lining Entrance		45.4	10.5
STA. 184+18.30	LT	Curb Lining Entrance		45.4	10.5
STA. 184+74.84 TO STA. 184+84.48	RT	Mainline	9.64		3.3
STA. 184+97.48 TO STA. 187+04.38	RT	Mainline	206.90		70.8
STA. 187+17.38 TO STA. 188+15.70	RT	Mainline	98.32		33.6
STA. 188+15.70 TO STA. 188+45.82	RT	NW Corner Altorfer & Allen	56.94		19.5
STA. 184+74.84 TO STA. 184+84.48	LT	Mainline	9.64		3.3
STA. 184+97.48 TO STA. 187+04.38	LT	Mainline	206.90		70.8
STA. 187+17.38 TO STA. 188+10.23	LT	Mainline	92.85		31.8
STA. 188+23.27 TO STA. 188+53.27	LT	NE Corner Altorfer & Allen	44.58		15.3
STA. 188+79.08 TO STA. 189+09.08	LT	SE Corner Altorfer & Allen	44.58		15.3
STA. 189+22.12 TO STA. 190+88.48	LT	Mainline	166.36		56.9
STA. 191+01.48 TO STA. 192+84.48	LT	Mainline	183.00		62.6
STA. 192+97.48 TO STA. 195+00.20	LT	Mainline	202.72		69.4
STA. 195+13.20 TO STA. 196+65.10	LT	Mainline	151.90		52.0
STA. 193+67.64 TO STA. 193+90.20	LT	NE Corner of Entrance		34.88	8.1
STA. 194+24.54	LT	Median		27.86	6.4
STA. 194+54.78 TO STA. 194+81.56	LT	SE Corner of Entrance		37.82	8.7
STA. 188+86.76 TO STA. 189+16.78	RT	SW Corner Altorfer & Allen	56.94		19.49
STA. 189+29.82 TO STA. 190+88.37	RT	Mainline	158.55		54.26
STA. 191+01.42 TO STA. 192+93.48	RT	Mainline	192.06		65.73
STA. 193+06.52 TO STA. 193+66.41	RT	Mainline	59.89		20.50
STA. 193+66.41 TO STA. 194+09.14	RT	NW Corner Future St. & Allen	55		18.82
STA. 194+44.45 TO STA. 194+87.16	RT	SW Corner Future St. & Allen	54.25		18.57
STA. 195+00.20 TO STA. 196+65.10	RT	Mainline	164.94		56.45
TOTAL			3518.14	275.36	1267.62

SUBBASE AND BASE COURSE SCHEDULE

LOCATION STATION TO STATION	BITUMINOUS BASE COURSE 12"	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	STRIP REFLECTIVE CRACK CONTROL TREATMENT SYSTEM A
	AREA SQ YD	AREA SQ YD	LENGTH FOOT
ALLEN ROAD MAIN LINE			
LT. STA. 178+89.50 TO LT. STA. 180+91.10	141.67	141.67	201.60
LT. STA. 180+91.10 TO LT. STA. 182+00.00	149.23	149.23	108.90
RT. STA. 180+91.10 TO RT. STA. 182+00.00	164.41	164.41	108.90
LT. STA. 182+00.00 TO LT. STA. 182+40.00	52.70	52.70	40.00
RT. STA. 182+00.00 TO RT. STA. 182+40.00	58.02	58.02	40.00
LT. STA. 182+40.00 TO LT. STA. 184+60.84	284.70	284.70	220.84
RT. STA. 182+40.00 TO RT. STA. 184+60.84	307.90	307.90	220.84
LT. STA. 184+77.84 TO LT. STA. 190+97.00	798.87	798.87	619.16
RT. STA. 184+77.84 TO RT. STA. 190+97.00	863.00	863.00	619.16
LT. STA. 190+97.00 TO LT. STA. 196+65.10	344.36	344.36	568.10
RT. STA. 190+97.00 TO RT. STA. 196+65.10	358.66	358.66	568.10
SIDE ROADS			
ALTORFER DRIVE @ STA. 188+66.47 LT & RT			
STA. 20+79.00 TO STA. 21+18.83		224.47	
STA. 21+80.84 TO STA. 22+21.30		159.11	
FUTURE STRET @ STA. 194+26.20 RT			
STA. 30+59.95 TO STA. 30+31.20		191.79	
TOTAL	3523.51	4098.88	3315.60

SUB-BASE GRANULAR MATERIAL TYPE A 4" SUMMARY

SCHEDULE	SQ YDS
SUBBASE & BASE COURSE SCHEDULE	4098.88
COMBINATION CONC. CURB & GUTTER SCHEDULE	1267.62
TOTAL	5366.50

SCHEDULE OF QUANTITIES

ALLEN ROAD
F.A.U. 6584 (SBI 174) SECTION 105R-1
PEORIA COUNTY