


DESIGNED AMPH/RB	 RANDOLPH & ASSOCIATES, INC. 111 N. PEORIA PARKWAY, PEORIA, IL 61624-2124 TEL. 309.691.9544 FAX. 309.691.9541 RTFA/22XXX.RANDOLPH.IL.CORP. CONSULTING ENGINEERS • LAND SURVEYORS	FILE NUMBER 136.115	F.A.U. RTE. 6584	SECTION 105R-1	COUNTY PEORIA	TOTAL SHEETS 115	SHEET NO. 23
CHECKED RB		DATE February 2004	STA.	TO STA.		FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT	
DRAWN AMP							
CHECKED RB							

PAINT PAVEMENT MARKING & TEMPORARY PAVEMENT MARKING															
LEGEND * ON PLANS	1	2	3	4	5	6	7	8	9	10	11	FOR INFO ONLY			
												TURN ARROW	RAILROAD "X"	RAILROAD "R"	
LOCATION STATION TO STATION	DISTANCE	4" YELLOW SKIP DASH	4" YELLOW	8" WHITE	6" WHITE SKIP DASH	4" WHITE	12" YELLOW	6" WHITE	24" WHITE	12" WHITE	4" DUAL YELLOW	LETTERS & SYMBOLS			
	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	SQ FT	#	#	#
☉ STA. 176+60.00 TO ☉ STA. 184+64.74	804.74	402.37	1609.48		402.37				82.00			254.00	8	3	6
☉ STA. 184+73.84 TO ☉ STA. 194+00.00	926.16	463.08	1852.32	77.20	463.08				82.00			271.60	10	3	6
☉ STA. 193+74.50 TO ☉ STA. 194+73.68	99.18			177.40											
☉ STA. 194+00.00 TO ☉ STA. 196+65.10	265.10				132.55										
☉ STA. 194+38.60 TO ☉ STA. 197+37.80	299.20					122.30					1204.50				
☉ STA. 198+95.35 TO ☉ STA. 199+56.30	60.95			102.30											
☉ STA. 202+65.66 TO ☉ STA. 203+16.12	50.46			86.80											
SUBTOTAL		865.45	3461.80	443.70	998.00	0.00	122.30	0.00	164.00	0.00	1204.50	525.60	18.00	6.00	12.00

PAINT PAVEMENT MARKING & TEMPORARY PAVEMENT MARKING TOTALS		
PAINT PAVEMENT MARKING & TEMPORARY PAVEMENT MARKING - LINE 4"	FEET	5532
PAINT PAVEMENT MARKING & TEMPORARY PAVEMENT MARKING - LINE 6"	FEET	998
PAINT PAVEMENT MARKING & TEMPORARY PAVEMENT MARKING - LINE 8"	FEET	444
PAINT PAVEMENT MARKING & TEMPORARY PAVEMENT MARKING - LINE 12"	FEET	123
PAINT PAVEMENT MARKING & TEMPORARY PAVEMENT MARKING - LINE 24"	FEET	164
PAINT PAVEMENT MARKING & TEMPORARY PAVEMENT MARKING - LETTERS & SYMBOLS	SQ FT	526

SHORT-TERM PAVEMENT MARKING			
LOCATION STATION TO STATION	NO. OF APPLICATIONS	APPLIED	LENGTH
			FEET
STA. 176+60.00 TO STA. 184+64.74	3	N. BOUND CENTERLINE	219.48
STA. 176+60.00 TO STA. 184+64.74	3	TURN LANE EDGELINES	438.95
STA. 176+60.00 TO STA. 184+64.74	3	S. BOUND CENTERLINE	219.48
STA. 184+73.84 TO STA. 197+37.80	3	N. BOUND CENTERLINE	344.72
STA. 184+73.84 TO STA. 197+37.80	3	TURN LANE EDGELINES	689.43
STA. 184+73.84 TO STA. 197+37.80	3	S. BOUND CENTERLINE	344.72
TOTAL			2256.77

WORK ZONE PAVEMENT MARKING REMOVAL		
LOCATION STATION TO STATION	APPLIED	AREA
		SQ FT
STA. 176+60.00 TO STA. 184+64.74	N. BOUND CENTERLINE	24.14
STA. 176+60.00 TO STA. 184+64.74	TURN LANE EDGELINES	48.28
STA. 176+60.00 TO STA. 184+64.74	S. BOUND CENTERLINE	24.14
STA. 184+73.84 TO STA. 197+37.80	N. BOUND CENTERLINE	37.92
STA. 184+73.84 TO STA. 197+37.80	TURN LANE EDGELINES	75.84
STA. 184+73.84 TO STA. 197+37.80	S. BOUND CENTERLINE	37.92
TOTAL		248.24

PAVEMENT MARKING REMOVAL		
LOCATION STATION TO STATION	APPLIED	AREA
		SQ FT
STA. 176+60.00 TO STA.180+36.10	TURN LANE SOLID	250.73
STA. 176+60.00 TO STA.180+36.10	TURN LANE SKIP DASH	62.68
STA. 176+60.00 TO STA. 180+36.10	4 TURN ARROWS	35.20
TOTAL		348.62

SCHEDULE OF QUANTITIES

 ALLEN ROAD
 F.A.U. 6584 (SBI 174) SECTION 105R-1
 PEORIA COUNTY