

FBI	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39		WOODFORD	12	4
STA. VARIOUS		TO STA. VARIOUS		
FED. ROAD DIST. NO. 3		ILLINOIS FED. AID PROJECT		
* D4 CONC MEDIAN REPAIR 2007				

SCHEDULE OF QUANTITIES

MOBILIZATION

JOBSITES = 1.0 LSUM

TRAFFIC CONTROL & PROT. STD. 701201

JOBSITES = 1.0 LSUM

TRAFFIC CONTROL & PROT. STD. 701602

JOBSITES = 1.0 LSUM

PAVEMENT MARKING TAPE, TYPE I, 4"

SN. 102-0047 = 700 FOOT
 SN. 102-0049 = 704 FOOT

CONCRETE MEDIAN REMOVAL

SN. 102-0047 = 567 SQ.FT.
 SN. 102-0049 = 594 SQ.FT.

REINFORCEMENT BARS, EPOXY COATED

SN. 102-0047 = 2277 LBS.
 SN. 102-0049 = 1287 LBS.

CONCRETE SUPERSTRUCTURE

SN. 102-0047 = 21 CU.YD.
 SN. 102-0049 = 22 CU.YD.

PROTECTIVE COAT

SN. 102-0047 = 1778 SQ.YD.
 SN. 102-0049 = 1895 SQ.YD.

PRISMATIC CURB REFLECTOR

CH2 BRIDGE MEDIAN = 64 EACH
 IL. 116 BRIDGE MEDIAN = 64 EACH

PLT DATE * DATE *
 PLOT NAME * NAME *
 PLOT SCALE * SCALE *
 USER NAME * USER *

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT.
 HORIZ.
 DATE 12-20-2005

DRAWN BY CEJ
 CHECKED BY