CONTRACT NO. 68600

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
646	(103-1)N-5,TS	PEORIA		8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

44000100 - PAVEMENT REMOVAL

LOCATION	SQ YD
STA. 137+12.6 TO 1+17.8 (EX. TURNLANE)	186.50
NE ISLAND AREA FOR STAGING	18.60
STA. 139+32.3 TO 2+47.6 (MEDIAN AREA)	79.30

CONCRETE

LOCATION	60605000 - COMB. CONC. CURB AND GUTTER, TYPE B-6.24	60622320 - CONCRETE MEDIAN, TYPE SM-6.24	31100300 - SUB-BASE GRANULAR MATERIAL, TYPE A 4"	35300500 - PORTLAND CEMENT CONCRETE BASE COURSE 10"
	FOOT	SQ. FT.	SQ. YD.	SQ. YD.
PROSPECT RD. AND KNOXVILLE (IL 40)				
STA. 0+71.2 TO 2+45.8		1775.1	276.5	
STA. 1+17.8 TO 137+36.8	301.1		86.4	
NE QUAD. ISLAND PORTION FOR STAGING			18.6	18.6
LIMITS OF EXIST. NE QUADRANT ISLAND			46.6	46.6
TOTAL	301	1775	428	65

44000500 - COMB. CURB & GUTTER REMOVAL

LOCATION	FOOT
KNOXVILLE (IL 40)	
LT. STA. 137+36.8 TO LT. STA. 2+01.1	321.5
PROSPECT RD.	
MEDIAN	249
RT. STA. 2+00 (PROP. SIDEWALK RAMP)	5
RT. STA. 2+45.7 (PROP. SIDEWALK RAMP)	5
TOTAL	581

42400100 - PORTLAND CEMENT CONCRETE SIDEWALK 4"

LOCATION	SQ FT
PROSPECT RD.	
LT. STA. 0+50 TO 2+00	823.5
RT. STA. 2+00 TO 2+45	287.5
KNOXVILLE RD.	
LT. STA. 137+66 TO 138+88.4	612.5
TOTAL	1723.5

42400800 - DETECTABLE WARNINGS

LOCATION	SQ FT
SIDEWALK RAMPS (4 LOCATIONS)	24
TOTAL	24.0

44002800 - ISLAND PAVEMENT REMOVAL

LOCATION	SQ YD
PROSPECT RD.	
LT. STA. 0+66	65.24
TOTAL	65

*REMOVAL AREA'S MATCH LIMITS OF PROPOSED ISLANDS

60500060 - REMOVING INLETS

LOCATION	EACH
PROSPECT RD.	
LT. STA. 0+71	1
KNOXVILLE RD.- IL 40	
LT. STA. 138+05	1
TOTAL	2

44000100 - PAVEMENT REMOVAL

LOCATION	SQ YD
STA. 137+12.6 TO 1+17.8 (EX. TURNLANE)	186.50
NE ISLAND AREA FOR STAGING	18.60
STA. 139+32.3 TO 2+47.6 (MEDIAN AREA)	79.30
TOTAL	284

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = 3/31/2006
FILE NAME = c:\projects\safety\1148_prospect\msao.dgn
PLOT SCALE = 40.0000 ' / IN.
USER NAME = ghudnsan