

SCHEDULE OF QUANTITIES

CONTRACT NO. 70119				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	*	VERMILION	30	11
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
*(RX,48Z-1RS-1&(47R-1RS				

THERMOPLASTIC PAVEMENT MARKING - 4" YELLOW (SKIP-DASH)

STA.	TO	STA.	S.B. O/S		N.B. O/S	FOOT
183+00		184+28	5.5' LT*	&	5.5' RT*	60
185+17		187+53	5.5' LT*	&	5.5' RT*	120
188+26		188+61	5.5' LT*	&	5.5' RT*	20
191+26		194+64	5.5' LT*	&	5.5' RT*	180
195+36		199+62	5.5' LT*	&	5.5' RT*	220
200+82		203+31	5.5' LT*	&	5.5' RT*	140
204+29		210+04	5.5' LT*	&	5.5' RT*	300
214+39		218+65	5.5' LT	&	5.5' RT	220
219+32		222+58	5.5' LT	&	5.5' RT	160
226+94		230+43	5.5' LT	&	5.5' RT	180
234+72		238+26	5.5' LT	&	5.5' RT	180
239+23		240+52	5.5' LT	&	5.5' RT	60
244+93		251+25	5.5' LT	&	5.5' RT	320
TOTAL =						2,160

* - O/S TO CONSTRUCTION CENTER LINE

THERMOPLASTIC PAVEMENT MARKING - 4" YELLOW (SOLID)

STA.	TO	STA.	S.B. O/S		N.B. O/S	FOOT
183+00		184+28	6' LT*	&	6' RT*	256
185+17		187+53	6' LT*	&	6' RT*	472
188+26		188+61	6' LT*	&	6' RT*	70
191+26		194+64	6' LT*	&	6' RT*	676
195+36		199+62	6' LT*	&	6' RT*	852
200+82		203+31	6' LT*	&	6' RT*	498
204+29		210+04	6' LT*	&	6' RT*	1150
214+39		218+65	6' LT	&	6' RT	852
219+32		222+58	6' LT	&	6' RT	652
226+94		230+43	6' LT	&	6' RT	698
234+72		238+26	6' LT	&	6' RT	708
239+23		240+52	6' LT	&	6' RT	258
244+93		251+25	6' LT	&	6' RT	1264
TOTAL =						8,406

* - O/S TO CONSTRUCTION CENTER LINE

THERMOPLASTIC PAVEMENT MARKING - 4" YELLOW (DOUBLE)

STA.	TO	STA.	O/S	FOOT
188+61		190+19	6' LT*	316
210+04		211+62	6' LT* TO 6' LT	316
212+81		214+39	6' RT	316
222+58		224+16	6' LT	316
225+36		226+94	6' RT	316
230+43		232+01	6' LT	316
233+14		234+72	6' RT	316
240+52		242+10	6' LT	316
243+35		244+93	6' RT	316
TOTAL =				2,844

* - O/S TO CONSTRUCTION CENTER LINE

THERMOPLASTIC PAVEMENT MARKING - 4" WHITE (SKIP-DASH)

STA.	TO	STA.	S.B. O/S		N.B. O/S	FOOT
183+00		184+28	17' LT*	&	17' RT*	60
185+17		187+53	17' LT*	&	17' RT*	120
188+26		190+19	17' LT*	&	17' RT*	100
191+26		194+64	17' LT*	&	17' RT*	180
195+36		199+62	17' LT*	&	17' RT*	220
200+82		203+31	17' LT* TO 18' LT*	&	17' RT* TO 18' RT*	140
204+29		211+62	18' LT* TO 18' LT	&	18' RT* TO 18' RT	380
212+81		218+65	18' LT	&	18' RT	300
219+32		224+16	18' LT	&	18' RT	240
225+36		232+01	18' LT	&	18' RT	340
233+14		238+26	18' LT	&	18' RT	260
239+23		242+10	18' LT	&	18' RT	140
243+35		251+25	18' LT	&	18' RT	400
TOTAL =						2,880

* - O/S TO CONSTRUCTION CENTER LINE

THERMOPLASTIC PAVEMENT MARKING - 4" WHITE (SOLID)

STA.	TO	STA.	O/S	FOOT
189+21		190+19	6' RT	98
210+24		211+40	30' RT	115
210+64		211+62	6' RT	98
212+81		213+79	6' LT	98
222+80		224+16	30' RT	136
223+18		224+16	6' RT	98
223+36		224+34	6' LT	98
231+03		232+01	6' RT	98
233+14		234+12	6' LT	98
241+12		242+10	6' RT	98
243+35		244+33	6' LT	98
TOTAL =				1,133
GRAND TOTAL =				17,423

* - O/S TO CONSTRUCTION CENTER LINE