

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
749	*	EDGAR	75	5

CONTRACT NO. 70134
 • 14RS-2,122RS-3 & (123NRS,14)BR

LOCATION OF WORK: FAP ROUTE 749 (IL ROUTE 133)
 SECTION 14RS-2, 122RS-3& (123NRS, 14)BR
 EDGAR COUNTY

STA 7+79.47	SN 023-2015	SN 023-2016	STA 623+25.00
TO	STA 280+24.00	STA 539+68.00	TO
STA 623+25.00	80% FED	80% FED	STA 694+92.30
80% FED	20% STATE	20% STATE	80% FED
20% STATE	1000	X028-2A	20% STATE
1000	X028-2A	X028-2A	1000

CODE NO	ITEM	CONSTRUCTION TYPE CODE#	UNIT	TOTAL QUANTITY	RURAL TWO-LANE	RURAL TWO-LANE	RURAL TWO-LANE	URBAN TWO-LANE
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2		EACH	1.0	0.0	1.0	0.0	0.0
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3		EACH	1.0	1.0	0.0	0.0	0.0
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4		EACH	1.0	0.0	0.0	1.0	0.0
50105210	REMOVE EXISTING CULVERTS		FOOT	67.0	67.0	0.0	0.0	0.0
51500100	NAME PLATES		EACH	4.0	2.0	1.0	1.0	0.0
54001001	BOX CULVERT END SECTION, CULVERT NO.1		EACH	2.0	2.0	0.0	0.0	0.0
54001002	BOX CULVERT END SECTION, CULVERT NO.2		EACH	2.0	0.0	2.0	0.0	0.0
54001003	BOX CULVERT END SECTION, CULVERT NO.3		EACH	2.0	2.0	0.0	0.0	0.0
54001004	BOX CULVERT END SECTION, CULVERT NO.4		EACH	2.0	0.0	0.0	2.0	0.0
54002060	EXPANSION BOLTS 3/4" X 12"		EACH	4.0	4.0	0.0	0.0	0.0
54020602	PRECAST CONCRETE BOX CULVERT 6' X 2' (M273)		FOOT	108.0	108.0	0.0	0.0	0.0
54020903	PRECAST CONCRETE BOX CULVERT 9' X 3' (M273)		FOOT	84.0	84.0	0.0	0.0	0.0
54021004	PRECAST CONCRETE BOX CULVERT 10' X 4' (M273)		FOOT	162.0	0.0	162.0	0.0	0.0
54021204	PRECAST CONCRETE BOX CULVERT 12' X 4' (M273)		FOOT	126.0	0.0	0.0	126.0	0.0
54213450	END SECTIONS 15"		EACH	4.0	4.0	0.0	0.0	0.0
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"		EACH	1.0	1.0	0.0	0.0	0.0
54248510	CONCRETE COLLAR		CU YD	0.3	0.3	0.0	0.0	0.0
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"		FOOT	12.0	12.0	0.0	0.0	0.0
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"		FOOT	89.0	89.0	0.0	0.0	0.0
• 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A		FOOT	2,075.0	1,075.0	475.0	525.0	0.0
• 63000005	STEEL PLATE BEAM GUARD RAIL, TYPE B		FOOT	400.0	200.0	100.0	100.0	0.0
• 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES		FOOT	275.0	75.0	100.0	100.0	0.0
• 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)		EACH	16.0	8.0	4.0	4.0	0.0
63200310	GUARDRAIL REMOVAL		FOOT	1,212.0	812.0	0.0	400.0	0.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A		CAL MO	10.0	10.0	0.0	0.0	0.0
67100100	MOBILIZATION		L SUM	1.0	0.9	0.0	0.0	0.1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201		L SUM	1.0	0.9	0.0	0.0	0.1
70100455	TRAFFIC CONTROL AND PROTECTION, STANDARD 701206		L SUM	1.0	1.0	0.0	0.0	0.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306		L SUM	1.0	0.9	0.0	0.0	0.1
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)		L SUM	1.0	1.0	0.0	0.0	0.0
70300100	SHORT-TERM PAVEMENT MARKING		FOOT	20,028.0	17,808.0	0.0	0.0	2,220.0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"		FOOT	153,567.0	133,480.5	0.0	0.0	20,086.5
70301000	WORK ZONE PAVEMENT MARKING REMOVAL		SQ FT	2,237.0	1,978.8	0.0	0.0	258.2
• 78001110	PAINT PAVEMENT MARKING - LINE 4"		FOOT	154,348.0	134,261.0	0.0	0.0	20,087.0
• SPECIALTY ITEMS						0.0	0.0	