

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
749	.	EDGAR	75	16

CONTRACT NO. 70134  
 • 14RS-2,122RS-3 & (123NRS,14)BR

# SCHEDULES OF QUANTITIES

## 44201815 CLASS D PATCH, TYPE II, 14" (CONT.)

STATION	DIRECTION	LENGTH (FT)	WIDTH (FT)	PATCH AREA TYPE II (SQ YD)
319+54	WB	6	12.5	8.3
323+41	WB	6	12.5	8.3
323+41	EB	6	12.5	8.3
326+34	EB	6	12.5	8.3
326+84	WB	8	12.5	11.1
330+78	WB	6	12.5	8.3
333+22	WB	6	12.5	8.3
333+73	WB	6	12.5	8.3
333+73	EB	6	12.5	8.3
335+20	WB	8	12.5	11.1
335+68	WB	8	12.5	11.1
336+66	WB	10	12.5	13.9
336+66	EB	6	12.5	8.3
337+16	WB	6	12.5	8.3
337+16	EB	6	12.5	8.3
346+98	WB	8	12.5	11.1
347+49	WB	6	12.5	8.3
347+49	EB	6	12.5	8.3
358+29	WB	8	12.5	11.1
358+78	WB	6	12.5	8.3
377+80	WB	6	12.5	8.3
378+28	WB	6	12.5	8.3
378+77	EB	8	12.5	11.1
379+29	WB	8	12.5	11.1
379+29	EB	6	12.5	8.3
379+78	WB	6	12.5	8.3
380+26	WB	8	12.5	11.1
384+67	WB	6	12.5	8.3
384+67	EB	6	12.5	8.3
385+16	WB	8	12.5	11.1
386+63	WB	6	12.5	8.3
386+63	EB	6	12.5	8.3
393+98	WB	8	12.5	11.1
398+93	WB	6	12.5	8.3
398+93	EB	6	12.5	8.3
404+34	WB	8	12.5	11.1
411+12	WB	8	12.5	11.1
411+12	EB	4	12.5	5.6
411+61	WB	6	12.5	8.3
412+60	WB	6	12.5	8.3
412+60	EB	6	12.5	8.3
413+08	WB	8	12.5	11.1
413+08	EB	6	12.5	8.3
413+58	WB	8	12.5	11.1
413+58	EB	6	12.5	8.3
416+03	EB	8	12.5	11.1
416+48	WB	8	12.5	11.1
475+80	WB	8	12.5	11.1
477+32	WB	6	12.5	8.3
477+32	EB	6	12.5	8.3
478+79	WB	6	12.5	8.3
478+79	EB	6	12.5	8.3
479+25	WB	8	12.5	11.1
479+25	EB	6	12.5	8.3
485+11	WB	6	12.5	8.3
486+16	WB	8	12.5	11.1
486+60	WB	6	12.5	8.3
488+63	EB	6	12.5	8.3
489+13	WB	8	12.5	11.1
492+02	WB	8	12.5	11.1
492+54	WB	6	12.5	8.3
494+04	WB	6	12.5	8.3
498+43	WB	6	12.5	8.3
498+43	EB	6	12.5	8.3
503+84	EB	10	12.5	13.9
504+32	WB	6	12.5	8.3
504+32	EB	6	12.5	8.3
505+29	WB	6	12.5	8.3
505+29	EB	6	12.5	8.3

STATION	DIRECTION	LENGTH (FT)	WIDTH (FT)	PATCH AREA TYPE II (SQ YD)
505+77	WB	6	12.5	8.3
506+28	WB	6	12.5	8.3
511+48	WB	4	12.5	5.6
511+48	EB	4	12.5	5.6
516+16	WB	8	12.5	11.1
516+16	EB	10	12.5	13.9
517+10	WB	8	12.5	11.1
517+10	EB	6	12.5	8.3
517+59	WB	6	12.5	8.3
517+59	EB	6	12.5	8.3
518+57	EB	6	12.5	8.3
519+56	WB	6	12.5	8.3
519+56	EB	6	12.5	8.3
520+54	WB	6	12.5	8.3
520+54	EB	6	12.5	8.3
522+98	WB	8	12.5	11.1
523+98	EB	6	12.5	8.3
533+28	WB	8	12.5	11.1
536+24	WB	10	12.5	13.9
536+24	EB	6	12.5	8.3
614+50	WB	6	12.5	8.3
622+83	WB	6	12.5	8.3
622+83	EB	6	12.5	8.3
623+80	WB	6	12.5	8.3
630+24	WB	8	12.5	11.1
634+18	WB	6	12.5	8.3
634+18	EB	6	12.5	8.3
				TOT 2,048.5
				USE = 2,049

## 44201819 CLASS D PATCH, TYPE III, 14"

STATION	DIRECTION	LENGTH (FT)	WIDTH (FT)	PATCH AREA TYPE III (SQ YD)
15+29	WB	12	13	17.3
147+05	WB	12	13	17.3
151+86	WB	15	13	21.7
346+58	WB	12	12.5	16.7
354+80	WB	12	12.5	16.7
389+98	WB	15	12.5	20.8
416+48	EB	12	12.5	16.7
				TOT 127.2
				USE = 128

## 44201821 CLASS D PATCH, TYPE IV, 14"

STATION	DIRECTION	LENGTH (FT)	WIDTH (FT)	PATCH AREA TYPE IV (SQ YD)
145+80	EB	20	13	28.9
8+76	BOX CULVERT #1 REMOVAL (STAGE 1) =			50.6
8+76	BOX CULVERT #1 REMOVAL (STAGE 2) =			52.5
280+24	BOX CULVERT #2 REMOVAL =			213.4
367+52	BOX CULVERT #3 REMOVAL =			103.9
539+68	BOX CULVERT #4 REMOVAL =			199.2
				TOT 648.5
				USE = 649

## PARTIAL DEPTH PATCHING

STATION	DIRECTION	EXISTING OVERLAY THICKNESS (INCHES)	LENGTH (FT)	WIDTH (FT)	X4401705 PARTIAL DEPTH REMOVAL (SQ YD)	Z0004800 BITUMINOUS MIXTURE FOR PATCHING (TON)
132+00	EB	5.25	120	6	80.0	37.0
136+70	WB	5.25	475	6	316.7	146.3
141+51	WB	5.25	131	6	87.3	40.3
145+80	WB	5.25	72	13.0	104.0	48.0
195+40	EB	5.25	92	6.0	61.3	28.3
					TOT 649.3	299.9
					USE = 650	300

## 48202600 BITUMINOUS SHOULDER SUPERPAVE 8"

STATION	STATION	LENGTH (FT)	WIDTH (FT)	SQ. YD.
244+00 RT.	247+00 RT.	300	3	100
				USE = 100 SQ. YD.

## 50105210 REMOVE EXISTING CULVERTS

STATION	FEET	TOTAL =
8+45 LT.	32.5	66.5
278+83 RT.	34.0	
		USE = 67 FEET

## 51500100 NAME PLATES

STATION	EACH
8+76	1
280+24	1
367+52	1
539+68	1
TOTAL = 4	
USE = 4 EACH	

## 54213450 END SECTIONS 15"

STATION	EACH
7+97.3 39.4' LT	1
8+44.0 38.3' LT	1
276+29.0 35.0' RT.	1
276+71.0 35.0' RT.	1
TOTAL = 4	
USE = 4 EACH	

## 54213663 PRC FLARED END SECTIONS, 18"

STATION	EACH
245+35 34.6' LT.	1
TOTAL = 1	

## 542A0223 PIPE CULVERT, CLASS A, TYPE 1, 18"

STATION	LENGTH (FT)
245+35 34.6' LT.	12.0
TOTAL = 12.0 FEET	