2/7/2006

SEC. 36, T. 14 N., R. 13 W., 3RD P.M.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
749	•	EDGAR	75	28
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 70134
• 14RS-2, 122RS-3 & (123NRS,14)BR

1"=20'
0' 5' 10' 15' 20' 40' 60'

TEMPORARY DITCH CHECKS

STATION	EACH
366+76 RT	1
367+01 LT	1
368+01 RT	1
368+01 LT	1

INLET AND PIPE PROTECTION

STATION	EACH
367+52 27' RT	1

REMOVE EXISTING STRUCTURE NO. 3
EXISTING S.N. 023-8305
STATION 367+52.00
R.C. BOX CULVERT 2 @ 6' x 3'

STA. 367+52.00, PROPOSED S.N. 023-8314
PRECAST BOX CULVERT 2 @ 9' x 3' x 42'
WITH BOX CULVERT END SECTIONS
CULVERT NO. 3 - 2 EACH
STA. 367+52.00, LT. 21.0', H=677.200
STA. 367+52.00, RT. 21.0', H=677.200

PLAN
SURVEYED BY
PLOTTED
ALIGNMENT CHECKED
RT. OF WAY CHECKED
DGN FILE NAME
NOTE BOOK
NO.
DATE

365+00 | 366 | 367 | 368 | 369 | ℄ IL. ROUTE 133 | 370+00 | 371

STA. 367+33.3

STA. 367+70.7

BENCHMARK 4399-26
A CHISELED SQUARE ON THE NORTH EAST CORNER OF THE NORTH HEADWALL OF STRUCTURE NUMBER 023-8305
ELEVATION = 681.27

PERIMETER EROSION BARRIER

STATION	TO	STATION	LENGTH
367+25 50' LT		367+79 50' LT	54'
367+25 50' RT		367+79 50' RT	54'

CLASS D PATCHING, TYPE IV, 14" = 103.9 SQ YD

PROFILE
SURVEYED BY
PLOTTED
GRADES CHECKED
BKM. NOTED
DGN FILE (GEOPAK)
NOTE BOOK
NO.
DATE

688 686 684 682 680 678 676 674 672

EXISTING PROFILE

EXISTING LEFT DITCH

EXISTING RIGHT DITCH

PROP. LEFT DITCH

PROP. RIGHT DITCH

	365+00	365+50	366+00	366+50	367+00	367+50	368+00	368+50	369+00	369+50	370+00	370+50	371+00
RIGHT DITCH	678.43	678.36	678.30	678.23	678.17 / 678.17	678.21 / 678.01	678.25 / 677.85	678.29 / 677.69	678.33 / 677.53	678.16 / 677.37	677.33 / 677.21	678.55 / 677.47	678.25 / 677.75
LEFT DITCH	678.85	678.83	678.81	678.78	678.76 / 682.42	678.70 / 682.40	678.65 / 678.65	678.60 / 678.29	678.54 / 677.94	678.30 / 677.58	677.40 / 677.23	678.41 / 677.54	678.34 / 677.90
	682.38 / 682.51	682.36 / 682.48	682.34 / 682.46	682.31 / 682.44	682.29 / 682.42	682.28 / 682.40	682.26 / 682.39	682.25 / 682.37	682.23 / 682.36	682.22 / 682.34	682.19 / 682.32	682.20 / 682.32	682.21 / 682.34

	368+50	369+00	369+50	370+00	370+50	371+00
RIGHT DITCH	678.33 / 678.33	678.37	678.41	678.51	678.62	678.72	678.82	678.95	679.08	679.21	679.34
LEFT DITCH	678.48 / 678.27	678.63 / 678.63	678.77 / 682.42	678.91	678.98	679.05	679.12	679.19	679.29	679.40	679.50	679.60
	682.24 / 682.36	682.27 / 682.39	682.29 / 682.42	682.32 / 682.45	682.41 / 682.54	682.50 / 682.63	682.59 / 682.72	682.68 / 682.81	682.80 / 682.93	682.92 / 683.05	683.04 / 683.17	683.16 / 683.29

c:\projects\d506400 (v8)\p&p20.dgn