

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET No.
315	34-5	HANCOCK	612	8
STA.		TO STA.		
FED. ROAD DIST. No.	ILLINOIS	FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

LOCATION OF WORK				CONSTRUCTION TYPE CODE			
CODE NO.	ITEM	UNIT	80% FED. 20% STATE TOTAL QUANTITY	ROADWAY 1000-2A	CULVERTS Y007	IMPACT ATTENUATORS SFTY-3N	HIGHWAY LIGHTING Y030-1E
44000400	GUTTER REMOVAL	FOOT	5,607	5,607	0	0	0
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	6,249	6,249	0	0	0
44002600	GUTTER OUTLET REMOVAL	FOOT	707	707	0	0	0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	12,560	12,560	0	0	0
48202000	BITUMINOUS SHOULDERS SUPERPAVE	TON	432	432	0	0	0
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	69,741	69,741	0	0	0
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	68	68	0	0	0
50102400	CONCRETE REMOVAL	CU YD	4.8	0.0	4.8	0.0	0.0
50105220	PIPE CULVERT REMOVAL	FOOT	2,602	2,602	0	0	0
50200100	STRUCTURE EXCAVATION	CU YD	103	103	0	0	0
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	18	18	0	0	0
50300225	CONCRETE STRUCTURES	CU YD	347.3	347.3	0.0	0.0	0.0
50500505	STUD SHEAR CONNECTORS	EACH	923	923	0	0	0
* 50700209	UNTREATED TIMBER LAGGING	SQ FT	2,699	2,699	0	0	0

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE:
DATE: MARCH 10, 2006

DRAWN BY: RG
CHECKED BY: JAC