

# SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET No.
315	34-5	HANCOCK	612	27
STA.		TO STA.		
FED. ROAD DIST. No.		ILLINOIS	FED. AID PROJECT	

EARTHWORK SCHEDULE													
LOCATION	DESCRIPTION	THEORETICAL		ROCK EXCAVATION	CHANNEL EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	TOPSOIL	ADJUSTED EARTHWORK			EXCESS (BORROW)	CUMMULATIVE EXCESS (BORROW)	FURNISHED EXCAVATION
		CUT	FILL					CUT	FILL	FILL X 1.25			
		(CU YD)											
MAINLINE	1152+00 TO 1166+50	0	0					0	0	0	0	0	0
	1166+50 TO 1182+00	1,316	20,498			200	556	1,316	20,498	25,623	-24,307	-24,307	19,445
	1182+00 TO 1196+00	135,343	6,554				789	135,343	6,554	8,193	127,150	102,843	-101,720
	1169+00 TO 1208+00	3,607	10,459				2,549	3,607	10,459	13,074	-9,467	93,376	7,573
	1208+00 TO 1221+00	48,746	28,666				1,101	48,746	28,666	35,833	12,913	106,289	-10,331
	1221+00 TO 1231+50	17,185	2,841				562	17,185	2,841	3,552	13,633	119,922	-10,907
	1231+50 TO 1244+00	50,892	37,682				1,811	50,892	37,682	47,103	3,789	123,711	-3,032
	1244+00 TO 1256+00	17,594	77,233				1,448	17,594	77,233	96,542	-78,948	44,763	63,158
	1256+00 TO 1270+00	141,665	13,405				1,982	141,665	13,405	16,757	124,908	169,671	-99,927
	1270+00 TO 1284+00	44,005	70,201				1,982	44,005	70,201	87,752	-43,747	125,924	34,997
	1284+00 TO 1297+00	5,046	31,634				1,245	5,046	31,634	39,543	-34,497	91,427	27,597
	1297+00 TO 1311+00	5,611	51,076				1,368	5,611	51,076	63,845	-58,234	33,193	46,587
	1311+00 TO 1325+00	3,256	76,671		1,025		1,339	3,256	76,671	95,839	-92,583	-59,390	74,066
	1325+00 TO 1338+00	1,455	54,649				2,211	1,455	54,649	68,312	-66,857	-126,247	53,485
	1338+00 TO 1352+00	6,174	93,281				1,923	6,174	93,281	116,602	-110,428	-236,675	88,342
	1352+00 TO 1366+00	36,789	5,378				1,336	36,789	5,378	6,723	30,066	-206,609	-24,053
	1366+00 TO 1380+00	28,350	30,828				1,367	28,350	30,828	38,535	-10,185	-216,794	8,148
	1380+00 TO 1392+50	2,968	32,140				1,007	2,968	32,140	40,175	-37,207	-254,001	29,766
	1392+50 TO 1406+00	40,229	20,177	17,593			1,986	40,229	20,177	25,222	15,007	-238,994	-12,006
	1406+00 TO 1418+00	2,494	5,265				778	2,494	5,265	6,582	-4,088	-243,082	3,270
TR 302		392	2,138					392	2,138	2,673	-2,281	-245,363	1,824
PE AT STA. 1254+00		1,788	17,426					1,788	17,426	21,783	-19,995	-265,358	15,996
CH 5		6,592	4					6,592	4	5	6,587	-258,771	-5,270
STAGE I TOTALS		601,497	688,206	17,593	1,025	200	27,340	601,497	688,206	860,268	-258,771	-258,771	207,008
STAGE II													
MAINLINE	1166+50 TO 1182+00	526	5,374			200	932	526	5,374	6,718	-6,192	-6,192	4,953
	1182+00 TO 1196+00	3,099	17,266				1,680	3,099	17,266	21,583	-18,484	-24,676	14,787
	1196+00 TO 1208+00	5,224	16,383				1,757	5,224	16,383	20,479	-15,255	-39,931	12,204
	1208+00 TO 1221+00	11,189	20,569				3,878	11,189	20,569	25,712	-14,523	-54,454	11,618
	1221+00 TO 1231+50	11,630	3,374					11,630	3,374	4,218	7,412	-47,042	-5,930
	1231+50 TO 1244+00	6,129	5,733					6,129	5,733	7,167	-1,038	-48,080	830
	1338+00 TO 1352+00	126	10,433				676	126	10,433	13,042	-12,916	-60,996	10,332
	1352+00 TO 1366+00	7,898	13,574				1,287	7,898	13,574	16,968	-9,070	-70,066	7,256
	1366+00 TO 1380+00	6,455	26,337				2,015	6,455	26,337	32,922	-26,467	-96,533	21,173
	1380+00 TO 1392+50	1,594	33,870				1,779	1,594	33,870	42,338	-40,744	-137,277	32,595
	1392+50 TO 1406+00	816	11,785				681	816	11,785	14,732	-13,916	-151,193	11,132
CH 31		8,967	6,622				1,292	8,967	6,622	8,278	689	-150,504	-552
PE CH 31		2,273	0					2,273	0	0	2,273	-148,231	-1,818
TR 213A		563	222				150	563	222	278	285	-147,946	-228
TR 221		926	2,899				340	926	2,899	3,624	-2,698	-150,644	2,158
STAGE II TOTALS		67,415	174,441	0	0	200	16,467	67,415	174,441	218,059	-150,644	-150,644	120,509

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SCHEDULES OF QUANTITIES

SCALE: DATE: MARCH 10, 2006

DRAWN BY: RG  
CHECKED BY: JAC

\*DGN-SPEC\*  
\*DATE-TIME\*  
\*REF01