

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET No.
315	34-5	HANCOCK	612	34
STA.		TO STA.		
FED. ROAD DIST. No.	ILLINOIS	FED. AID PROJECT		

PIPE CULVERT REMOVAL SCHEDULE												
STATION	OFFSET	LT/RT	STATION	OFFSET	LT/RT	TYPE	50105220 PIPE CULVERT REMOVAL (FOOT)	X0545000 BOX CULVERT REMOVAL (FOOT)	Z0013825 CONTROLLED LOW- STRENGTH MATERIAL (CU YD)	X0323092 HEADWALL REMOVAL (EACH)	COMMENTS	
1167+65	0		1171+83	0	RT	18" CMP	418					
1180+15	90	RT	1180+48	92	RT	18" CMP	33					
1180+65	14	RT	1181+26	22	RT	24" CMP	62					
1191+26	118	RT	1191+36	56	RT			64				
1196+45	51	RT	1196+45	135	RT	30" RCP	84					
1201+32	54	RT	1201+62	54	RT	18" CMP	30					
1208+63	41	RT	1209+05	40	RT	24" CMP	43					
1208+69	135	RT	1209+09	135	RT	18" CMP	40					
1209+75	133	RT	1210+27	131	RT	30" CMP	52					
1209+88	42	RT	1210+27	45	RT	18" CMP	39					
1222+53	184	RT	1222+97	36	RT	42" RCP	164				HEADWALL REMOVAL	
1225+93	50	RT	1225+93	138	RT	36" RCP	88				HEADWALL REMOVAL	
1235+40	77	RT	1235+82	57	RT	18" RCP	48					
1235+53	35	LT	1235+90	33	LT	12"	37					
1237+94	23	LT	1240+37	41	LT	12" RCP	240				INLET REMOVAL	
1240+38	40	LT	1240+43	46	RT	18" RCP	87				INLET REMOVAL	
1245+80	79	LT	1245+81	6	RT	6.5x8 BOX		332	2		EX DBL 6.5' x 8' BOX CULVERT - REMOVE HEADWALLS	
1248+61	81	LT	1249+16	75	LT	15" CMP	56					
1249+27	5	RT	1249+56	2	LT	12" CMP	31					
1253+01	71	LT	1253+76	97	LT	15" CMP	80					
1254+17	94	LT	1254+17	27	RT	48" RCP		59	2		EX 48" RCP - REMOVE END SECTIONS	
1254+38	30	RT	1255+04	1	RT	30" CMP	73					
1260+91	23	LT	1261+31	25	LT	18" CMP	41					
1265+48	96	LT	1265+78	13	LT	12" RCP	89				HEADWALL REMOVAL	
1268+63		LT							1			
1268+58	102	LT	1268+98	103	LT	12" CMP	43					
1278+12	88	LT	1278+12	41	RT	30" RCP	20	46				
1288+87	29	RT	1289+55	24	RT	Ø	68				UNKNOWN SIZE OR OUTFALL	
1291+37	92	LT	1291+90	79	LT	24"	57					
1289+80		LT/RT							2			
1298+82	70	LT	1299+06	6	RT	3x3 BOX		27				
1299+06	6	RT	1299+42	109	RT	42"	20	36			42" TEMPORARY CULVERT PIPE	
1301+67	70	LT	1301+62	8	LT	30" RCP		12	2		HEADWALL REMOVAL	
1301+62	8	LT	1301+53	110	RT	30"	20	20			30" TEMPORARY CULVERT PIPE	
1304+26	19	RT	1304+27	66	LT	30" RCP	43	9			PARTIAL REMOVAL w/ DROP BOX	
1304+26	19	RT	1304+37	115	RT	30"	20	16			30" TEMPORARY CULVERT PIPE	
1308+21	70	LT	1308+21	30	RT	2x2 BOX		15				
1308+21	30	RT	1308+00	126	RT	30"	20	16			30" TEMPORARY CULVERT PIPE	
1318+54		LT/RT							2			
1330+41	85	LT	1331+08	68	LT	15" CMP	70					
1334+70	66	LT	1334+78	2	RT	30" CMP		13	2		HEADWALL REMOVAL	
1334+78	2	RT	1334+78	112	RT	30"	20	18			30" TEMPORARY CULVERT PIPE	
1335+21	42	RT	1335+37	29	RT	24" CMP	22					
1336+49	65	LT	1336+49	15	RT	30" RCP		15				
1336+49	15	RT	1336+51	115	RT	30"	20	17			30" TEMPORARY CULVERT PIPE	
1341+47	79	LT	1341+47	23	RT	30" RCP		19			EX 30" RCP - REMOVE END SECTIONS	
1350+16	58	LT	1349+88	115	RT	6x5 BOX		200	2		EX 6' x 5' BOX CULVERT - REMOVE HEADWALLS	
1359+32	13	LT	1359+79	14	LT	15" RCP	47					
1362+81	72	RT	1363+22	73	RT	15" CMP	41					
1368+00	8	LT	1368+00	87	RT	6x6 BOX		56			FILL EX BOX AROUND NEW 60" STEEL PIPE	
1371+67	1	RT	1371+68	74	RT	30" RCP	73					
1380+16	1	LT	1380+16	76	RT	10x8 BOX		174			FILL EX BOX AROUND NEW 60" STEEL PIPE	
1384+65	12	LT	1384+66	84	RT	30" RCP	96					
1388+49	4	RT	1388+49	76	RT	7x3 BOX		56	2		HEADWALL REMOVAL	
1403+64	14	LT	1403+94	16	LT	15" CMP	31					
17+60	22	LT	17+89	2	LT		36				CH 31	
TOTAL							2,602	64	1,156	17		

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: DATE: MARCH 10, 2006

DRAWN BY: RG
CHECKED BY: JAC

DGN-SPEC
DATE-TIME
*REF01