

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET No.
315	34-5	HANCOCK	612	41
STA.		TO STA.		
FED. ROAD DIST. No.	ILLINOIS	FED. AID PROJECT		

PIPE UNDERDRAIN SCHEDULE														
LOCATION		PIPE UNDERDRAINS, 4 INCH						PIPE UNDERDRAINS, (SPECIAL) 4 INCH					CONCRETE HEADWALL FOR PIPE UNDERDRAINS (EACH)	
		WESTBOUND			EASTBOUND			TOTAL	WESTBOUND		EASTBOUND			TOTAL
		OUTSIDE	MEDIAN	TY A GUTTER	OUTSIDE	MEDIAN	OUTSIDE		MEDIAN	OUTSIDE	MEDIAN			
STATION TO STATION		(FOOT)						(FOOT)					(EACH)	
1307+00.00	1310+00.00	300	300	---	300	600	1,200	16	12	16	12	56	4	
1310+00.00	1316+00.00	600	600	---	600	---	2,400	20	---	16	---	36	2	
1316+00.00	1317+25.00	---	---	---	125	242	125	---	---	---	---	0	---	
1317+25.00	1319+67.00	242	242	---	242	333	968	16	12	16	12	56	4	
1319+67.00	1323+00.00	333	333	---	333	350	1,332	32	24	32	24	112	4	
1323+00.00	1326+50.00	350	350	---	350	300	1,400	16	12	16	12	56	4	
1326+50.00	1329+50.00	300	300	---	300	50	1,200	---	---	16	---	16	1	
1329+50.00	1330+00.00	50	50	---	50	---	200	---	---	---	---	0	---	
1330+00.00	1331+25.00	125	---	---	125	225	250	---	---	---	---	0	---	
1331+25.00	1333+50.00	225	225	---	225	400	900	16	12	16	12	56	4	
1333+50.00	1337+50.00	400	400	---	400	485	1,600	16	12	16	12	56	4	
1337+50.00	1342+35.00	485	485	---	485	15	1,940	16	---	---	---	16	1	
1342+35.00	1342+50.00	15	15	---	15	14	60	---	12	16	12	40	3	
1342+50.00	1342+64.00	14	14	---	14	486	56	10	---	---	---	10	---	
1342+64.00	1347+50.00	486	486	486	486	50	2,430	---	14	16	14	44	3	
1347+50.00	1348+00.00	50	50	50	50	100	250	---	---	---	---	0	---	
1348+00.00	1349+00.00	100	100	---	100	350	400	16	---	---	---	16	1	
1349+00.00	1352+50.00	350	350	---	350	350	1,400	16	12	18	12	58	4	
1352+50.00	1356+00.00	350	350	---	350	275	1,400	16	12	16	10	54	4	
1356+00.00	1358+75.00	275	275	---	275	375	1,100	---	---	---	---	0	---	
1360+25.00	1364+00.00	375	375	---	375	450	1,500	16	10	16	12	54	4	
1364+00.00	1368+50.00	450	450	---	450	500	1,800	16	12	16	12	56	4	
1368+50.00	1373+50.00	500	500	---	500	500	2,000	16	25	16	25	82	4	
1373+50.00	1378+50.00	500	500	---	500	500	2,000	16	12	16	12	56	4	
1378+50.00	1383+50.00	500	500	---	500	300	2,000	16	12	16	12	56	4	
1383+50.00	1386+50.00	300	300	---	300	50	1,200	16	---	---	---	16	1	
1386+50.00	1387+00.00	50	50	---	50	50	200	---	19	---	19	38	2	
1387+00.00	1387+50.00	50	50	---	50	---	200	---	---	16	---	16	1	
1387+50.00	1388+50.00	100	---	---	---	47	100	---	---	---	---	0	---	
1388+50.00	1388+96.36	47	47	---	47	229	188	32	25	32	25	114	4	
1388+96.36	1391+25.00	229	229	---	229	25	916	16	---	---	---	16	1	
1391+25.00	1391+50.00	25	25	---	25	25	100	---	10	---	12	22	2	
1391+50.00	1391+75.00	25	25	---	25	300	100	---	---	16	---	16	1	
1391+75.00	1394+75.00	300	300	---	300	40	1,200	---	12	---	12	24	2	
1394+75.00	1395+15.00	40	40	---	40	135	160	---	---	16	---	16	1	
1395+15.00	1396+50.00	135	135	---	135	325	540	16	---	---	---	16	1	
1396+50.00	1399+75.00	325	325	---	325	25	1,300	16	---	16	---	32	2	
1399+75.00	1400+00.00	25	25	---	25	300	100	---	25	---	25	50	2	
1400+00.00	1403+00.00	300	300	---	300	50	1,200	32	---	32	---	64	2	
1403+00.00	1403+50.00	50	50	---	50	175	200	---	12	---	12	24	2	
1403+50.00	1405+25.00	175	175	---	175	---	700	---	---	---	---	0	---	
TOTALS		22,597	22,047	1,605	22,723	22,047	91,019	1,023	778	1,008	800	3,609	206	

TRANSVERSE DRAINS, COMPLETE					
STATION	SIDE	STATION	SIDE	STATION	SIDE
1207+00	RT & LT	1258+00	RT & LT	1351+00	RT & LT
1212+00	RT & LT	1273+00	RT & LT	1367+00	RT & LT
1217+00	RT & LT	1278+00	RT & LT	1372+00	RT & LT
1240+00	RT & LT	1283+00	RT & LT	1377+00	RT & LT
1245+00	RT & LT	1336+00	RT & LT	1382+00	RT & LT
1250+00	RT & LT	1341+00	RT & LT	1387+00	RT & LT
1253+00	RT & LT	1346+00	RT & LT		

BACKSLOPE DRAIN SCHEDULE				
STATION TO STATION	RT/LT	ELEV	60109600 BACKSLOPE DRAINS TYPE 1 4"	
		(FT)	(FOOT)	
1375+00	1376+25	RT	565	125
1400+50	1403+50	LT	557	300
TOTAL			425	

NOTE:

BACKSLOPE DRAINS SHALL BE INSTALLED AT THE SOIL-ROCK INTERFACE IN THE CUT SECTIONS INDICATED. ACTUAL ELEVATION AND LIMITS WILL BE DETERMINED BY THE ENGINEER.

DGN-SPEC
DATE-TIME
*REF01

D6 PROJECT: FILE:

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE:
DATE: MARCH 10, 2006

DRAWN BY: RG
CHECKED BY: JAC