

# SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET No.
315	34-5	HANCOCK	612	44
STA.		TO STA.		
FED. ROAD DIST. No.	ILLINOIS	FED. AID PROJECT		

## STRIPING SCHEDULE

STATION TO STATION	70300100	70301000				70300610		70300630		70300635		70300645	70300660		70300210	70300230	70300240	70300260	78003120	78003180	78008300	78008320	78008330	78100100	78200100	78300200	78100200						
	SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL				TEMPORARY PAINT PAVEMENT MARKING - LETTERS & SYMBOLS		TEMPORARY PAINT PAVEMENT MARKING - LINE 5"		TEMPORARY PAINT PAVEMENT MARKING - LINE 6"		TEMPORARY PAINT PAVEMENT MARKING - LINE 12"	TEMPORARY PAINT PAVEMENT MARKING - LINE 24"		TEMPORARY PAVEMENT MARKING - LETTERS & SYMBOLS	TEMPORARY PAVEMENT MARKING - LINE 5"	TEMPORARY PAVEMENT MARKING - LINE 6"	TEMPORARY PAVEMENT MARKING - LINE 24"	PREFORMED PLASTIC PAVEMENT MARKING, TY B - LINE 5"	PREFORMED PLASTIC PAVEMENT MARKING, TY B - LINE 24"	POLYUREA PAVEMENT MARKING, TY II LET & SYM	POLYUREA PAVEMENT MARKING, TY II LINE 5"	POLYUREA PAVEMENT MARKING, TY II LINE 6"	RAISED REFLECTIVE PAVEMENT MARKERS	MONO-DIRECTIONAL PRISMATIC BARRIER REFLECTOR	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKERS						
	(FOOT)	STAGE 2 (SQ FT)	STAGE 3 (SQ FT)	FINAL (SQ FT)	STAGE 2 (SQ FT)	STAGE 3 (SQ FT)	STAGE 2 (FOOT)	STAGE 3 (FOOT)	STAGE 2 (FOOT)	STAGE 3 (FOOT)	STAGE 2 (FOOT)	STAGE 3 (FOOT)	STAGE 2 (FOOT)	STAGE 3 (FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(SQ FT)	(FOOT)	(FOOT)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)					
1155+68	1167+00	232	1,047	1,082	77			2492	1880			464	60					10,050		30	559	15			4,466		29		37	17	20		
1167+00	1182+00	300	1,932	4,596	99			4,600	9,779			440	268					13,500			750					6,000		38		73	28	28	
1182+00	1196+00	280	1,323	1,323	93			3,150	3,150									12,600			700					5,600		36		58	18	18	
1196+00	1208+00	240	1,134	1,134	80			2,700	2,700									10,800			600					4,800		30		52	15	15	
1208+00	1221+00	260	1,584	1,162	86	46.8		3,325	2,765	200				20		187.2		12,310	830	44	650	22	93.6		5,505	415	46		66	21	23		
1221+00	1232+00	210	1,397	1,368	70			3,325	3,255									9,900			550					4,400		28		50	14	14	
1232+00	1244+00	250	1,565	2,364	83		62.4	3,726	4,922			315		38	468.0		15,344	2,478	114	600	57	234.0		7,072	1,239	63		59	12	25			
1244+00	1256+00	240		2,016	80				4,800								10,800			600						4,800		30		37		15	
1256+00	1270+00	280		2,352	93				5,600								12,600			700						5,600		36		40		18	
1270+00	1284+00	280		2,352	93				5,600								12,600			700						5,600		36		40		18	
1284+00	1297+00	260		2,184	86				5,200								11,700			650						5,200		34		39		17	
1297+00	1311+00	280		2,279	93				5,425								12,600			700						5,600		36		8	40		18
1311+00	1325+00	280		1,323	93				3,150						187.2		13,314	826	56	700	28	93.6		5,957	413	48		40		41		18	
1325+00	1338+00	260	126	1,229	86			300	2,925								11,700			650					5,200		34		41	2	17		
1338+00	1352+00	280	2,055	1,994	93			4,892	4,746								12,600			700					5,600		36		58	18	18		
1352+00	1366+00	280	2,685	2,281	93	62.4	46.8	5,759	4,953	315	210			23	24	436.8	15,752	2,188	92	700	46	218.4		7,176	1,094	66		81	26	33			
1366+00	1380+00	280	1,911	1,323	93			4,550	3,150								12,600			700					5,600		36		58	18	18		
1380+00	1393+00	260	1,556	2,127	86		46.8	3,703	4,350			405			25	280.8	12,780	1,260	46	650	23	140.4		5,740	630	52		62	17	23			
1393+00	1415+00	440	3,234	2,779	146			7,700	6,616								11,026			613					4,900		32		84	40	22		
SUB-TOTALS		5,192	21,549	37,268	1,723	109.2	156.0	50,222	84,966	515	1,834			43	87														246		378		
TOTALS		5,192	60,540				266		135,188		2,349		328	130	1,560.0	234,576	7,582	382		12,472	191	780.0	104,816	3,791	746	30	1,015		624				
USE																																	

\*DGN-SPEC\*  
\*DATE-TIME\*  
\*REF01

D6 PROJECT: FILE:

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

### SCHEDULES OF QUANTITIES

SCALE: DATE: MARCH 10, 2006

DRAWN BY: RG  
CHECKED BY: JAC