

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET No.
315	34-5	HANCOCK	612	45
STA.		TO STA.		
FED. ROAD DIST. No.	ILLINOIS	FED. AID PROJECT		

SIGN SCHEDULE													
STATION	LOCATION	SIGN NUMBER	SIZE	MESSAGE	NUMBER OF POSTS	72000100	72000200	72000300	72400310	72400320	72400330	72800100	73100100
		(MUTCD)	(IN)			SIGN PANEL - TYPE 1	SIGN PANEL - TYPE 2	SIGN PANEL - TYPE 3	REMOVE SIGN PANEL - TYPE 1	REMOVE SIGN PANEL - TYPE 2	REMOVE SIGN PANEL - TYPE 3	TELESCOPING STEEL SIGN SUPPORT	BASE FOR TELESCOPING STEEL SIGN SUPPORT
					(EACH)	(SQ FT)	(SQ FT)	(SQ FT)	(SQ FT)	(SQ FT)	(SQ FT)	(FOOT)	(EACH)
1174+50.00	MEDIAN	R6-1R	36 x 12	ONE WAY	1	3.00						14	1
1118+18.00	MEDIAN	R6-1R	36 x 12	ONE WAY	1	3.00						14	1
1188+76.00	MEDIAN	R5-1a	36 x 24	WRONG WAY	1	6.00						15	1
1188+76.00	RT	R5-1a	36 x 24	WRONG WAY	1	6.00						15	1
1190+76.00	MEDIAN	R5-1	36 x 36	DO NOT ENTER	1	9.00						16	1
1190+76.00	RT	R5-1	36 x 36	DO NOT ENTER	1	9.00						16	1
1191+07.00	MEDIAN	R6-1L	36 x 12	ONE WAY		3.00							
1191+07.00	MEDIAN	W1-2	36 x 36	YIELD	1	9.00						17	1
1191+56.00	LT	R6-1L	36 x 12	ONE WAY	1	3.00						14	1
1191+78.00	RT	R6-1L	36 x 12	ONE WAY	1	3.00						14	1
1192+04.00	MEDIAN	R6-1L	36 x 12	ONE WAY		3.00							
1192+04.00	MEDIAN	W1-2	36 x 36	YIELD	1	9.00						17	1
1192+36.00	LT	R5-1	36 x 36	DO NOT ENTER	1	9.00						16	1
1192+36.00	MEDIAN	R5-1	36 x 36	DO NOT ENTER	1	9.00						16	1
1194+36.00	LT	R5-1a	36 x 24	WRONG WAY	1	6.00						15	1
1194+36.00	MEDIAN	R5-1a	36 x 24	WRONG WAY	1	6.00						15	1
1202+04.00	MEDIAN	R6-1R	36 x 12	ONE WAY		3.00							
1202+04.00	MEDIAN	R6-1R	36 x 12	ONE WAY	1	3.00						14	1
1205+25.00	MEDIAN	W2-2L	36 x 36	SIDE ROAD (SYMBOL)	1	9.00						17	1
1205+25.00	RT	W2-2L	36 x 36	SIDE ROAD (SYMBOL)	1	9.00						17	1
1207+10.00	RT	W2-2L	30 x 30	SIDE ROAD (SYMBOL)					6.25				
1208+25.00	MEDIAN	R3-1100L	24 x 24	LEFT TURN LANE	1	4.00						16	1
1208+25.00	MEDIAN	M6-2L	21 x 15	ARROW		2.19							
1209+00.00	RT	W14-3	30 x 40	NO PASSING ZONE						8.33			
1211+50.00	MEDIAN	R5-1a	36 x 24	WRONG WAY	1	6.00						15	1
1211+50.00	RT	R5-1a	36 x 24	WRONG WAY	1	6.00						15	1
1213+50.00	MEDIAN	R5-1	36 x 36	DO NOT ENTER	1	9.00						16	1
1213+50.00	RT	R5-1	36 x 36	DO NOT ENTER	1	9.00						16	1
1213+82.00	MEDIAN	R6-1L	36 x 12	ONE WAY		3.00							
1213+82.00	MEDIAN	W1-2	36 x 36	YIELD	1	9.00						17	1
1213+91.00	RT	R1-1	30 x 30	STOP					6.25				
1213+91.00	RT	W16-8	30 x 9	270OE					1.88				
1213+91.00	RT	W16-8	30 x 9	150ON					1.88				
1214+04.00	RT		96 x 30	LAMOINE CHRISTIAN CAMP						20.00			
1214+11.00	RT	W1-7	48 x 24	ARROW					8.00				
10+80 (TR 302)	LT	R6-1L	36 x 12	ONE WAY		3.00							
10+80 (TR 302)	LT	R6-1R	36 x 12	ONE WAY		3.00							
10+80 (TR 302)	LT	R1-1	36 x 36	STOP	1	9.00						19	1
10+80 (TR 302)	LT	R6-3a	24 x 18	DIVIDED HIGHWAY		3.00							
15+00 (TR 302)	LT	W3-1a	36 x 36	STOP AHEAD (SYMBOL)	1	9.00						16	1

DGN-SPEC
DATE-TIME
*REF01

D6 PROJECT: FILE:

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: DATE: MARCH 10, 2006

DRAWN BY: RG
CHECKED BY: JAC