

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET No.
315	34-5	HANCOCK	612	49
STA.		TO STA.		
FED. ROAD DIST. No.		ILLINOIS	FED. AID PROJECT	

SIGN SCHEDULE

STATION	LOCATION	SIGN NUMBER (MUTCD)	SIZE (IN)	MESSAGE	NUMBER OF POSTS (EACH)	72000100	72000200	72000300	72400310	72400320	72400330	72800100	73100100
						SIGN PANEL - TYPE 1 (SQ FT)	SIGN PANEL - TYPE 2 (SQ FT)	SIGN PANEL - TYPE 3 (SQ FT)	REMOVE SIGN PANEL - TYPE 1 (SQ FT)	REMOVE SIGN PANEL - TYPE 2 (SQ FT)	REMOVE SIGN PANEL - TYPE 3 (SQ FT)	TELESCOPING STEEL SIGN SUPPORT (FOOT)	BASE FOR TELESCOPING STEEL SIGN SUPPORT (EACH)
1327+95.00	MEDIAN	R5-1a	36 x 24	WRONG WAY	1	6.00						15	1
1327+95.00	RT	R5-1a	36 x 24	WRONG WAY	1	6.00						15	1
1329+95.00	MEDIAN	R5-1	36 x 36	DO NOT ENTER	1	9.00						16	1
1329+95.00	RT	R5-1	36 x 36	DO NOT ENTER	1	9.00						16	1
1330+00.00	MEDIAN	W1-2	36 x 36	YIELD		9.00							
1330+00.00	MEDIAN	R6-1R	36 x 12	ONE WAY	1	3.00						17	1
1330+47.00	LT	R1-1	30 x 30	STOP				6.25					
1331+20.00	MEDIAN	R6-1R	36 x 12	ONE WAY	1	3.00						17	1
1331+20.00	MEDIAN	W1-2	36 x 36	YIELD		9.00							
1331+45.00	LT	R5-1	36 x 36	DO NOT ENTER	1	9.00						16	1
1331+45.00	MEDIAN	R5-1	36 x 36	DO NOT ENTER	1	9.00						16	1
1333+45.00	LT	R5-1a	36 x 24	WRONG WAY	1	6.00						15	1
1333+45.00	MEDIAN	R5-1a	36 x 24	WRONG WAY	1	6.00						15	1
1335+50.00	MEDIAN	R6-1R	36 x 12	ONE WAY	1	3.00						14	1
1338+48.00	MEDIAN	W1-2L	30 x 30	CURVE (SYMBOL)				6.25					
1338+55.00	LT	W14-3	30 x 40	NO PASSING ZONE					8.33				
1339+05.00	LT	W11-10	30 x 30	TRUCK CROSSING (SYMBOL)				6.25					
1347+00.00	LT	R2-1104	48 x 96	SPEED LIMIT OVER 4 TONS	1			32.00				20	1
1348+66.00	MEDIAN	W2-1	36 x 36	CROSS ROAD (SYMBOL)	1	9.00						18	1
1348+66.00	RT	W2-1	36 x 36	CROSS ROAD (SYMBOL)	1	9.00						18	1
1351+00.00	LT	R2-1	36 x 48	SPEED LIMIT 65	1		12.00					17	1
1351+50.00	RT		93 x 39	CHRISTIAN CAMP / JOETTA ROAD	2			25.19				32	1
1351+66.00	MEDIAN	R3-1100L	24 x 24	LEFT TURN LANE	1	4.00						16	1
1351+66.00	MEDIAN	M6-2L	21 x 15	ARROW		2.19							
1352+22.00	RT	W2-1	30 x 30	CROSS ROAD (SYMBOL)				6.25					
1352+50.00	MEDIAN	R2-5A	36 x 48	SPEED ZONE AHEAD	1		12.00					19	1
1352+50.00	MEDIAN	R2-1101	30 x 30	55 M.P.H.		6.25							
1352+50.00	RT	R2-5A	36 x 48	SPEED ZONE AHEAD	1		12.00					19	1
1352+50.00	RT	R2-1101	30 x 30	55 M.P.H.		6.25							
1353+49.00	RT	R3-1100R	24 x 24	RIGHT TURN LANE	1	4.00						16	1
1353+49.00	RT	M6-2R	21 x 15	ARROW		2.19							
1355+00.00	LT	M1-4	30 x 24	136	1	5.00						16	1
1355+00.00	LT	M1-1100	24 x 24	336	1	4.00						16	1
1355+00.00	LT	M3-2	24 x 12	WEST		2.00							
1355+00.00	LT	M3-1	24 x 12	SOUTH		2.00							
1355+28.00	RT		93 x 39	CHRISTIAN CAMP / JOETTA ROAD						25.19			
1356+74.00	MEDIAN	R5-1A	36 x 24	WRONG WAY			6.00					15	1
1356+88.00	RT	R5-1A	36 x 24	WRONG WAY			6.00					15	1
1358+74.00	MEDIAN	R5-1	36 x 36	DO NOT ENTER	1	9.00						16	1
1358+88.00	RT	R5-1	36 x 36	DO NOT ENTER	1	9.00						16	1
1358+95.00	MEDIAN	W1-2R	30 x 30	CURVE (SYMBOL)				6.25					

DGN: SPEC
 DATE: TIME
 *REF01

D6 PROJECT: FILE:

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE:
DATE: MARCH 10, 2006

DRAWN BY: RG
CHECKED BY: JAC