

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET No.
315	34-5	HANCOCK	612	50
STA.		TO STA.		
FED. ROAD DIST. No.		ILLINOIS	FED. AID PROJECT	

SIGN SCHEDULE													
STATION	LOCATION	SIGN NUMBER	SIZE	MESSAGE	NUMBER OF POSTS (EACH)	72000100	72000200	72000300	72400310	72400320	72400330	72800100	73100100
		(MUTCD)	(IN)			SIGN PANEL - TYPE 1 (SQ FT)	SIGN PANEL - TYPE 2 (SQ FT)	SIGN PANEL - TYPE 3 (SQ FT)	REMOVE SIGN PANEL - TYPE 1 (SQ FT)	REMOVE SIGN PANEL - TYPE 2 (SQ FT)	REMOVE SIGN PANEL - TYPE 3 (SQ FT)	TELESCOPING STEEL SIGN SUPPORT (FOOT)	BASE FOR TELESCOPING STEEL SIGN SUPPORT (EACH)
1359+07.00	MEDIAN	R6-1L	36 x 12	ONE WAY		3.00							
1359+07.00	MEDIAN	W1-2	36 x 36	YIELD	1	9.00						17	1
1359+33.00	MEDIAN		30 x 9	2950E					1.88				
1359+33.00	MEDIAN		30 x 9	1460N					1.88				
1359+39.00	MEDIAN	R1-1	30 x 30	STOP					6.25				
35+00 (TR 213)	RT	W3-1a	36 x 36	STOP AHEAD (SYMBOL)	1	9.00						16	1
39+10 (TR 213)	RT	R1-1	30 x 30	STOP					6.25				
39+20 (TR 213)	RT	R6-1L	36 x 12	ONE WAY		3.00							
39+20 (TR 213)	RT	R6-1R	36 x 12	ONE WAY		3.00							
39+20 (TR 213)	RT	R1-1	36 x 36	STOP	1	9.00						19	1
39+20 (TR 213)	RT	R6-3	24 x 18	DIVIDED HIGHWAY		3.00							
40+83 (CH 5)	LT	R6-1L	36 x 12	ONE WAY		3.00							
40+83 (CH 5)	LT	R6-1R	36 x 12	ONE WAY		3.00							
40+83 (CH 5)	LT	R1-1	36 x 36	STOP	1	9.00						19	1
40+83 (CH 5)	LT	R6-3	24 x 18	DIVIDED HIGHWAY		3.00							
43+83 (CH 5)	LT	W3-1a	30 x 30	STOP AHEAD (SYMBOL)					6.25				
45+83 (CH 5)	LT	W3-1a	36 x 36	STOP AHEAD (SYMBOL)	1	9.00						16	1
1360+27.00	MEDIAN	R6-1L	36 x 12	ONE WAY		3.00							
1360+27.00	MEDIAN	W1-2	36 x 36	YIELD	1	9.00						17	1
1360+38.00	MEDIAN	R5-1	36 x 36	DO NOT ENTER	1	9.00						16	1
1360+61.00	LT	R5-1	36 x 36	DO NOT ENTER	1	9.00						16	1
1362+00.00	MEDIAN	R2-1	36 x 48	SPEED LIMIT 55	1		12.00					17	1
1362+00.00	RT	R2-1	36 x 48	SPEED LIMIT 55	1		12.00					17	1
1362+38.00	LT	R5-1a	36 x 24	WRONG WAY	1	6.00						15	1
1362+53.00	MEDIAN		93 x 39	CHRISTIAN CAMP / JOETTA ROAD							25.19		
1362+61.00	MEDIAN	R5-1a	36 x 24	WRONG WAY	1	6.00						15	1
1363+00.00	MEDIAN	R6-1R	36 x 12	ONE WAY	1	3.00						14	1
1364+00.00	MEDIAN	W9-2R	36 x 36	LANE ENDS MERGE RIGHT	2	9.00						35	1
1364+00.00	RT	W9-2R	36 x 36	LANE ENDS MERGE RIGHT	2	9.00						35	1
1364+00.00	RT	M1-4	30 x 24	136		5.00							
1364+00.00	RT	M1-1100	24 x 24	336		4.00							
1364+00.00	RT	M3-2	24 x 12	EAST		2.00							
1364+00.00	RT	M3-1	24 x 12	NORTH		2.00							
1365+85.00	MEDIAN	R3-1100L	24 x 24	LEFT TURN LANE	1	4.00						16	1
1365+85.00	MEDIAN	M6-2L	21 x 15	ARROW		2.19							
1367+59.00	LT		93 x 39	CHRISTIAN CAMP / JOETTA ROAD	2			25.19				36	1
1367+59.00	LT	R3-1100R	24 x 24	RIGHT TURN LANE		4.00							
1367+59.00	LT	M6-2R	21 x 15	ARROW		2.19							
1368+56.00	MEDIAN	W2-1	30 x 30	CROSS ROAD (SYMBOL)					6.25				
1370+59.00	MEDIAN	W2-1	36 x 36	CROSS ROAD (SYMBOL)	1	9.00						17	1
1370+59.00	LT	W2-1	36 x 36	CROSS ROAD (SYMBOL)	1	9.00						17	1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: DATE: MARCH 10, 2006

DRAWN BY: RG
CHECKED BY: JAC

DGN: SPEC
 DATE: TIME
 *REF: 01