

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET No.
315	34-5	HANCOCK	612	55
STA.		TO STA.		
FED. ROAD DIST. No.	ILLINOIS	FED. AID PROJECT		

CONCRETE BARRIER SCHEDULE									
STATION	TO	STATION	LT/RT	63801000 CONCRETE GLARE SCREEN (FOOT)	XX004340 CONC MEDIAN BARRIER BASE, TY F (FOOT)	XX004341 CONC MEDIAN BARRIER TY F (FOOT)	Z0030030 IMPACT ATTENUATOR (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3 (EACH)	Z0030250 IMPACT ATTENUATOR TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 (EACH)	70400100 TEMPORARY CONCRETE BARRIER (FOOT)
1238+25.00			RT					1	
1238+50.00		1248+00.00	RT						950
1248+25.00			RT					1	
1286+92.00			LT				1		
1286+92.00		1297+00.00	LT	1,008	1,008	1,008			
1297+00.00		1299+34.00	LT	234	234	234			
1299+34.00		1301+08.00	RT	174	174	174			
1301+08.00			RT				1		
1301+25.00			RT					1	
TOTALS				1,416	1,416	1,416	2	3	950

GUARDRAIL SCHEDULE							
LOCATION (STATION TO STATION)	LT/RT	STEEL PLATE BEAM GUARD RAIL, TYPE A (FOOT)	TRAFFIC BARRIER TERMINAL		GUARD RAIL REMOVAL (FOOT)	GUARD RAIL MARKER TYPE A (EACH)	TERMINAL MARKER - DIRECT APPLIED (EACH)
			TYPE 1, SPECIAL (TANGENT) (EACH)	TYPE 6 (EACH)			
FAP ROUTE 315 (IL 336)							
1243+40 TO 1247+82	LT				442		
1244+98 TO 1248+51	LT				353		
1288+51 TO 1289+01	RT		1				1
1289+01 TO 1293+26	RT	425				6	
1292+54 TO 1297+15	LT				461		
1293+26 TO 1293+50	RT			1			
1297+00 TO 1297+24	RT			1			
1297+24 TO 1297+74	RT		1				1
1316+27 TO 1320+15	LT				388		
1317+08 TO 1320+99	LT				391		
1331+10 TO 1332+85	LT				175		
TOTALS		425	2	2	2,210	6	2

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE:
DATE: MARCH 10, 2006

DRAWN BY: RG
CHECKED BY: JAC

DGN: SPEC
 DATE: TIME
 *REF: 01