

# SUMMARY OF QUANTITIES

100% STATE  
SFTY - 2A

| ITEM #     | DESCRIPTION   | UNIT  | QUANTITY |
|------------|---|-------|----------|
| 50102400   | CONCRETE REMOVAL  | CU YD | 16.3     |
| 50300255   | CONCRETE SUPERSTRUCTURE                                       | CU YD | 16.1     |
| 50800205   | REINFORCEMENT BARS, EPOXY COATED                              | POUND | 2020     |
| 59000100   | EPOXY CRACK SEALING   | FOOT  | 10       |
| 67100100   | MOBILIZATION  | L SUM | 1        |
|            |   |       |          |
| 70100815   | TRAFFIC CONTROL AND PROTECTION, STANDARD 701446               | L SUM | 1        |
| 70400100   | TEMPORARY CONCRETE BARRIER                                    | FOOT  | 600      |
| 70400200   | RELOCATE TEMPORARY CONCRETE BARRIER                           | FOOT  | 600      |
| X0320887   | POLYMER CONCRETE  | CU FT | 4.6      |
| X7011420   | TRAFFIC CONTROL AND PROTECTION, STANDARD 701411               | L SUM | 1        |
| XX004814   | SILICONE JOINT SEALER, 3"                                     | FOOT  | 126      |
| Z0002600   | BAR SPLICERS  | EACH  | 24       |
| ⊙ Z0030250 | IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 | EACH  | 2        |
| ⊙ Z0030350 | IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3  | EACH  | 2        |
|            |   |       |          |

⊙SFTY-3M

SUMMARY OF  
QUANTITIES  
C-96-001-07  
LOGAN COUNTY