

INDEX OF SHEETS

- 1 COVER SHEET
- 2 INDEX OF SHEETS, GENERAL NOTES, & SIGNATURES
- 3 SUMMARY OF QUANTITIES
- 4 EXISTING PLAN & ELEVATION VIEWS
- 5 CONCRETE REMOVAL & SUPERSTRUCTURE DETAILS
- 6 REINFORCEMENT & JOINTING DETAILS
- 7 REINFORCEMENT DETAILS
- 8 BAR DRILLING LOCATION DETAILS
- 9 APPROACH SLAB CONCRETE DETAILS
- 10 APPROACH SLAB REINFORCEMENT DETAILS

STANDARDS

- 701101-01
- 701106-01
- 701400-02
- 701402-05
- 701406-04
- 702001-06
- 704001-02

GENERAL NOTES:

PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING STRUCTURE HAVE BEEN TAKEN FROM EXISTING PLANS AND ARE SUBJECT TO NOMINAL CONSTRUCTION VARIATIONS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY SUCH DIMENSIONS AND DETAILS IN THE FIELD AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION OR A CHANGE IN THE SCOPE OF WORK, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE FOR THE WORK.

EXISTING REINFORCEMENT EXTENDING INTO THE REMOVAL AREA SHALL BE CLEANED, STRAIGHTENED, AND INCORPORATED INTO THE NEW CONSTRUCTION. ANY REINFORCEMENT BARS THAT ARE DAMAGED DURING CONCRETE REMOVAL SHALL BE REPLACED WITH AND APPROVED BAR SPLICER OR ANCHORAGE SYSTEM. COST SHALL BE INCLUDED WITH CONCRETE REMOVAL.

<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS DISTRICT 6</b>
EXAMINED <u>March 17</u> 20 <u>06</u> <u>[Signature]</u> ENGINEER OF OPERATIONS
EXAMINED <u>March 21</u> 20 <u>06</u> <u>[Signature]</u> ENGINEER OF PROGRAM IMPLEMENTATION
EXAMINED <u>MARCH 20</u> 20 <u>06</u> <u>[Signature]</u> ENGINEER OF PROGRAM DEVELOPMENT

CONTRACT 72A37  
INDEX OF SHEETS,  
GENERAL NOTES,  
& SIGNATURES