

GUARDRAIL SCHEDULE

STA TO	STA	SIDE	TRAF. BARR. TERM. TY 1 SPC. (TANGENT) EACH	TRAF. BARR. TERM. TY 6A EACH	STEEL PLATE BEAM GUARDRAIL FEET	REMOVE AND REPLACE STEEL BRIDGERAIL TYPE T-1, (SPECIAL) FEET	GUARDRAIL REMOVAL FEET	TERMINAL MARKERS DIRECT APPLIED EACH	GUARDRAIL MARKERS TY A EACH
SN 034-0057									
723+11.74	723+61.74	RT	1				46	1	
723+61.74	725+36.74	RT			175		175		2
725+36.74	725+68.74	RT		1			32		
725+68.74	726+63.24	RT				94.5			2
726+63.24	726+95.24	RT		1			32		
726+95.24	727+70.24	RT			75		75		1
727+70.24	728+20.24	RT	1				46	1	
724+98.39	725+48.39	LT	1				19	1	
725+48.39	725+80.39	LT		1			32		
725+80.39	726+65.24	LT				84.85			2
726+65.24	726+97.24	LT		1			32		
726+97.24	728+34.74	LT			137.5		137.5		2
728+34.74	728+84.74	LT	1				45.5	1	
905+00	905+50	RT	1				47.5	1	
905+50	920+50	RT			1500		1500		19
920+50	921+00	RT	1				47.5	1	
TOTALS			6	4	1887.5	179.35	2267	6	28

DATE	
BY	
NO. OF	
POSTHOLE	
NO.	

CONTRACT 72A40
GUARDRAIL SCHEDULE