

district
3/30/2006
c:\projects\74063dp\d04304pa.dgn

CONTRACT NO. 74063

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
95	18RS	EFFINGHAM	13	4
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PAVING & REMOVAL SCHEDULE

STATION TO STATION	LENGTH	EXISTING PAVT WIDTH	AREA	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	PCC SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	BITUMINOUS SURFACE REMOVAL (SPECIAL)	MEDIAN REMOVAL PARTIAL DEPTH	POLY BCSC, SUPERPAVE, MIX D, N90	PCC PAVEMENT SURFACE REMOVAL
EB LANES											
69+25 TO 70+71	146	24	389	42	0.8	80	19			46	322
70+71 TO 73+80	309	24	824	89	1.8					98	858
73+80 TO 79+47	567	24	1512	164	3.3					180	1575
79+47 TO 80+67	120	14	187	21	0.4	17	8	187		23	
80+67 TO 82+78	211	14-24	445	49	1.0			445		54	
82+78 TO 83+83	105	24	280	30	0.6		58	280		33	
EXISTING RAISED MEDIAN											
69+25 TO 70+71	146	4	65	6	0.1	13	3		464	7	
79+47 TO 82+78	331	4	147	15	0.3				1324	16	
CENTERTURN LANE											
70+71 TO 73+80	309	4-14	309	31	0.6					35	309
73+80 TO 79+47	567	14	882	88	1.8					99	882
79+47 TO 82+78	331	10	368	37	0.7			368		41	
82+78 TO 83+83	105	10-12	128	13	0.3		9	128		14	
WB LANES											
69+25 TO 70+71	146	24	389	42	0.8	80	19			46	322
70+71 TO 73+80	309	24	824	89	1.8					98	858
73+80 TO 79+47	567	24	1512	164	3.3					180	1575
79+47 TO 83+83	436	24	1163	126	2.5		120	1163		138	
N. LEG FEATHER OF RANEY STREET (TRAPEZOIDAL AREA W/ BASES OF 158' & 116', 8' WIDE)											
EOP WIDTH (FT)	WIDTH 8' BACK (FT)	WIDTH (FT)									
158	116	8	121.8	12.2	0.2					6	
S. LEG FEATHER OF RANEY STREET (TRAPEZOIDAL AREA W/ BASES OF 154' & 120', 8' WIDE)											
EOP WIDTH (FT)	WIDTH 8' BACK (FT)	WIDTH (FT)									
154	120	8	121.8	12.2	0.2					14	
TOTALS:				1032	21	190	236	2571	1788	1130	6702

PATCHING SCHEDULE

LANE	PARTIAL DEPTH REMOVAL	PARTIAL DEPTH PATCHING	PAVEMENT FABRIC	CLASS B PATCHES, TYPE II, 10 INCHES	CLASS B PATCHES, TYPE III, 10 INCHES	SAW CUTS	DOWEL BARS 1 1/2"	TIE BARS
EBDL	88	20	0	31.9	0	216	80	0
EBPL	16	3	0	63.8	60	747	260	42
WBDL	129	29	32	42.5	32	1095	420	0
WBPL	47	10	16	118.2	16	384	160	0
CENTERTURN LANE	28	6	0	47.8	0	396	160	0
TOTALS:	307	69	108	304	108	2838	1080	42

PAVEMENT MARKING SCHEDULE

STATION TO STATION	LENGTH	SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	TEMPORARY PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 6"	TEMPORARY PAVEMENT MARKING - LINE 12"	TEMPORARY PAVEMENT MARKING - LINE 24"	WORK ZONE PAVEMENT MARKING REMOVAL	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	RAISED REFLECTIVE PAVEMENT MARKER
69+25 TO 76+53	728	1296	62	2492	723	234	82	144	62	2492	723	234	82	54
77+44 TO 83+83	639	1470	140	1396	682	0	48	163	140	1396	682	0	48	54
TOTALS:	2766	203	3888	1405	234	130	307	203	3888	1405	234	130	108	

PERMANENT SURVEY MARKERS, TYPE I

STATION	DESCRIPTION	EACH
65+00	(WEST P.O.T.)	•
66+94.74	P.C.	•
70+80.6	P.I.	1
74+66.41	P.T.	1
75+35.526	P.C.	1
78+65.14	P.I.	1
81+94.68	P.T.	1
85+16.09BK=98+87.13AH	P.O.T. DISK	•
TOTAL:		5

*WAS NOT INCLUDED IN THIS PAY ITEM'S QUANTITY. SHOWN ON PLANS ONLY FOR INFORMATION.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. HORIZ. DATE

DRAWN BY CHECKED BY