

SUMMARY OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	MARION	17	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

- * VARIOUS ROUTES
- ** D7 SIGNAL MODERIZATION 2006-2

SUMMARY OF QUANTITIES			URBAN 90% FED. 5% STATE 5% CITY TOTAL	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		QUANTITIES	Y031-1F SB U.S. 51 & BROADWAY	Y031-1F NB U.S. 51 & BROADWAY	Y031-1F NB U.S. 51 & 2ND ST.
* 42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	3978	2317	1621	40	
* 42400420	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH, SPECIAL	SO FT	438	119	319		
* 44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	11		11		
* 44000600	SIDEWALK REMOVAL	SO FT	4345	2317	1988	40	
* 44004700	SIDEWALK REMOVAL (SPECIAL)	SO FT	119	119			
* 60604500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18 (ABUTTING EXISTING PAVEMENT)	FOOT	11		11		
67100100	MOBILIZATION	L SUM	1	0.25	0.25	0.25	0.25
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.34	0.33	0.33	
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	0.34	0.33	0.33	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.25	0.25	0.25	0.25
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	0.34	0.33	0.33	
* 72000100	SIGN PANEL - TYPE 1	SO FT	24		16	8	
* 72000200	SIGN PANEL - TYPE 2	SO FT	48	36	12		
80500200	SERVICE INSTALLATION, TYPE B	EACH	3	1	1	1	
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	521	204	195	122	
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	141	57	57	27	
81021550	CONDUIT, AUGERED 2" DIA., PVC	FOOT	40			40	
81021590	CONDUIT, AUGERED 4" DIA., PVC	FOOT	539	163	222	154	
81400100	HANDHOLE	EACH	13	4	5	4	
81400300	DOUBLE HANDHOLE	EACH	3	1	1	1	
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	662	261	252	149	
85700100	FULL-ACTUATED CONTROLLER AND TYPE III CABINET	EACH	3	1	1	1	
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2430	320	1175	935	
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2058	677	786	565	30
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	563	176	223	164	
87502660	TRAFFIC SIGNAL POST, ALUMINUM 12 FT.	EACH	2	2			
87502700	TRAFFIC SIGNAL POST, ALUMINUM 16 FT.	EACH	6		3	3	
87502720	TRAFFIC SIGNAL POST, ALUMINUM 18 FT.	EACH	2	1	1		

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY