

SUMMARY OF QUANTITIES (Cont'd)

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	MARION	17	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

- * VARIOUS ROUTES
- ** D7 SIGNAL MODERIZATION 2006-2

SUMMARY OF QUANTITIES			URBAN 90% FED. 5% STATE 5% CITY TOTAL	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		QUANTITIES	Y031-IF SB U.S. 51 & BROADWAY	Y031-IF NB U.S. 51 & BROADWAY	Y031-IF NB U.S. 51 & 2ND ST.
87700120	STEEL MAST ARM ASSEMBLY AND POLE, 16 FT.	EACH	1	1			
87700140	STEEL MAST ARM ASSEMBLY AND POLE, 20 FT.	EACH	2	1	1		
87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	1		1		
87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1	1			
87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1		1		
87700300	STEEL MAST ARM ASSEMBLY AND POLE, 52 FT.	EACH	1			1	
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	30	9	12	9	
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	9	3	3	3	
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	40	20	20		
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	39	11	13	15	
88200410	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	47	11	14	9	13
88800100	PEDESTRIAN PUSH-BUTTON	EACH	8				8
89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	1				1
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	4	1	1	1	1
89502380	REMOVE EXISTING HANDHOLE	EACH	11	4	3	4	
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	16	5	6	5	
X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	1666	613	643	410	
X8801300	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	10	2	5	2	1
X8801310	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	23	6	6	3	8
X8801395	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2				2
X8801400	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	4	1	1		2
X8801415	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2			2	
X8801437	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	2	1	1		
X8810395	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	4		4		
X8810495	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED	EACH	14	4	2	4	4

PLOT DATE = 3/20/2008
 PLOT SCALE = #SCALE
 USER NAME = district

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES (Cont'd)

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY