

RURAL

URBAN

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
774	(107,107Z) I-2	EFFINGHAM	12	4
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT				

CONTRACT NO. 74129

LOCATION	EPOXY PAVEMENT MARKING						RAISED REFLECTIVE PAVEMENT MARKERS			
	LETTERS AND SYMBOLS	YELLOW 4"	WHITE 4"	WHITE 6"	YELLOW 12"	WHITE 12"	WHITE 24"	ONE WAY CRYSTAL EACH	ONE WAY AMBER EACH	TWO WAY AMBER EACH
STATION TO STATION	SQ. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.			
Q 942+50 TO Q 955+69		4988			489			16	62	
RT 942+50 TO RT 955+69			2190	92		352				
LT 942+50 TO LT 955+69			2269	92		352				
Q 955+69 TO Q 970+00		3699						77	51	16
RT 955+69 TO RT 970+00			1286	340						
LT 955+69 TO LT 970+00			1566	620						
Q 955+87	15.6 (TURN ARROW)									
Q 956+54	15.6 (TURN ARROW)									
Q 957+19	15.6 (TURN ARROW)									
Q 957+84	15.6 (TURN ARROW)									
Q 958+49	15.6 (TURN ARROW)									
Q 962+99	31.2 (2WLT)									
Q 965+99	31.2 (2WLT)									
Q 968+75	31.2 (2WLT)									
Q 970+00 TO Q 975+00		1064						24	22	
RT 970+00 TO RT 975+00			462	116						
LT 970+00 TO LT 975+00			462	116						
Q 970+40	31.2 (2WLT)									
Q 972+22	31.2 (2WLT)									
Q 974+03	31.2 (2WLT)									
Q 975+00 TO Q 977+84		455						12	10	
RT 975+00 TO RT 977+84			237	62						
LT 975+00 TO LT 977+84			238	62						
Q 975+58	31.2 (2WLT)									
Q 976+77	31.2 (2WLT)									
Q 977+84 TO Q 982+52		990						22	20	
RT 977+84 TO RT 982+52			427	108						
LT 977+84 TO LT 982+52			426	108						
Q 978+23	31.2 (2WLT)									
Q 979+90	31.2 (2WLT)									
Q 981+58	31.2 (2WLT)									
Q 982+52 TO Q 991+74		2244						43	40	
RT 982+52 TO RT 991+74			848	492						
LT 982+52 TO LT 991+74			848	492						
Q 983+36	15.6 (TURN ARROW)									
Q 984+01	15.6 (TURN ARROW)									
Q 984+67	15.6 (TURN ARROW)									
Q 985+32	15.6 (TURN ARROW)									
Q 988+19	15.6 (TURN ARROW)									
Q 988+85	15.6 (TURN ARROW)									
Q 989+50	15.6 (TURN ARROW)									
Q 990+16	15.6 (TURN ARROW)									
Q 990+78	15.6 (TURN ARROW)									
Q 991+74 TO Q 1015+30		5750			240			116	114	
RT 991+74 TO RT 1015+30			2356	869						
LT 991+74 TO LT 1015+30			2356	869						
Q 991+92	15.6 (TURN ARROW)									
Q 992+57	15.6 (TURN ARROW)									
Q 993+23	15.6 (TURN ARROW)									
Q 993+88	15.6 (TURN ARROW)									
Q 994+54	15.6 (TURN ARROW)									
Q 998+13	31.2 (2WLT)									
Q 1001+13	31.2 (2WLT)									
Q 1004+13	31.2 (2WLT)									
Q 1007+13	31.2 (2WLT)									
Q 1011+98	15.6 (TURN ARROW)									
Q 1012+53	15.6 (TURN ARROW)									
Q 1013+19	15.6 (TURN ARROW)									
Q 1013+84	15.6 (TURN ARROW)									
Q 1014+50	15.6 (TURN ARROW)									
Q 1015+30 TO Q 1016+00		151			45			4	4	
RT 1015+30 TO RT 1016+00			70	20						
LT 1015+30 TO LT 1016+00			70	20						
NAZARENE ROAD										
Q 82+36 TO Q 84+56		400								2
RT 82+36 TO RT 84+56			136	142		77	30			
LT 82+36 TO LT 84+56			136							
RURAL TOTALS	842.4	19,741	16,383	4,620	774	781	30	314	323	18

LOCATION	EPOXY PAVEMENT MARKING						RAISED REFLECTIVE PAVEMENT MARKERS			
	LETTERS AND SYMBOLS	YELLOW 4"	WHITE 4"	WHITE 6"	YELLOW 12"	WHITE 12"	WHITE 24"	ONE WAY CRYSTAL EACH	ONE WAY AMBER EACH	TWO WAY AMBER EACH
STATION TO STATION	SQ. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.			
Q 1016+00 TO Q 1024+19		1851						38	36	
RT 1016+00 TO RT 1024+19			771	194						
LT 1016+00 TO LT 1024+19			771	195						
Q 1016+50	31.2 (2WLT)									
Q 1020+73	31.2 (2WLT)									
Q 1023+19	31.2 (2WLT)									
Q 1024+19 TO Q 42+93		4624			95		42	91	80	10
RT 1024+19 TO RT 42+93			1720	595						
LT 1024+19 TO LT 42+93			1555	430						
Q 1024+54	31.2 (2WLT)									
Q 1027+54	31.2 (2WLT)									
Q 1030+54	31.2 (2WLT)									
Q 1033+54	31.2 (2WLT)									
Q 1036+92	31.2 (2WLT)									
Q 1038+09	31.2 (2WLT)									
Q 40+09	15.6 (TURN ARROW)									
Q 40+84	15.6 (TURN ARROW)									
Q 41+56	15.6 (TURN ARROW)									
Q 42+93 TO Q 46+80		1317					50	24	10	8
RT 42+93 TO RT 46+80			97							
LT 42+93 TO LT 46+80			244							
Q 43+11	15.6 (TURN ARROW)									
Q 43+77	15.6 (TURN ARROW)									
Q 44+40	15.6 (TURN ARROW)									
FORD AVENUE										
RT 184+43							30			
RT 185+48 TO LT 185+48			198							
LT 185+55							30			
URBAN TOTALS	374.4	7,792	5,158	1,612	95	0	152	153	126	18
TOTALS	1,216.8	27,533	21,541	6,232	869	781	182	467	449	36
GRAND TOTALS	1,216.8	49,074	6,232	1,650	182		952			

O:\P\ogdev\Projects\74129\CADD FILES ADJUSTED BY D:\Pav_Markingsched.dgn
 mack\lindr\12-1-06

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION PAVEMENT MARKING SCHEDULE DRAWN BY NJV CHECKED BY RMD DATE 3/03
NAME	DATE	
DRM	3/06	