

F.A.P. SHEET NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
774	107 WRS-2, L	EFFINGHAM	127	60
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 74130

### SCHEDULE OF QUANTITIES

ELECTRIC SERVICE INSTALLATION (80400100)

STATION	EACH
56' LT STA. 955+53.55	1

ANCHOR BASE 83052600  
 LIGHT POLE, FIBERGLASS, 45 FT. M.H., TENON MOUNT (8300640)

STATION	EACH
45' LT STA. 955+25.08	1

CONDUIT IN TRENCH, 2" DIA., PVC (81012600)

STATION	STATION	FEET
45' LT STA. 955+25.08	51' LT STA. 955+60.40	33
56' LT STA. 955+53.55	51' LT STA. 955+60.40	4
		37

LIGHT POLE FOUNDATION, 24" DIAMETER (83600200)

STATION	FEET
45' LT STA. 955+25.08	8

TRENCH AND BACKFILL FOR ELECTRICAL WORK (81500200)

STATION	STATION	FEET
45' LT STA. 955+25.08	51' LT STA. 955+60.40	33
56' LT STA. 955+53.55	51' LT STA. 955+60.40	4
		37

BREAKAWAY DEVICE, COUPLING, WITH ALUMINUM SKIRT (83800505)

STATION	EACH
45' LT STA. 955+25.08	4

ELECTRICAL CABLE IN CONDUIT, 600V (XLP - TYPE USE) 1/C #10 (81702110)

STATION	STATION	FEET	SLACK	NO.	FEET
45' LT STA. 955+25.08	51' LT STA. 955+60.40	33	5	3	114

ELECTRICAL CABLE IN CONDUIT, 600V (XLP - TYPE USE) 1/C #6 (81702130)

STATION	STATION	FEET	SLACK	NO.	FEET
56' LT STA. 955+53.55	51' LT STA. 955+60.40	29	6	3	105

LUMINAIRE, SODIUM VAPOR, MULTI MOUNT, 250 WATT (82103900)

STATION	EACH
45' LT STA. 955+25.08	1

LIGHTING CONTROLLER TYPE CB-RCS 60 AMP - 240 VOLT (82500510)

STATION	EACH
51' LT STA. 955+60.40	1

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		NAZARENE ROAD LIGHTING PLANS SHEET 6 OF 6

Rev. 6-1-06

4/19/06