

CONTRACT NO. 74130

LOCATION	EPOXY PAVEMENT MARKING							RAISED REFLECTIVE PAVEMENT MARKERS		
	LETTERS AND SYMBOLS	YELLOW 4"	WHITE 4"	WHITE 6"	YELLOW 12"	WHITE 12"	WHITE 24"	ONE WAY CRYSTAL	ONE WAY AMBER	TWO WAY AMBER
STATION TO STATION	SQ. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	EACH	EACH	EACH
☺ 541+93 TO ☺ 552+14		2660			153			8	31	16
RT 541+93 TO RT 552+14			1257							
LT 541+93 TO LT 552+14			850							
☺ 548+35	15.6 (TURN ARROW)									
☺ 549+00	15.6 (TURN ARROW)									
☺ 549+65	15.6 (TURN ARROW)									
☺ 550+30	15.6 (TURN ARROW)									
☺ 550+97	15.6 (TURN ARROW)									
☺ 552+14 TO ☺ 896+98		6614			899			46	73	16
RT 552+14 TO RT 896+98			2067							
LT 552+14 TO LT 896+98			1951	303						
☺ 555+40	20.8 (ONLY)									
☺ 555+16	15.6 (TURN ARROW)									
☺ 554+38	20.8 (ONLY)									
☺ 554+14	15.6 (TURN ARROW)									
☺ 553+35	20.8 (ONLY)									
☺ 553+11	15.6 (TURN ARROW)									
☺ 893+10	15.6 (TURN ARROW)									
☺ 893+75	15.6 (TURN ARROW)									
☺ 894+40	15.6 (TURN ARROW)									
☺ 895+05	15.6 (TURN ARROW)									
☺ 895+72	15.6 (TURN ARROW)									
☺ 896+98 TO ☺ 914+31		4470						88	68	16
RT 896+98 TO RT 914+31			1711	410						
LT 896+98 TO LT 914+31			1926	420						
☺ 897+16	15.6 (TURN ARROW)									
☺ 897+83	15.6 (TURN ARROW)									
☺ 898+48	15.6 (TURN ARROW)									
☺ 899+13	15.6 (TURN ARROW)									
☺ 899+78	15.6 (TURN ARROW)									
☺ 904+30	31.2 (2WLT)									
☺ 907+30	31.2 (2WLT)									
☺ 910+30	31.2 (2WLT)									
☺ 913+30	31.2 (2WLT)									
☺ 914+31 TO ☺ 941+06		10010			1525			132	130	
RT 914+31 TO RT 941+06			2675	670						
LT 914+31 TO LT 941+06			2570	650						
☺ 914+70	31.2 (2WLT)									
☺ 941+06 TO ☺ 952+00		4391			720			54	54	
RT 941+06 TO RT 952+00			1094	365						
LT 941+06 TO LT 952+00			1094	365						
ROUTE 32										
☺ 49+90 TO ☺ 56+06		1128			225				15	4
RT 49+90 TO RT 56+06			502	189		113	31			
LT 49+90 TO LT 56+06			578	217		99				
LAKE SARA ROAD										
☺ 60+00 TO ☺ 63+79		794			39		12			2
RT 60+00 TO RT 63+79			193	390		178				
☺ 61+92	15.6 (TURN ARROW)									
☺ 62+72	15.6 (TURN ARROW)									
TOTALS	530.4	30067	18468	3979	3561	390	43	328	371	54
GRAND TOTALS	530.4	48535		3979	3951		43		753	

•DGN-SPEC•
•DATE•

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		PAVEMENT MARKING SCHEDULE PAVEMENT MARKING PLAN SHEET 1 OF 5

DRAWN BY NJV
CHECKED BY RMD

DATE 3/03