

CONTRACT NO. 74131

*80% FED. / 20% STATE*

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	
PAY CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	1000-2A	X080-2A
				RURAL	RURAL
20200100	EARTH EXCAVATION	CU YD	5,730	5,730	
20700400	POROUS GRANULAR EMBANKMENT (SPECIAL)	CU YD	53		53
25000210	SEEDING, CLASS 2A	ACRE	1.25	1.25	
25000312	SEEDING, CLASS 4A	ACRE	2.50	2.50	
25000320	SEEDING, CLASS 5	ACRE	2.50	2.50	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	338	338	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	338	338	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	338	338	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	7.5	7.5	
25100120	MULCH, METHOD 2	TON	7.5	7.5	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	380	380	
28000300	TEMPORARY DITCH CHECKS	EACH	6	6	
28000400	PERIMETER EROSION BARRIER	FOOT	1,060	1,060	
28000500	INLET AND PIPE PROTECTION	EACH	1	1	
28100107	STONE RIPRAP, CLASS A4	SQ YD	2223		2223
28200200	FILTER FABRIC	SQ YD	2223		2223
31000300	SUB-BASE GRANULAR MATERIAL, TYPE A 4'	SQ YD	2,744	2,744	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	19	19	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	12	12	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,448	1,448	
40600300	AGGREGATE (PRIME COAT)	TON	10	10	
44000100	PAVEMENT REMOVAL	SQ YD	571	571	
48101600	AGGREGATE SHOULDERS, TYPE B 8'	SQ YD	440	440	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50200100	STRUCTURE EXCAVATION	CU YD	71		71
59100100 60109580	GEOCOMPOSITE WALL DRAIN PIPE UNDERDRAINS FOR STRUCTURES 4"	SQ YD FOOT	31 78		31 78

*80% FED. / 20% STATE*

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	
PAY CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	1000-2A	X080-2A
				RURAL	RURAL
50300225	CONCRETE STRUCTURES	CU YD	37.4		37.4
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	3,101		3,101
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4,546		4,546
50900205	STEEL RAILING, TYPE SI	FOOT	222		222
51201600	FURNISHING STEEL PILES HP 12x53	FOOT	680		680
51202700	DRIVING STEEL PILES	FOOT	680		680
51203600	TEST PILE STEEL HP 12x53	EACH	2		2
51204315	CONCRETE ENCASEMENT	CU YD	31.4		31.4
51500100	NAME PLATES	EACH	1		1
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	287.5	287.5	
* 63000130	STEEL PLATE BEAM GUARD RAIL, TYPE A (SPECIAL)	FOOT	25	25	
* 63100075	TRAFFIC BARRIER TERMINAL, TYPE 5A	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL TYPE I, SPECIAL (TANGENT)	EACH	4	4	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MC	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1	
78200405	GUARDRAIL MARKERS	EACH	8	8	
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
X3550300	BITUMINOUS BASE COURSE SUPERPAVE 6'	SQ YD	2,415	2,415	
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	2	2	
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX 4D, N70	TON	271	271	
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION-LOCATION 1	EACH	1		1
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION-LOCATION 2	EACH	1		1

\*SPECIALTY ITEMS

\* DENOTES SPECIALTY ITEM

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SUMMARY OF QUANTITIES

DRAWN BY ASB  
CHECKED BY SJK  
DATE 8/02