

# SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	B2-BRS-1	ST. CLAIR	39	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN - 90% FEDERAL / 10% STATE					
				I-64 MAINLINE 1000	SILVER CREEK SN 082-0186 SFTY-2A	SILVER CREEK SN 082-0187 SFTY-2A	SILVER CREEK SN 082-0188 SFTY-2A	SILVER CREEK SN 082-0189 SFTY-2A	TR 222 SN 082-0185 SFTY-2A
X0325338	CLASS A PATCHES, TYPE I, 13 INCH	SQ YD	5	5					
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5")	SQ FT	4		1	1	1	1	
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	22		5	13	4		
25000200	SEEDING, CLASS 2	ACRE	0.5	0.5					
28100109	STONE RIPRAP, CLASS A5	SQ YD	1766		582	600	292	292	
28200200	FILTER FABRIC	SQ YD	1766		582	600	292	292	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	83.4	83.4					
40600300	AGGREGATE (PRIME COAT)	TON	400.1	400.1					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	22	22					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600990	TEMPORARY RAMP	SQ YD	423	423					
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	111078	111078					
44213000	PATCHING REINFORCEMENT	SQ YD	240	240					
44213200	SAW CUTS	FOOT	1490	1490					
45200300	JOINT OR CRACK FILLING	POUND	6165	5290	140	290	132	313	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1153	1153					
48202000	BITUMINOUS SHOULDERS SUPERPAVE	TON	9497	9497					
50300225	CONCRETE STRUCTURES	CU YD	0.8		0.2	0.2	0.2	0.2	
50300530	FLOOR DRAIN EXTENSION	EACH	9		1				8
50800105	REINFORCEMENT BARS	POUND	160		40	40	40	40	
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	63	63					
60100072	SHOULDER REMOVAL AND REPLACEMENT 5"	FOOT	30282	30282					
60107600	PIPE UNDERDRAINS 4"	FOOT	29652	29652					
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	1260	1260					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	9	9					
*63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	2650	100	637.5	637.5	637.5	637.5	
*63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2					
*63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	8		2	2	2	2	
*63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	10	2	2	2	2	2	
63200310	GUARDRAIL REMOVAL	FOOT	3274	250	754	741	779	750	

PLOT DATE = 2/28/2006  
 FILE NAME = c:\pwworkspace\edl\0406\plan\p1010406.dgn  
 PLOT SCALE = 49.5993' / IN.  
 REFERENCE = \*REF\*

\*SPECIALTY ITEMS

Rev.